

ADDENDUM NO. 2

To: Prospective Bidders

Contract: Bid Reference Number 2292

General Construction: Contract No. H2456001
Plumbing Construction: Contract No. H2456002
Mechanical Construction: Contract No. H2456003
Electrical Construction: Contract No. H2456004

Project: Oneida County Department of Public Works
Division of Engineering
Cornell Cooperative Extension
Addition & Alterations
121 Second Street, Oriskany, New York 13424

Prepared By: MARCH Associates, Architects & Planners, PC
258 Genesee Street, Suite 300
Utica, NY 13502

Date: April 23, 2025

This addendum is issued indicating changes to the Contract Documents dated March 13, 2025. All changes shall be incorporated in the Contractor's Proposal as described herein, as this addendum will become part of the Contract Documents, if and when an award is made. Acknowledgment of this addendum shall be indicated on the proposal.

The following changes, additions, and deletions shall be incorporated into the Project Manual and Drawings.

REFER TO THE PROJECT MANUAL:

ITEM 1. SECTION 01 51 23, TEMPORARY HEATING, COOLING, AND VENTILATING

- A. Page 01 51 23/1. **ADD** the following sentences to Subparagraph 1.03 A.2: "This includes the tank. The Owner will also schedule all fuel deliveries, in coordination with the mechanical contractor."

ITEM 2. SECTION 07 21 19, FOAMED-IN-PLACE INSULATION

- A. Page 07 21 19/2. **DELETE** Subparagraph 2.01 A.7.a in its entirety and **REPLACE** with the following:
"a. BASF Corporation; WALLTITE Max Series: www.spf.basf.com"

ITEM 3. SECTION 26 67 21-I, ADDRESSABLE FIRE ALARM AND DETECTION SYSTEM

- A. Page 26 67 21-I/1. **DELETE** Paragraph 1.01 A. in its entirety and **REPLACE** with the following:
"A. Furnish and install a non-proprietary fire alarm and detection systems in accordance with the parameters shown on the drawings and herein specified."

REFER TO THE DRAWINGS:

ITEM 1. DRAWING A302, WALL SECTIONS

- A. **ADD** the following note:
"Foundation waterproofing system to be insulated on face of concrete foundation, not on face of insulation as shown."
- B. Refer to Section 2/A302. **DELETE** "Vapor Retarder" **REPLACE** with "Waterproofing System"

ITEM 2. DRAWING E001, SITE PLAN

- A. The existing primary feeder conduit shall remain, remove the primary cables; in lieu of complete removal noted.

ITEM 3. DRAWING P102, FIRST FLOOR PLAN

- A. **DELETE** "4" MIT UP & DN" from chase in WOMEN 124.

ITEM 4. DRAWING P103, ROOF PLAN

- A. **DELETE** "4" MIT DN" from roof plan.

* * * * *