

SPECIFICATIONS
FOR
P.I.N. 2754.83
COUNTY BID NO. 2377
REPLACEMENT OF SIMMONS ROAD CULVERT

ONEIDA COUNTY DEPARTMENT OF PUBLIC WORKS
JEFFREY QUACKENBUSH, ONEIDA COUNTY COMMISSIONER

ONEIDA COUNTY

JULY 2026

PREPARED BY:



**Engineering
Architecture
Landscape Architecture
and Land Surveying, P.C.**

21 Corporate Drive
Clifton Park, NY 12065

TABLE OF CONTENTS

I. GENERAL BID INFORMATION

A. Invitation to Bidders	I-1
B. Instruction to Bidders.....	I-3
1.) General Note	I-3
2.) Definition of Terms.....	I-3
3.) Change of Letting Date.....	I-5
4.) Qualification of Bidders.....	I-6
5.) Delivery of Proposals.....	I-6
6.) Notice of Special Conditions	I-6
7.) Specialty Items.....	I-6
8.) Disqualification of Bidders	I-7
9.) Award and Execution of Contract.....	I-7
10.) Scope of Work	I-8
11.) Control of Work.....	I-9
12.) Control of Materials	I-10
13.) Subcontractors, Materialmen, and Laborers	I-11
14.) Responsibility of Damage Claims	I-11
15.) No Waiver of Legal Rights	I-12
16.) Hold Harmless Clause.....	I-12
17.) Insurance	I-13
18.) Waiver of Subrogation.....	I-16
19.) Prosecution and Progress	I-17
20.) Measure and Payment	I-18

II. SPECIAL NOTES

A. Description of Work	II-1
B. Payment for Required Work.....	II-1
C. Borings and Subsurface Data	II-1
D. Pre-Construction Conference	II-1
E. Power of Attorney.....	II-2
F. Laws and Regulations.....	II-2
G. Non-collusive Bidding Certification	II-2
H. Standard Sheets.....	II-2
I. Specifications: General.....	II-2
J. Survey and Stakeout	II-3
K. Demolition of Existing Culvert Structure.....	II-3
L. NYSDEC Limitations on Work	II-3
M. Special Conditions	II-3
N. Inspection and Testing.....	II-4
O. Payroll Records.....	II-4
P. Permits	II-4
Q. Subcontracts.....	II-4
R. General Notes	II-4

S.	Work Zone Traffic Control.....	II-5
T.	Utilities.....	II-5
U.	Asphalt Prices	II-5
	Special Note – Asphalt Price Adjustment.....	II-6
	Special Note – Fuel Price Adjustment.....	II-8
	Special Note – PG Binder and Mix Design Level	II-10
	Special Note – Right of Way Notes	II-11
	Special Note –Supplemental Information to Bidders	II-12
III. SPECIFICATIONS		
A.	Specifications.....	III-1
B.	Definitions.....	III-1
C.	Special Specifications	III-2
IV. STATE REQUIREMENTS FOR PUBLIC WORK		
A.	Prevailing Wage Schedule	Following IV-1

APPENDICES

Appendix A – Right of Way Information

Appendix B – Permits

Appendix C – Utility Agreements

I. GENERAL BID INFORMATION

The Contractor's attention is specifically called to Section 102-08 of the State of New York Department of Transportation, Office of Engineering, Standard Specifications, Construction and Materials (US Customary), which are current on the date of advertisement for bids.

A. INVITATION TO BIDDERS

Notice is hereby given that Oneida County will accept bids for:

PIN 2754.83, County Bid No. 2377, Simmons Road Culvert Replacement

Contract will be awarded based upon the lowest qualified bid.

The work includes providing all labor, materials, machinery, tools, equipment and other means of construction necessary and incidental to the completion of the work shown on the plans and described in these specifications including, but not necessarily limited to:

This project includes the complete replacement of the existing culvert under Simmons Road and replace with a box culvert. The project will include installation of the precast box culvert and precast wingwalls. In stream work to include a full realignment of the stream in addition to the necessary scour protection at the inlet and outlet of the box culvert.

This is a state funded project and NYSDOT Standard Specifications, officially finalized and adopted on May 1, 2026, as posted on the New York State Department of Transportation's website must be followed by the successful bidder.

The WBE goal for this project is: 15%

The MBE goal for this project is: 8%

The SDVOB goal for this project is: 6%

There are no DBE goals for this project.

The EEO Employment goals for this project are: 2.1% Minority Employment Goal
6.9% Women Employment Goal

The use of the NYSDOT approved civil rights reporting software, Equitable Business Opportunities (EBO), is required. Access authorization to EBO can be found at <https://ebo.dot.ny.gov/>.

To obtain copies of the Contract Documents and become a Registered Plan Holder, bid documents will only be obtained from the Oneida County Purchasing Office, 800 Park Avenue, Utica, NY 13501, (315)798-5880, between the hours of 8:30 am and 4:30 pm. A refundable deposit of \$100.00 will be required to obtain the bid documents. Contractors that obtain the Contract Documents from a source other than the issuing office must notify the issuing office in order to be placed on the official Registered Plan Holders list to receive Addenda and any other Bid correspondence. Bids received from Contractors other than those on the official Registered Plan Holders list will not be accepted. Contract Documents will be available starting on July 15, 2026.

No questions or inquiries regarding this bid will be accepted within three (3) business days prior to the bid opening date. The last date for submitting questions will be Friday, July 31, 2026.

Questions regarding the Contract Documents should be directed to MJ's Engineer Contact through email at deckert@mjteam.com. Bidders shall promptly notify MJ of any errors, omissions, conflicts, or ambiguity within the Contract Documents within three (3) business days of bid opening.

All bids must include the complete Bid Form. This is a unit price bid as described in the Instructions to Bidders. Each bidder must deposit with their bid, a bid security in the amount of not less than five percent (5%) of their bid, in the form and subject to the conditions provided in the Information to Bidders.

Simultaneously with their executed contract, the successful bidder must deliver to Oneida County an executed performance and completion bond in a form meeting the County's approval, in an amount not less than 100% of the accepted bid as security for the faithful performance and completion of this contract, and also a separate bond guaranteeing prompt payment of monies due to all persons supplying the contractors or subcontractors with labor and materials employed and used in carrying out the contract, and having as surety on the bonds such surety companies as are approved or acceptable to Oneida County.

The successful low bidder will have ten (10) calendar days to provide their complete MBE/DBE/SDVOB Participation package in accordance with §102-12.G.2 of the New York State Department of Transportation Standard Specifications. The time period is measured starting the day after the Letting. If the last day is a Saturday, Sunday, State holiday, or Federal holiday, the period is extended to the next day that State offices are open.

Oneida County, through the County's Department of Public Works Office, reserves the right to reject any or all bids. All work shall be subject to equal opportunity in employment, State wage rates and all other requirements in accordance with applicable law.

No bidder may withdraw their bid within forty-five (45) days after the actual date of opening thereof. The attention of the bidder is particularly called to the requirements as to conditions of employment to be observed and minimum wages to be paid, in addition there are M/WBE and SDVOB goals for this project.

Bids to be considered must be received in a sealed envelope at the Oneida County Purchasing Office, 800 Park Avenue Utica, NY 13501 by **10:30 AM, local time, on Wednesday August 5, 2026**, at which time they will be publicly opened and read aloud. Bids received after the above noted time will not be accepted.

Owner's Contact

Jeff Dora

Assistant Engineer
County of Oneida Department of
Public Works
(315) 793-6200

Engineer's Contact

Daniel Eckert, P.E.

Project Manager
MJ Engineering, Architecture, Landscape
Architecture, and Land Surveying, P.C.
(518) 371-0799

jdora@oneidacountyny.govdeckert@mjteam.com

B. INSTRUCTION TO BIDDERS

1. General Note

In general, the New York State Department of Transportation Office of Engineering *Standard Specifications, Construction and Materials* of the NYSDOT specifications, and all addenda in effect on the date of advertising for bids shall apply, except where modified in these specifications. The Contractor should note that the Project Plans are dimensioned in English units only, and that all Payment Items will be measured and paid in Standard English units. Further direction is provided under SPECIAL NOTES. Where reference is made to New York State Department of Transportation, Commissioner, etc., the appropriate Oneida County official shall be substituted.

Except as modified herein, the latest edition of the Standard Specifications, Construction and Materials (Section 100 and Section 200-700) issued by the New York State Department of Transportation, Office of Engineering, including all revisions and addenda issued by NYSDOT prior to the date the Notice to bidders is advertised, hereinafter referred to as the NYSDOT Standard Specifications, shall govern the work to be done where referred to on the plans and in these specifications. If a conflict exists between the NYSDOT Standard Specifications and these Contract Documents, the Contract Documents shall govern.

For Convict Labor, see Section 102-10 in the latest edition of the Standard Specifications issued by NYSDOT. For changed Conditions & Dispute Provisions, see Sections 104, 105 and 108. For Buy America, see Section 106-11.

Except as otherwise described in the Contract Documents, neither the State of New York nor the NYSDOT are parties to this agreement.

Oneida County or its authorized representative shall make the final interpretations of any irregularities, ambiguities or questions arising out of these specifications and the New York State Department of Transportation *Standard Specifications, Construction and Materials* used on this project.

Under this contract the newest New York State Department of Transportation Office of Engineering *Standard Specifications, Construction and Materials* and addenda are amended as follows:

References to the County's representative and County personnel shall hereinafter be made as the "Engineer".

2. Definition of Terms

The Definitions and Terms under Section 101-02 of the NYSDOT Standard Specifications are hereby modified.

- 2.1 Chief Engineer. Delete the stated definition. This term where used in the specifications or contract documents shall mean "Oneida County " or their authorized representative.
- 2.2 Commissioner. Delete the stated definition. This term where used in the specifications or contract documents shall mean "Oneida County ".
- 2.3 Comptroller. Delete the stated definition. This term where used in the specifications or contract documents shall mean "Oneida County ".
- 2.4 Department. Delete the stated definition. This term where used in the specifications or contract documents shall mean "Oneida County " and may also be used to mean the "Oneida County " or their authorized representative.
- 2.5 Departmental Geotechnical Engineer. Delete the stated definition. The "Oneida County " authorized representative shall be responsible and is in charge of all engineering and construction work on this contract.
- 2.6 Departmental Engineering Geologist. Delete the stated definition and substitute the same definition as above for Note 2.5.
- 2.7 Engineer or Engineer-In-Charge. Delete the words "Department of Transportation" and substitute "Oneida County ". Also delete the words "Regional Director" and substitute "Oneida County Engineer".
- 2.8 Final Agreement. Delete "State of New York, Department of Transportation" and substitute "Oneida County ".
- 2.9 Inspector. Delete "The Department of Transportation" and substitute "The authorized representative of "Oneida County ".
- 2.10 Materials Bureau. Delete the word "Bureau" and the stated definition and substitute "Oneida County has the responsibility in the quality assurance for materials to be used on the contract".
- 2.11 Regional Director. Delete the stated definition and substitute: "When used, means the Oneida County Engineer".
- 2.12. State. Delete the stated definition and substitute: "When used, means Oneida County ".

Under Section 102 - Bidding Requirements and Conditions

- 2.13 Subsection 102-01, Location of Regional Offices. Delete entire subsection -- not applicable.
- 2.14 Subsection 102-07, Bid Deposit. Delete the words "State of New York, Department of Transportation" and substitute "Oneida County Purchasing Department, Oneida County ".

Under subsequent sections of this document:

- 2.15 The term "**Owner**" means **Oneida County** .
- 2.16 The term "**Engineer**" means **MJ Engineering, Architecture, Landscape Architecture, and Land Surveying, P.C.** and or any duly authorized representative of these firms.
- 2.17 The term "Bidder" shall mean any party or parties submitting in proper form a Proposal to perform the work specified hereinafter.
- 2.18 The term "Contractor" shall mean the successful Bidder selected by the Owner to contract to perform the work - or their heirs, executors, successors, administrators or assigns.
- 2.19 The term "Work" is used to designate the work, equipment, materials and things required to be done, furnished or performed by the Contractor under the Specifications attached hereafter.
- 2.20 Where the NYSDOT is mentioned in any capacity (including, but not limited to, Department, State, Commissioner of Transportation, DOT, DCES or Directors(s) of its subdivisions) as an approving authority with regard to materials, fabrication or other approvals, the approving authority shall be changed to the Owner. This change shall be made in all of the documents relating to this contract.
- 2.21 Specific modifications to technical aspects of the NYSDOT Standard Specifications are noted on the contract plans, special specifications, and/or in the Special Notes.
- 2.22 In the Materials subheadings of the Technical Specifications of the contract documents and the latest edition of the NYSDOT Standard Specifications, the following shall apply:
- Any references to materials testing by the Department or its representative shall be interpreted to mean by the Contractor, the Owner or its representative, as referenced in Section 106-02 – Quality Requirements. This interpretation also applies to any testing or sampling to be obtained in the presence of a Department representative.
- 2.23 Any reference to NYSDOT Standard Specifications is limited in scope to technical engineering and construction work, materials, details, procedures, etc. All references to the State or the NYSDOT or administrative officers or employees thereof are null and void with respect to legal or contractual responsibilities.
- 2.24 The terms Engineer and Owner shall have their respective meanings as defined in Article 1 of the General Conditions.

3. **Change of Letting Date**

If the County or their Engineer determine that the advertisement period must be extended, notice of the new letting date shall be provided to prospective bidders at least three (3) days prior to the original scheduled letting date.

4. Qualification of Bidders

The apparent low bidder will be required to submit an itemized financial statement covering the previous twelve (12) calendar months of actual operations within five (5) working days of bid opening. The statement shall include financial resources, liabilities, equipment, and experience of such a nature as to be acceptable to the Owner. Experience on projects of a similar nature may be taken into consideration in determining the lowest responsible bidder.

The apparent low bidder shall complete and submit the "Statement of Qualifications and Experience contained within the financial statement.

The Owner reserves the right to reject any bid if the evidence submitted by, or investigation of, such bidder fails to satisfy the Owner that such bidder is properly qualified to carry out the obligations of the contract and to complete the work contemplated therein. Conditional bids will not be accepted.

5. Delivery of Proposals

Each proposal must be submitted in triplicate in a sealed envelope clearly marked "**BID FOR PIN 2754.83, County Bid No. 2377, SIMMONS ROAD CULVERT REPLACEMENT**". Sealed proposals must be delivered to the Oneida County Purchasing Department on or before the date, time and location specified herein. No responsibility shall be attached to the County or their representatives for the premature opening of any proposal not properly labeled. Bidders assume all responsibilities of risks associated with mail or courier delivery. When sent by mail, the sealed proposal must be addressed to the County at the address and in care of the official in whose office the bids are to be received. All proposals shall be filed prior to the time and at the place specified in the "Invitation to Bidders". Proposals received after the time for opening of bids will be returned to the bidder unopened.

6. Notice of Special Conditions

The Contractor's attention is particularly called to those parts of the contract documents and specifications that deal with the following:

- A. Insurance requirements included in Section I.17 and Section II.D.
- B. NYS Department of Transportation Special Conditions included in Chapter III - Special Notes.
- C. Various Revised and Special Specifications included in Chapter IV.
- D. Prevailing wage rates required by N.Y.S. Labor Law included in Chapter V.
- E. Environmental Regulation Standard Clauses and Permits, Chapter III (P).
- F. Required Contract Provisions, Federal Aid Construction Contracts, Chapter VI.

7. Specialty Items

This contract does contain items that shall be considered "Specialty Items" as per RDI 14-11. Those Items include:

Not Applicable

8. Disqualification of Bidders

Any one or more of the following may be considered as sufficient cause for the disqualification of a bidder and the rejection of their proposal.

- (a) More than one proposal for the same work from an individual, firm or corporation under the same or different names.
- (b) Evidence of collusion among bidders. Participants in such collusion will receive no recognition as bidders for any future work of the County until any such participant shall have been reinstated as a qualified bidder.
- (c) Lack of competency and adequate machinery, plant and other equipment, as revealed by the financial statements and experience questionnaire.
- (d) Unsatisfactory performance record as shown by past work for any County judged from the standpoint of work quality and progress.
- (e) Uncompleted work, which in the judgment of the County, might hinder or prevent the prompt completion of this work if awarded.
- (f) Failure to pay, or satisfactorily settle, all bills due for labor and materials on former contracts in force at the time of letting.
- (g) Failure to comply with any qualification regulations of the County.

9. Award and Execution of Contract

9.1 Consideration of Proposals

After the proposals are opened and read, they will be compared on the basis of the summation of the unit prices shown in the bid schedule. In the event of a discrepancy between the sum of the unit prices and the gross sum bid, the sum of the unit prices shall govern.

The right is reserved to reject any or all proposals, to waive technicalities, to advertise for new proposals, or to proceed to do the work otherwise, if in the judgment of the County Engineer the best interests of the County will be promoted thereby.

9.2 Cancellation of Award

The County reserves the right to cancel the award of any Contract at any time before the execution of the said Contract by all parties without any liability against the County.

9.3 Return of Proposal Guaranty

All proposal guaranties, except those of the **three** lowest bidders, will be returned immediately following the opening and checking of the proposals. That of the successful bidder will be returned after a satisfactory bond has been furnished and the Contract has been executed. The remaining two guaranties will be returned within ten (10) days following the award of the Contract.

9.4 Bonds

The successful bidder shall, prior to the execution of the Contract, furnish a performance bond and a payment bond each in an amount equal to the full amount of the Contract. The purpose of said bonds is to assure the faithful performance of this Contract as well as the payment of all persons performing labor and furnishing materials in connection with this Contract. The form of the bonds and the security shall be acceptable to the County.

Negotiable securities, satisfactory to the County, in an amount equal to that specified for the Contract bond, may be deposited with the County in lieu of such Contract bond and shall be subject to all the conditions of such bond and to such agreements as may be required by the County.

9.5 Failure to Execute Contract

Failure of the Contractor to execute the Contract within ten (10) days after he has received the Contract form shall be just cause for the annulment of the award, and for the forfeiture of the proposal guaranty. The proposal guaranty shall become the property of the County, not as a penalty, but in liquidation of damages sustained. Award may then be made to the next lowest responsible bidder or the work may be re-advertised and constructed under a new Contract or otherwise as the County may decide.

10. Scope of Work

10.1 Responsibility of the Contractor

The Contractor will be held responsible for the execution of a satisfactory and complete piece of work, in accordance with the true intent of the drawings and specifications. The Contractor shall provide, without extra charge, all incidental items required as a part of the work including layout and survey, even though not particularly specified or indicated. If there is good reason for objecting to the use of any material, appliance, or method of construction as shown or specified, the Contractor shall report such objections to the Engineer, and if approved by the Engineer, shall obtain proper adjustment before the Contract is made, and then shall proceed with the work with the understanding that a satisfactory job will be required. The Contractor is solely responsible for site safety and adherence to OSHA regulations.

General Scope of Work - Contractor:

- On-site maintenance and protection of traffic during construction
- Survey and layout of items in Contract
- Removal of existing pipe
- Install precast box culvert
- Install precast wingwalls
- Install scour protection
- Mill and pave approaches
- Install guide rail at the approaches
- Restoration of disturbed banks
- Restore traffic to normal operating patterns

11. Control of Work

11.1 Authority of Engineer

An Engineer provided by the County, who will observe the work done under the Contract during construction, will represent the County Engineer. The Engineer shall inspect work performed, review materials to be used, and to stop and reject work and materials found to be not in accordance with the plans and specifications. The Engineer's authority shall cover all phases of the work. In the event that questions should arise concerning the interpretation or changes of plans and specifications or to the acceptability of the work, the Contractor shall submit any questions, in writing, to the Engineer. These questions shall be forwarded to the County along with the Engineer's recommendations.

The Engineer may place on the job other personnel who shall observe the work as direct representatives. Their authority shall consist of observing the work under the Contract, rejecting any defective material used and temporarily suspending any work improperly performed. They will not have any authority to make changes or alterations in the plans and specifications, nor be permitted to act as foremen for the Contractor.

Any work done or materials used without scheduling the observation by the Engineer or an authorized representative may be ordered removed and replaced at the Contractor's expense.

11.2 Final Acceptance of Work

When, in the opinion of the Engineer, the Contractor has fully performed the work under the Contract, the Engineer shall recommend to the County and the NYSDOT Regional Local Project Liaison the acceptance of the work so completed. If the County Engineer accepts the recommendation of the Engineer, they notify the Contractor by letter of such acceptance, and copies of such acceptance shall be sent to other interested parties.

11.3 Contractor's Personnel

The Contractor shall place in charge of the work a competent and reliable English speaking Superintendent, who shall have the authority to act for the Contractor and who shall be acceptable to the Engineer. This Superintendent must be present at all times during the working day to receive directions and orders given by the Engineer or designated representatives. All workers must have sufficient skill and experience to properly perform the work assigned to them. Any person employed by the Contractor who the Engineer may deem incompetent or unfit to perform the work shall at once be discharged and shall not again be employed on projects for the County at that specific task.

11.4 Cooperation with Utilities

It shall be the Contractor's duty to notify all utility companies, all pipe line, or other parties affected within a time frame as not to affect the schedule prior to all necessary adjustment of the public or private utility fixtures, pipe lines, and other appurtenances within or adjacent to the limits of construction. The Contractor shall notify the Engineer in writing describing the need for and extent of utility adjustments and the anticipated schedule. The Contractor shall be responsible for UFPO notifications and to maintain current UFPO clearances.

Known utilities include, and may not be limited to:

TDS Telecom – Overhead Telecommunication
Verizon – Overhead Telecommunication

It is understood and agreed upon that the Contractor has considered in the bid all of the permanent and temporary utility appurtenances in their present or relocated positions as shown on the plans and that no additional compensation will be allowed for any delays, inconveniences, or damage sustained due to any interference from the said utility appurtenances or the operation of moving them by the utility. The Contractor will be responsible for any fees required by the utility for temporary locations. Any damage resulting to any utility (buried, aerial, etc.) by the Contractor, personnel, subcontractor or any other person within the confines of the site (500 feet beyond each end of the project) shall be the responsibility of the Contractor.

11.5 Guarantee

The Contractor shall provide to Oneida County any manufacturer's warranties and guarantees normally given as customary trade practice.

12. Control of Materials

12.1 Certificate of Acceptability

The Contractor, at no expense to the Owner, shall supply all certificates of acceptability of materials required by the specifications. The County shall have the right to approve of the laboratories or fabricators, which will issue the certificates.

The Contractor shall obtain materials to be incorporated into the work from NYSDOT approved sources. The Contractor shall obtain and submit Manufacturer's Material Certification to the Engineer for each such material, as specified in Section 106-04 – Material Acceptance Records, indicating that the respective item meets the applicable NYSDOT or Special Specification included in this contract.

The cost of the inspection by the County's Representative of any unapproved plants shall be borne by the Contractor. This shall include, but not be limited to, plants employed to provide mobile concrete, structural steel and steel reinforcement.

The inspections and certifications for any steel or precast concrete items are to be in compliance with all the requirements of the contract plans, specifications and the Steel / Precast Concrete Construction Manuals. Particular items of importance to be checked for each unit fabricated are:

- All dimensions
- All testing of materials as defined in Chapter IV

13. Subcontractors, Materialmen, And Laborers

The Contractor shall furnish the Engineer, before final payment is authorized, an affidavit that all labor and material associated with the work in any way is paid for in full. The Contractor shall indemnify and hold the County and the Engineer harmless from any lien or claim which may be made or filed after such payment by any subcontractor, materialman or laborer in connection with work performed hereunder.

14. Responsibility of Damage Claims

The Contractor shall defend, indemnify and save harmless Oneida County, and NYSDOT, their officers, and employees and The Engineer, from all suits, actions, or claims of any character brought because of any injuries or damage received or sustained by any person, persons, or property on account of the operations of the said Contractor; or on account of or in consequence of any neglect in safeguarding the work; or through use of unacceptable materials in constructing the work; or because of any act or omission, neglect, or misconduct of said Contractor; or because of any claims or amounts recovered from any infringements of patent, trademark, or copyright; or from any claims on amounts arising or recovered under the Workers Compensation Act, or any other law, ordinance, order, or decree; and so much of the money due the said Contractor under and by virtue of this Contract as shall be considered necessary by the County, for such purpose, may be retained for the use of the County; or, in case no money is due, the surety may be held until such suit or suits, action or actions, claim or claims for injuries or damages as aforesaid shall have been settled and suitable evidence to that effect furnished to the County; except that money due the Contractor will not be withheld when the Contractor produces satisfactory evidence that the Contractor is adequately protected by public liability and property damage insurance.

The Contractor agrees to make no claim for damages for delay in the performance of this contract occasioned by any act, or omission to act, of the Owner or the Engineer, or any of its representatives, and the Contractor agrees that any such claim shall be fully compensated for by an extension of time to complete the performance of work as provided herein.

15. No Waiver of Legal Rights

In the event that the County does not strictly enforce the terms and conditions of the Agreement, such non-enforcement shall not act as or be deemed to act as a waiver or modification of this Agreement, nor shall such non-enforcement prevent the County from enforcing each and every term of this Agreement thereafter.

The County shall not be precluded or stopped by a measurement, estimate or certificate made either before or after the completion and acceptance of the work and payment therefore, from showing the true amount and character of the work performed and materials furnished by the Contractor, nor from showing that any such measurement, from recovering from the Contractor or their sureties, or both, such damage as it may sustain by reason of the Contractor's failure to comply with the terms of the Contract. Neither the acceptance by the County, or any representative of the County, shall operate as a waiver of any portion of the Contract or of any power herein reserved, or of any right to damages. A waiver of any breach of the Contract shall not be held to be a waiver of any other or subsequent breach.

16. Hold Harmless Clause

TO THE FULLEST EXTENT PERMITTED BY LAW, CONTRACTOR AND ANY SUBCONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE OWNER, ITS LEGISLATORS, REPRESENTATIVES, AGENTS AND EMPLOYEES FROM AND AGAINST ANY AND ALL CLAIMS, SUITS, LIENS, JUDGMENTS, DAMAGES, LOSSES AND EXPENSES, INCLUDING LEGAL FEES AND ALL COURT COSTS AND LIABILITY (INCLUDING STATUTORY LIABILITY) ARISING IN WHOLE OR IN PART AND IN ANY MANNER FROM INJURY AND/OR DEATH OF ANY PERSON OR DAMAGE TO OR LOSS OF ANY PROPERTY IN CONNECTION WITH THE PERFORMANCE OF ANY WORK OR ANY OTHER ACT OR OMISSION BY OR FOR CONTRACTOR OR SUBCONTRACTOR, PURSUANT TO ANY CONTRACT PURCHASE ORDER AND/OR RELATED PROCEED ORDER. FOR ANY SUCH CLAIMS, SUITS, LIENS, JUDGMENTS, DAMAGES, LOSSES AND EXPENSES CONTRACTOR AND ANY SUBCONTRACTOR SHALL DEFEND AND BEAR ALL COSTS OF DEFENDING ANY ACTIONS OR PROCEEDINGS BROUGHT AGAINST THE CONTRACTOR OR SUBCONTRACTOR AND/OR OWNER, ITS LEGISLATORS, REPRESENTATIVES, AGENTS AND EMPLOYEES, ARISING IN WHOLE OR IN PART OUT OF ANY SUCH ACTS, OMISSION, BREACH OR DEFAULT. THE FOREGOING INDEMNITY SHALL INCLUDE INJURY OR DEATH OF ANY EMPLOYEE OF THE CONTRACTOR OR SUBCONTRACTOR AND SHALL NOT BE LIMITED IN ANY WAY BY AN AMOUNT OR TYPE OF DAMAGE, COMPENSATION OR BENEFITS PAYABLE UNDER ANY APPLICABLE WORKERS COMPENSATION, DISABILITY BENEFITS OR OTHER SIMILAR EMPLOYEES BENEFIT ACT. THE CONTRACTOR AND SUBCONTRACTOR HEREBY EXPRESSLY PERMITS THE GENERAL CONTRACTOR TO PURSUE AND ASSERT CLAIMS AGAINST THE SUBCONTRACTOR FOR INDEMNITY, CONTRIBUTION AND COMMON LAW NEGLIGENCE ARISING OUT OF CLAIMS FOR DAMAGES FOR DEATH AND PERSONAL INJURY.

17. **Insurance**

Prior to any work being performed, certificates of insurance (IIA/ACORD form) must, in the required form and amount, be properly executed by an authorized representative of the insurance underwriter (A.M. Best Rated 'A' or 'A+'). The Contractor, at their own expense, shall procure and maintain until one year after date of the Notice of Certificate of Substantial Completion or one year after the Contractor or any Subcontractor last performs any work under the Contract if the Project is abandoned or deferred, insurance for liability for damages required by law of the kinds and in the amounts stated herein and as may be modified by provisions in the Supplementary Conditions, through insurance companies authorized to operate in New York State. The insurance shall cover all operations necessary to complete the work, whether performed by the Contractor or Subcontractors. Before starting work, the Contractor shall furnish the County five certificates of insurance for each and every type of insurance required. The certificates shall be in form and content satisfactory to the County, shall show compliance by the Contractor with the provisions herein contained, and shall provide that the policies shall not be cancelled or altered until after 30 days written notice to the County. Property damage insurance shall in all cases include coverage for XCU hazards (explosion, collapse, and underground operations).

All liability insurance required by this Contract shall be maintained in force during the term of this Contract and until one year after the date of the Notice of Substantial Completion or one year after the Contractor or any Subcontractor last performs any work under the Contract if the Project is abandoned or deferred.

The kinds and amounts of insurance required are:

a.) **Commercial General Liability Insurance:**

Unless specifically required otherwise elsewhere in the Contract Documents, commercial general liability insurance policies shall be provided in amounts not less than:

Personal Injury Liability:	\$1,000,000	Each Occurrence
Bodily Injury and Property	\$1,000,000	Each Occurrence
Damage Liability:	\$2,000,000	General Aggregate
	\$2,000,000	Products Aggregate

Note: Oneida County, State of New York/New York State Department of Transportation, and MJ Engineering, Architecture, Landscape Architecture, and Land Surveying, P.C. shall be added to the General Liability policy as "Additional Insured."

The aggregate must be applicable on a per project basis.

A Certificate of Insurance must be furnished reflecting the inclusion of the interest of the County, its Legislators, representatives, agents and employees, and naming each as an Additional Insured on a primary basis. Endorsement or policy shall waive subrogation rights. Coverage is to be endorsed to reflect that insurance is primary and

non-contributory with respect to any other collectable insurance, for the County and all other parties required to be named as additional insureds.

This policy shall cover all damages arising during the policy period, and shall include but not be limited to:

- 1.) Contractor's Liability Insurance issued to and covering the liability for damages imposed by law upon the Contractor with respect to all work performed by him under the Contract.
 - 2.) Contractor's Liability Insurance issued to and covering the liability for damages imposed by law upon each Subcontractor with respect to all work performed by him under the Contract.
 - 3.) Contractor's Protective Liability Insurance issued to and covering the liability for damages imposed by law upon the Contractor with respect to all work under the Contract performed for the Contractor by Subcontractors.
 - 4.) Completed Operations Liability Insurance issued to and covering the liability for damages imposed by law upon the Contractor and each Subcontractor arising during the period between the date of the Notice of Certificate of Substantial Completion and one year thereafter.
 - 5.) Product Liability Insurance issued to and covering the liability for damages imposed by law upon the Contractor arising, after physical possession of the products has been relinquished, out of the Contractor's products or reliance upon a representation or warranty with respect thereto.
 - 6.) Contractual Liability Insurance issued to and covering the liability for damages imposed by law upon the Contractor, assumed under this Contract.
 - 7.) Contractual Liability Insurance issued to and covering the liability imposed by the Contract upon the County and the Engineer for work performed on private lands with respect to the work of the Contract by the Contractor or their Subcontractors.
- b.) Automobile Liability Insurance covering all claims against the Contractor, Subcontractors, Engineer and the County as the result of work under the Contract. The limit for this coverage shall be \$1,000,000 per occurrence.
- c.) Umbrella Liability Insurance coverage shall be provided for a limit of at least \$5,000,000 per occurrence/aggregate in excess of primary insurance and shall cover over the areas of Commercial General Liability, Contractual Liability and Automobile Liability coverage.
- d.) Worker's Compensation Insurance:

A policy covering the Contractor's obligations in compliance with the Worker's Compensation Law (Chapter 41 of the Laws of 1914, as amended) covering all operations of

the work, whether performed by the Contractor or by Subcontractors. This Contract shall be null and void, and of no effect unless the Contractor provides during the life of the Contract compensation coverage for the benefit of their employees, and those of their Subcontractors, in compliance with the Worker's Compensation Law (State Finance Law, Section 142). The Contractor shall require each Subcontractor to also comply with these requirements, unless the Subcontractor's employees are adequately covered by the Contractor's policy. If any employees are not covered by the Worker's Compensation Law due to being engaged in a hazardous type of work, the Contractor shall provide adequate Employer's General Liability Insurance for their protection. **This coverage must include coverage of sole proprietors and officers of corporations who will be performing work on the job.**

PROOF OF WORKER'S COMPENSATION INSURANCE MUST BE PROVIDED ON THE FOLLOWING FORMS ONLY:

- a) if coverage is obtained from an insurance carrier, on forms C-105.2 (9-07) OR U-26.3
- b) if contractor/vendor is self-insured or participates in an authorized group self-insurance plan, on forms SI-12 OR GSI-105.2

Please note that ACORD forms are NOT acceptable proof of New York State Worker's Compensation insurance.

If contractor/vendor is legally exempt from obtaining worker's compensation insurance, proof of such exemption MUST BE PROVIDED on the following form:

- a) CE-200 12/2008, Certificate of Attestation of Exemption from New York State Workers' Compensation and/or Disability Benefits Insurance Coverage.
- e.) New York State Disability Benefits:

Contractor shall maintain coverage as required by law for disability benefits.

PROOF OF DISABILITY COVERAGE MUST BE PROVIDED ON THE FOLLOWING FORMS ONLY:

- a) if coverage is obtained from an insurance carrier, on forms DB-120.1 OR DB-820/829
- b) if contractor/vendor is self-insured, on form DB-155

Please note that ACORD forms are NOT acceptable proof of New York State disability insurance.

If contractor/vendor is legally exempt from obtaining disability benefits coverage, proof of such exemption MUST BE PROVIDED on one of the following forms:

- a) CE-200 12/2008, Certificate of Attestation of Exemption from New York State Workers' Compensation and/or Disability Benefits Insurance Coverage.

- f.) County's Protective Liability Insurance issued in the name of the County, with MJ Engineering, Architecture, Landscape Architecture, and Land Surveying, PC and the State of New York/New York State Department of Transportation listed as Additional Insured, covering the liability for damages imposed by law upon the County and the Engineer with respect to all operations under the Contract by the Contractor or their Subcontractors, including supervisory acts and omissions of the County.

The limit for this coverage shall be \$1,000,000 per occurrence and aggregate.

- g.) Property Insurance – Fire & Extended Coverage (Builders Risk/Installation Floater)

The Contractor shall provide and maintain, at their own expense, a standard Property Insurance – Fire & Extended policy including special peril and theft to insure all work of the Contract against any loss or damage. The value of the insurance shall at all times be equal to or greater than the full value of the work (on-site & off-site), shall be in the names of the County and the Contractor, payable to the County, and any proceeds thereof shall be retained by the County as security for the performance by the Contractor in making good any loss, damage or injury. Upon such satisfactory performance by the Contractor, the proceeds shall be paid by the County to the Contractor.

- h.) Maintenance of Insurance: The above insurances shall each contain the following wording: County is interested in the maintenance of this insurance and it is agreed that this insurance will not be canceled, materially changed or not renewed without at least a thirty (30) day advance written notice to the County by certified mail – return receipt requested.
- i.) The Term "Contractor": The term "Contractor" as used in these insurance requirements shall mean and include Subcontractors of every tier.
- j.) Liability Insurance Time Frame: All liability insurance required by this contract shall be maintained in force during the term of this contract and until one year after the date of the Notice of Substantial Completion or one year after the contractor or **any Subcontractor last performs any work under the contract if the project is abandoned or deferred.**

18. Waiver of Subrogation

The Contractor and Subcontractor(s) waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents and employees, each of the other, and (2) the County, the Architect/Engineer, the Architect/Engineer's consultants, separate contractors, and any of their subcontractors, sub-subcontractors, agents and employees for damages caused by fire or other causes of loss to the insurance applicable to the work, except such rights as they may have to proceeds of such insurance held by the County as fiduciary. The contractor/subcontractor shall require of their sub-subcontractors, agents and employees, by appropriate agreements, written where legally required for validity, similar waivers in favor of the parties enumerated herein. All policies required under this contract shall provide

such waivers of subrogation by endorsement or otherwise. A waiver of subrogation shall be effective as to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the insurance premium directly or indirectly, and whether or not the person or entity had an insurable interest in the property damaged. The County does not waive any rights of subrogation it may have.

19. Prosecution and Progress

19.1 Notice to Proceed

The "Notice to Proceed" will stipulate the date on which it is expected the Contractor will begin the work. Commencement of work by the Contractor shall be deemed and taken as a waiver of this notice on their part. In no case, however, shall the Contractor begin work prior to the date of the signing of the Contract.

19.2 Prosecution of Work

The Contractor shall start construction operations on the part of the project approved by the Engineer or set forth in the approved Progress Schedule. The work shall be conducted in such manner and with sufficient materials, equipment, and labor as are considered necessary to ensure its completion in accordance with the plans and specifications as interpreted by the Engineer, by the date set forth in the Agreement. Should the prosecution of the work for any reason be discontinued, the Contractor shall notify the Engineer at least 24 hours in advance of resuming operations.

19.3 Temporary Suspension of Work

The Engineer shall have the authority to suspend the work wholly or in part by written order for such period as he may deem necessary due to unsuitable weather, to conditions considered unfavorable for the suitable prosecution of the work, or to carry out orders given or to perform any provisions of the Contract.

19.4 Date of Completion of Contract Work

The Contractor shall perform fully, entirely, and in a satisfactory and acceptable manner the work contracted, by the date stipulated in the Agreement. In adjusting the Agreement date for the completion of the project, all strikes, lock-outs, unusual delays in transportation, or any condition over which the Contractor has no control, and also any suspensions ordered by the Engineer for causes not the fault of the Contractor, shall be excluded from the computation of the contract time for completion of the work. No allowance will be made for delays or suspensions of the prosecution of the work due to the fault of the Contractor.

19.5 Termination of Contract

If the Contractor is adjudged bankrupt or makes an assignment for the benefit of creditors or a receiver is appointed for the Contractor or any insolvency arrangement proceedings are instituted by or against him, or if the Contractor fails after seven (7) days' notice to supply enough properly skilled workers or proper materials or fails to prosecute the work with such diligence as will insure its completion by the Agreement date or shall in any other respect commit a breach of their Agreement and fail to remedy the same within seven (7) days after notice thereof, the County may, by twenty-four (24) hours written notice, terminate the Contractor's right to proceed with the balance of the work or with any portion thereof and may take possession of the work and complete it by Contract or otherwise. The County may utilize such materials, plant and equipment as may be on the site of the work.

19.6 Failure to Complete Work on Time

When the work embraced in the Contract is not completed on or before the date specified therein, engineering and inspection expenses incurred by the County upon the work from the completion date originally fixed in the Agreement to the final date of completion of the work may be charged to the Contractor and be deducted by the County from any payment due the Contractor. Consideration of any extra work or supplemental Contract work added to the original Contract as well as extenuating circumstances beyond the control of the Contractor, will be given due consideration by the County before assessing engineering and inspection charges against the Contractor. The Contractor will be responsible for any delays resulting from causes within the Contractor's control, including inefficient operations, and the County shall be the sole judge of whether such charges shall be assessed against the Contractor.

The beginning and ending dates of the allowable period of construction will be stipulated in the New York State Department of Environmental Conservation (NYSDEC) and/or Army Corps of Engineers wetland permits. If work is performed outside the stipulated period of time, the Contractor will be subject to pay any fines resulting from violation of the permits.

19.7 Assignment

The Contract shall be binding upon the parties hereto and upon their respective successors and assigns; but neither party hereto shall assign or transfer any interest herein, without the written consent of the other.

20. Measurement and Payment

20.1 Payments on Contract

Payments to the Contractor for work satisfactorily completed will be made monthly in full for the work completed. No monthly payment will be rendered for less than 10% of the Contract amount or \$1,000, whichever is less. The payments will be based on the completed percentage of each unit bid as shown in the Itemized schedule.

The attention of persons intending to make proposals is specifically called to the provisions of Section 70 and 71 of the Lien Law, and Section 1302-C of the Penal Law in relation to funds being received by a Contractor for a public improvement. These provisions declare that the funds received by the Contractor shall constitute trust funds in the hands of such Contractor to be applied first to the payment of certain claims.

No certificate approving or authorizing the first partial payment, or in the event taxes shall be found due in accordance with this Section after the first payment to the Contractor, then no certificates approving or authorizing any final payment shall be made to a foreign Contractor unless such Contractor furnishes satisfactory proof that all taxes due by such Contractor under the provisions of Articles 9, 9A, 16, and 16A of the Tax Law have been paid. The certificate of the State Tax Commission to the effect that all such taxes have been paid shall be conclusive proof of the payment of such taxes.

The term "Foreign Contractor" as used in the preceding paragraph means in the case of an individual, a person who is a legal resident of another state or foreign country; and in the case of a firm or co-partnership, one having one or more partners who is a legal resident of another State or foreign country and in the case of a corporation, one having its principal place of business in another State or foreign country.

20.2 Differing Site Conditions

The Contractor shall promptly, and before the conditions are disturbed, give a written notice to the Engineer of (1) subsurface or latent physical conditions at the site which differ materially from those indicated in this contract, or (2) unknown physical conditions at the site of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the contract.

The Engineer shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the Contractor's cost of, or the time required for, performing any part of the work under this contract, whether or not changed as a result of the conditions, then an equitable adjustment shall be made under this clause and the contract modified in writing accordingly. The Contractor shall not have rights to suspend work during resolution of a differing site condition as stipulated in Section 105-14 of the Standard Specifications.

GENERAL REQUIREMENTS

No request by the Contractor for an equitable adjustment to the contract under this clause shall be allowed, unless the Contractor has given the written notice required; provided, that the time prescribed above for giving written notice may be extended by the Engineer.

II. SPECIAL NOTES

A. DESCRIPTION OF WORK

The project includes the removal of the existing culvert, installation of a new precast box culvert and full depth reconstruction of Simmons Road. The work breakdown is as follows:

The portion of work which will be the responsibility of the Contractor is generally described as:

1. On-site maintenance and protection of traffic during construction
2. Survey and layout of items in Contract
3. Removal of existing pipe
4. Install precast box culvert
5. Install scour protection
6. Install steel superstructure.
7. Mill and pave approaches
8. Install guide rail at the approaches
9. Restoration of disturbed banks
10. Restore traffic to normal operating patterns

In general, the Contractor shall perform or provide all items necessary to complete the described work to the lines indicated on the drawings or noted in these specifications.

B. PAYMENT FOR REQUIRED WORK

The Contractor shall be advised that the Owner shall pay the Contractor for work performed in accordance with these Contract Documents, based on the quantity of each item of work completed. The Specification section of these Contract Documents details the applicable item numbers from the New York State Standard Specifications; however the Contractor shall be aware that the Contract Drawings and Specifications contained herein may contain modifications which he is responsible for in the performance of the Contract.

C. BORINGS AND SUBSURFACE DATA

Two (2) test borings were drilled for subsurface exploration of this location, one (1) on the northeast side of the existing culvert and one (1) on the southwest side of the existing culvert. The existing soils at this site consisted of fill type soils of sandy silty clay atop a thick layer of silty, clayey sand, which is perched on top of a layer of shale.

Geotechnical Report and boring logs are available upon request.

D. PRE-CONSTRUCTION CONFERENCE

A pre-construction conference will be held prior to the issuance of the Notice to Proceed for the Contract, and prior to commencement of construction, at the Oneida County Department of Public Works Building. The Contractor shall have an authorized representative of his firm

present at the meeting.

E. POWER OF ATTORNEY

Attorneys-in-fact who sign Bid Bonds or Contract Bonds must file with each bond a certified and effectively dated copy of their power of attorney.

F. LAWS AND REGULATIONS

The Bidder's attention is directed to the fact that all applicable Federal and State Laws, municipal ordinances and the rules and regulations of all authorities having jurisdiction over the construction of the Project shall apply to the Contract throughout, and they will be deemed to be included in the Contract the same as though herein written out in full.

G. NON-COLLUSIVE BIDDING CERTIFICATION

A Non-Collusive Bidding Certification form as bound in these documents must be executed and accompany the Bid. Refer to Section II of this Project Manual.

H. STANDARD SHEETS

Where applicable, all New York State Department of Transportation Standard Sheets are to be incorporated as part of the Contract Documents. The details may not apply directly to the work to be performed by the Contractor but shall be reviewed for any effects they may have upon this work.

I. SPECIFICATIONS: GENERAL

With the exception of the items listed under "SPECIAL SPECIFICATIONS" all work items shall be in accordance with the requirements of the "STANDARD SPECIFICATIONS - CONSTRUCTION AND MATERIALS" of the New York State Department of Transportation in effect on date of advertising for bids, including any addenda. All applicable paragraphs pertaining to the referenced items shall apply.

The "Basis of Payment" will be used to compute the "Progress Payment" for the work in progress. The total of the progress payments shall not exceed the total sum bid price for the project without the written authorization of Oneida County or their Engineer.

Any reference to New York State Department of Transportation or personnel of the Department of Transportation shall refer to Oneida County

Any reference to sections or sub-sections given in the "SPECIAL SPECIFICATIONS" refers to the "STANDARD SPECIFICATIONS - CONSTRUCTION AND MATERIALS" of the New York State Department of Transportation in effect on date of advertising for bids and any Addenda.

Any reference to the AASHTO Design Specifications contained in the "SPECIAL SPECIFICATIONS" refers to the "AASHTO LRFD Bridge Design Specifications" by the

American Association of State Highway and Transportation officials as modified by the New York State Department of Transportation.

In addition, the applicable requirements of Section 700 - Material Details of the "STANDARD SPECIFICATIONS - CONSTRUCTION AND MATERIALS" as noted within the text of the "SPECIAL SPECIFICATIONS" shall apply.

J. SURVEY AND STAKEOUT

The Contractor is responsible for all survey and stakeout for the work. The Contractor shall establish sufficient survey control points based on the survey control as shown on the Contract Plans. Cost of all survey work required to complete the work shall be included in the unit price bid for the survey and stakeout.

The Contractor will be required to set or reset, location or relocate by field survey, and record the establishment or reestablishment of all survey baseline points, permanent survey markers, Right of Way Markers and property line evidence as well as centerline of improvement points as directed by the Resident Engineer, all as required in Section 625 of the Standard Specifications.

K. DEMOLITION OF EXISTING CULVERT STRUCTURE

The Contractor and any Subcontractors shall demolish any structure in accordance with the requirements of Section 202 of the "STANDARD SPECIFICATIONS - CONSTRUCTION AND MATERIALS" of the New York State Department of Transportation in effect on date of advertising for bids, including any addenda.

The Contractor's attention is directed to the requirements of subsection 202-3.01 General and Safety Requirements. A removal plan, signed by a licensed and registered professional engineer in the state of New York, shall be submitted to the Engineer thirty (30) days prior to beginning the demolition.

L. NYSDEC LIMITATIONS ON WORK

No instream between October 1 and May 15 to avoid suspension of sediment during the trout spawning and incubation period.

M. SPECIAL CONDITIONS

1. The Contractor shall maintain at all times a safe and adequate ingress and egress to and from all residences and private and public places of business for both vehicular and pedestrian traffic.
2. Disposal of all materials shall be in accordance with all current Federal, State and local laws, rules and regulations, and any provisions found elsewhere in the Contract Documents. There shall be no on-site disposal throughout the duration of this contract, and the County is not able to provide a disposal site.

N. INSPECTION AND TESTING

It is the intent of the specifications that materials of construction shall be obtained from approved sources of the NYSDOT.

Tests made by the NYSDOT are acceptable to the Owner. This shall in no way preclude the Owner from requiring retesting or additional tests if in the opinion of the Engineer it is in the best interests of the County to do so.

Unless otherwise noted in the Plans or Specifications, the results of all such required inspections, tests, analyses, etc., shall be expeditiously furnished in duplicate to the Engineer.

O. PAYROLL RECORDS

The Contractor and any Subcontractors shall submit weekly to the Engineer, payroll records which shall cover all days from the commencement of construction to the date of completion.

P. PERMITS

A NYSDEC Article 15 and Article 24 and a Section 404 USACE Nationwide Permit #3 (NWP#3) have been obtained for this project to permit the proposed wetland disturbances.

Refer to Appendix B for the permit(s).

Q. SUBCONTRACTS

The 50% limit of subcontracts value shall be strictly enforced. Any Contractor exceeding this limit without written approval from the Owner shall be considered in violation of this Contract. This contract does not contain any items designated as Specialty Items as noted in this proposal in Chapter 1.B.7.

R. GENERAL NOTES

1. Material and Construction Specifications: Standard Specifications, Construction and Materials, New York State Department of Transportation, Office of Engineering, in effect on date of advertising for bids, with current additions and modifications.
 - a. The cost of furnishing, installing, maintaining, removing and disposing of all platforms and other protective devices shall be included in the price bid for appropriate items of the Contract.
 - b. Vehicles belonging to the Contractor or his workmen shall not be parked on the pavement or shoulders along a roadway being used by the public except where parking is normally permitted. The Contractor shall not park his equipment overnight where it is deemed a safety hazard.
 - c. The Contractor shall perform all work with care so that any materials which are to remain in place, or which are to remain the property of Oneida County will not be

damaged. If the Contractor damages any materials which are to remain in place, or which are to remain the property of the County, the damaged materials shall be repaired or replaced, in a manner satisfactory to the Engineer, at the expense of the Contractor.

- d. The Contractor shall field measure and verify all dimensions prior to commencing any work.
- e. During the course of construction, the Contractor shall conduct his operations in such a manner to prevent or reduce to a minimum any damage to adjacent streams from pollution by debris or from the manipulation of equipment and/or materials in or near the stream. He shall not return directly to the stream, any water which has been used for wash purposes or other similar operations which cause the water to become polluted with sand, silt, cement, oil or other impurities.

S. WORK ZONE TRAFFIC CONTROL

The Contractor will be responsible for providing all barricades and advance warning signs at the site as shown in the Contract Plans. The Contractor will also be responsible for the maintenance of all signs during construction. Maintenance shall include the replacement of any damaged signs. All barricades and signs shall be in conformance with the "Standard Specifications" and the "Manual of Uniform Traffic Control Devices".

The contractor is responsible for maintaining all safety barriers, temporary retaining walls, and proper signage throughout the duration of the project.

T. UTILITIES

The existing pole #69 is owned by TDS Telecom, located on the eastern side of Simmons Road and within the proposed excavation area, will be replaced with a 35-foot pole by TDS Telecom. TDS Telecom will relocate all existing lines to the new pole, and the overhead lines will be shielded during construction. The following are names and numbers that should be used to coordinate the movements:

- TDS Telecom – Duane Krzyzanowski – duane.krzyzanowski@tdstelecom.com – (315) 404-6501
- Charter – Dustin Anderson – dustin.anderson@charter.com – (315) 534-6899

U. ASPHALT PRICES

The Contractor shall employ an approved commercial bituminous concrete plant supplier and purchase asphalt materials used in the project. Refer to asphalt price adjustment information on the following page.

SPECIAL NOTE**ASPHALT PRICE ADJUSTMENT**

The PGB Index Price, which shall apply to this contract, shall be \$_____ per ton.

ASPHALT PRICE ADJUSTMENT¹ CONVERSION FACTORS

MATERIAL DESCRIPTION	CONVERSION FACTOR	ITEM NUMBER²
Bituminous Stabilized Course	0.065 t PGB/yd ³	302.01
Asphalt Treated Permeable Base Type 2	0.035 t PGB/t	404.028X
Shim Course	0.0825 t PGB/t	404.0589
6.3 Top Course	0.067 t PGB/t	404.068X
9.5 Top Course, T&L, Shoulder Course	0.062 t PGB/t	404.09XX, 404.01X9, 404.XX89
12.5 Top Course, T&L, Shoulder Course	0.055 t PGB/t	404.12XX, 404.01X9, 404.XX89
19 Binder Course	0.049 t PGB/t	404.19XX
25 Binder Course	0.045 t PGB/t	404.25XX
37.5 Base Course	0.040 t PGB/t	404.37XX
Paved Placed Surface Treatment, Types A, B, and C	0.064 t PGB/t	415.0X0F0118
Micro-Surfacing, Quick-Set Slurry	0.078 t PGB/t	413.0X0F0118, 414.0X0F0118
Straight Tack Coat	0.0026 t PGB/gal	407.0103
Asphaltic Sealants (ASTM 6690)	0.0027 t PGB/gal	402.75XXXX18, 402.76XX018
Chip Seal	0.0027 t PGB/gal	410.X0
Asphalt Emulsion for Cold Recycling	0.0027 t PGB/gal	416.02XX00RR, 416.20XX00RR, 416.2X, 416.21XX00RR
Fog Seal and Dilute Tack Coat	0.0016 t PGB/gal	407.0102, 407.01XXXXRR, 410.40, 416.30, 416.040000RR, 416.300000RR
PG Binder for Cold Recycling	0.0043 t PGB/gal	416.030000RR, 416.22000018
Asphaltic Sealant – Clean & Seal	0.225 t PGB/LNMI	412.76XX0001
Asphaltic Sealant – Treating Cracks	0.240 t PGB/LNMI	412.76040001
Asphaltic Sealant – Rout & Seal	0.00005 t PGB/LF 0.270 t PGB/LNMI	412.760100RR, 412.760300RR
Repair of Pavement, Temporary Asphalt	See Note 4	633.140X, 633.15, 633.16, 619.05XX
True and Leveling, Asphalt Sidewalks, Driveways, Bike Paths, Gutters	See Note 5	404.01X9, 608.020102, 624.02XXXX

Notes:

1. In accordance with Standard Specification §698-3.01, the index value for the asphalt price adjustment is the average posted price of Performance Graded Binder (PGB) for the month of bid letting.
2. Item Number - This is the contract pay item number under which these materials are most frequently paid. Unless indicated otherwise, materials similar to those indicated under the column entitled "Material Description" are also eligible for adjustment using the factor listed for a similar material with the same pay units regardless of the actual contract pay item number.
3. Quality Adjustment Items (404/608/624) are not eligible for asphalt price adjustment.
4. Asphalt Price Adjustment Conversion Factor based on units of TONS of asphalt placed, not the pay units of this item. The conversion factor for Pavement Repair and Temporary Asphalt will be based on the actual asphalt mixture used.
5. The conversion factor for Truing and Leveling, Driveways, and other items that allow asphalt mix options, will be based on the actual mixtures used.
6. A two digit suffix (RR) at the end of a contract pay item indicates a special specification.
7. The conversion factors for asphalt mixed with slag shall be increased by 25%.
8. t = tons

SPECIAL NOTE**FUEL PRICE ADJUSTMENT**

The Fuel Index Price, which shall apply to this contract, shall be \$____per gallon. The table below lists eligible items used in computing the Fuel Price Adjustment.

MATERIAL DESCRIPTION	CONVERSION FACTOR	ITEM NUMBER²
Unclassified Excavation	0.35 gal/yd ³	203.02
Embankment	0.10 gal/yd ³	203.03, 620.XX
Fill	0.45 gal/yd ³	203.05, 203.06, 203.07, 203.08XX, 203.20, 203.21, 203.25
Controlled Low Strength Material	1.00 gal/yd ³	204.01, 204.02, 204.03, 204.04
Structure/Trench/Culvert Excavation	0.50 gal/yd ³	206.01, 206.0201
Bituminous Stabilized Course	1.40 gal/yd ³	302.01, 307.01
Subbase Course	1.00 gal/yd ³	304 Items
Asphalt Mixtures	2.50 gal/ton	404 Items ³ , 405.01, 608.020102 ³ , 619.0601 ⁴ , 624.02XXXX ^{3,4} , 633.14 ^{3,4} , 633.15 ^{3,4} , 633.16 ^{3,4}
Milling	0.10 gal/yd ²	490 Items
Portland Cement Concrete Pavement	1.00 gal/yd ³	502 Items ³ , 503.1010, 503.1011, 503.1012
Fill Type Retaining Walls	0.45 gal/yd ³	554.30XX ⁵ , 554.31 ⁵ , 554.4X ⁵
Footing Concrete & Concrete for Structures – All classes	1.00 gal/yd ³	555 Items, 582.05
Approach Slabs	0.33 gal/yd ²	557.2001, 557.2002, 557.2003, 557.2009, 557.22
Structural Slabs with bottom formwork	0.25 gal/yd ²	557.01XX, 557.07, 557.30, 557.41XX
Structural Slabs-no bottom formwork	0.15 gal/yd ²	557.05XX, 557.09, 557.43XX
Class D and Overlay Concrete	0.05 gal/yd ²	557.13, 584 Items
Concrete Barrier, Type A	0.16 gal/ft	606.3001, 606.3021, 606.3031
Concrete Barrier, Type B	0.19 gal/ft	569.01, 606.3002, 606.3022, 606.3032
Concrete Barrier, Type C	0.22 gal/ft	606.3003, 606.3023, 606.3033
Concrete Barrier, Half Section	0.11 gal/ft	569.02, 606.3004, 606.3024, 606.3034
Concrete Median Barrier, Single Slope	0.23 gal/ft	569.05, 606.3041, 606.3043, 606.3044
Concrete Median Barrier Wide, Single Slope	0.28 gal/ft	606.3051, 606.3053, 606.3054
Concrete Barrier Half Single Slope	0.17 gal/ft	569.04, 606.3061, 606.3063, 606.3064
Vertical Faced Concrete Parapet	0.10 gal/ft	569.03
Gravel, Stone, Slag	1.00 gal/yd ³	411.01, 411.02, 411.03, 623.1X
Concrete Sidewalks and Driveways	1.00 gal/yd ³	608.01XX
Topsoil	0.45 gal/yd ³	610.10, 610.11XX, 610.14XX
Turf Establishment – Performance	0.05 gal/yd ²	610.1605

Notes:

1. In accordance with Standard Specification §698-3.02, the index value for the fuel price adjustment is the posted price for the month of bid letting.
2. Item Number - This is the contract pay item number under which these materials are most frequently paid. Unless indicated otherwise, materials similar to those indicated under the column entitled "Material Description" are also eligible for adjustment using the factor listed for a similar material with the same pay units regardless of the actual contract pay item number.
3. Quality Adjustment Items (404/502/608/624) are not eligible for fuel price adjustment.
4. Fuel Price Adjustment Conversion Factor based on units of TONS of asphalt placed, not the pay units of this item.
5. Fuel Price Adjustment Conversion Factor based on units of CY of backfill paid under this item, not the pay units of this item.

SPECIAL NOTE PG BINDER AND MIX DESIGN LEVEL

Requirements of this note apply to all Section 404 Asphalt items in this contract.

PG BINDER

Use a **PG 64S-22** (Standard) meeting the requirements of AASHTO M 332, *Standard Specification for Performance Graded Asphalt Binder using Multiple Stress Creep Recovery (MSCR)*, for the production of asphalt mixtures for this project. Terminal Blend Crumb Rubber modifier may be used for this PG binder.

When terminal blend CRM PG binder is used, the following shall apply:

- Crumb rubber particles shall be finer than #30 sieve size.
- The CRM PG binder shall be storage-stable and homogeneous.
- The Dynamic Shear Rheometer (DSR) shall be set at 2-mm gap.
- The CRM PG binder shall be 99% free of particles retained on the 600 µm sieve as tested in accordance with Section 5.4 of M 332.

Use of polyphosphoric acid (PPA) to modify the PG binder properties is prohibited for asphalt mixtures under this contract. This prohibition also applies to the use of PPA as a cross-linking agent for polymer modification.

MIX DESIGN

The mixture designs must be developed in accordance with the criteria specified in the items that are appropriate for the Mixture Design Level of 50 gyrations.

Note: The PG binder for this project may be modified with CRM additives to meet the requirements stated above. Handling of the asphalt shall be discussed at pre-construction and pre-paving meetings.

**SPECIAL NOTE
RIGHT OF WAY NOTES**

1. All work to be performed under this contract will be within the public Right-of-Way (ROW) in accordance with Section 105-15 of the Standard Specifications. The Contractor is to assure himself that all work is being performed within the ROW, including but not limited to vehicle access; storage of equipment, materials, debris, and waste; landscaping; vegetation removal and management; grading, seeding and the installation of turf; and the installation of any fences or protective barrier.
2. If the Contractor is unable to identify the limits of the ROW when the contract calls for work in those vicinities, the Contractor must contact the Engineer for definitive boundary determinations before any work may be initiated at those locations (Standard Specifications Sections 105-10 and 625).
3. In accordance with Section 105-15 of the Standard Specifications, releases for any non-essential contract work outside of the existing ROW, including plantings, landscaping or driveway enhancement, will be obtained by the Contractor. the Contractor shall not invade upon private properties, lands, or buildings outside of the ROW for any reason without first securing written permission from the property owner (Standard Specifications Sections 105-15).
4. The Contractor will be held liable for any damages done. Any such injuries or damages shall be satisfactorily repaired, or items placed at the contractor's expense (Standard Specifications Section 107-08).

SPECIAL NOTE SUPPLEMENTAL INFORMATION TO BIDDERS

The information checked in the "Digital" column on this form is available at the offices having jurisdiction for this project, as identified in the advertisement for bids. The information checked in the "Inspection Only" column on this form is available at the offices having jurisdiction for this project, as identified in the advertisement for bids, for inspection and review prior to the letting date. The bidder's signature on this proposal certifies that they have made themselves aware of the availability of the information indicated below:

THERE IS NO SUPPLEMENTAL INFORMATION AVAILABLE FOR THIS CONTRACT: ☐

INFORMATION	Digital ¹	Inspection Only
1. Grayscale PDF of Sealed Plan Set (for printing) ^{2,4}	☒	
2. Unsealed Layered or 3D PDF Files	☐	
3. CADD Information		
a. MicroStation DGN	☐	
b. InRoads DTM and XML format	☐	
c. InRoads ALG and XML format	☐	
4. Cross Sections in ADOBE PDF format	☐	
5. Quantity Work-ups ³	☐	
6. Record Plans	☐	☐
7. Rock Cores (available for inspection only)		☐
8. Sign Face Layouts in ADOBE PDF format	☐	
9. Stormwater Pollution Prevention Plan (SWPPP)	☐	☐
10. Subsurface Information		
a. Subsurface Exploration Logs	☒	☐
b. Undisturbed Sample Logs	☐	☐
c. Laboratory Test Data from Soil Samples	☒	☐
d. Tabulated Results of Probing	☒	☐
e. Tabulated Depth to Bedrock	☐	☐
f. Rock Core Evaluation Logs	☐	☐
g. Compression Test Data from Rock Samples	☐	☐
h. Rock Outcrop Maps	☐	☐
i. Granular Materials Resource Survey Reports	☐	☐
j. Terrain Reconnaissance Reports	☐	☐
11. Subsurface Information - Other Information		
a. Subsurface information from outside sources	☒	☐
b. Source Information - Granular Material and aggregates	☐	☐
c. Special Subsurface Reports	☐	☐
12. Anticipated Construction Schedule	☐	☐
13. Asbestos Information		
a. Asbestos Blanket Variances	☐	☐
b. Asbestos Report	☐	☐
14. Special Reports or Other Information:		
a. Permits	☒	☐
b. Design Approval Document	☐	☒
c. Survey Control Report	☐	☒
d. Wetland Compensation Report	☐	☒

¹ – All digital material is provided in ADOBE (PDF) format, unless noted above.

² – Required for all projects that have 11"x17" plan sets. See HDM Section 21.3.9.2

³ – Required for all projects.

⁴ – Grayscale PDF's of sealed plans must be provided at PS&E submittal. An updated version must be provided whenever the plans are modified or amended.

III. SPECIFICATIONS

A. SPECIFICATIONS

The State of New York Department of Transportation Office of Engineering *Standard Specifications, Construction and Materials* in effect on the date of advertising for bids, including any addenda to date, are hereby incorporated, in their entirety, and made a composite part of these specifications except as herewith modified and supplemented by these specifications and subsequent documents issued by Oneida County.

The Specifications, Plans and Contract Documents of Oneida County shall govern over those of other agencies but where the method of work and requirements of materials are not included in the Contract Documents of the County of Oneida, the State of New York Department of Transportation *Standard Specifications, Construction and Materials* of January 1, 2026 shall govern.

The Contractor should note that the Project Plans are dimensioned in English units only, and that all Payment Items will be measured and paid in Standard English units.

The Engineer for Oneida County or their authorized representative shall make the final interpretations of any irregularities, ambiguities or questions arising out of these specifications and the New York State Department of Transportation *Standard Specifications, Construction and Materials* used on this project. References to the County's representative and personnel shall hereinafter be made as the "Engineer".

B. DEFINITIONS

Refer to Chapter I. B.2 for Definitions and terms.

Whenever the words directed, required, permitted, ordered, instructed, designated, considered necessary, or where the words of like import are used, it shall be understood that the direction, requirement, permission, order, instruction, designation or prescription of the Engineer is intended; and similarly, the words approved, acceptable, satisfactory, or words of like import shall mean approved by or acceptable or satisfactory to the Engineer, unless another meaning is plainly intended. Whenever, in the description of any part of the Work to be done under this Contract, the expression as shown, on the plans or the words of like import are used, it shall be understood to mean as shown on the Contract Drawings, unless another meaning is plainly intended.

C. SPECIAL SPECIFICATIONS

The following Special Specifications contained in Part II of these Technical Specifications are included in this project:

203.24010017	Shoulder Backup Material
595.50000018	Sheet-Applied Waterproofing Membrane
603.64140715	Precast Concrete Box Culvert (Fill Height 24 in. or Greater) 14 Foot Span, 7 Foot Rise
603.67000001	Precast Concrete Wingwall Units for Box Culverts
607.41010010	Temporary Plastic Barrier Fence
613.04000001	Stockpiling and Placing Existing Stream Bed Materials
627.50140008	Cutting Pavement

ITEM 203.24010017 - SHOULDER BACKUP MATERIAL

DESCRIPTION:

This work shall consist of furnishing, placing, grading, compacting, and trimming shoulder backup material of the type indicated adjacent to shoulders to the lines, grades, and locations indicated in the contract documents or to the lines, grades, and locations directed by the Engineer, in accordance with these specifications and details shown in the plans.

MATERIALS:

General. Except as indicated below, §304-2 shall apply. Where the term “subbase course” is used in that subsection, “shoulder backup material” shall replace it.

Material incorporated into the work need not be stockpiled. The State may test for plasticity, soundness, and gradation at its discretion, or may decide not to test for these properties. Materials incorporated into the work shall consist of uncontaminated materials, free of glass, conforming with these specifications, the contract documents, and the directions of the Engineer.

Unless indicated otherwise in the contract documents, the Contractor may choose the type or types of material to use from the list of types given below. Intermixing of the permitted types, however, will be subject to the approval of the Engineer.

Material that proves to be, or that is determined by the Engineer to be impractical to place, grade, trim or compact as shown in the contract documents or as directed by the Engineer shall not be used.

Type A (Crusher-run, crushed gravel, or crushed stone.) Shoulder backup material of this type shall consist of well graded crusher-run material from a stone quarry or gravel source, or crushed Portland cement concrete. The material shall contain no organic, deleterious, hazardous or toxic material. Gradation shall be subject to the approval of the Engineer, but no material larger than 1 inch in greatest dimension will be allowed. Materials shall not show losses greater than 20% after four cycles of the Magnesium Sulfate Soundness test.

Type B (Subbase Course, Type 2.) Shoulder backup material of this type shall meet the material requirements of Subbase Course, Type 2. The Regional Geotechnical Engineer will examine each proposed source of material for compliance with these specification requirements, and submit an evaluation of the material including any limiting conditions to the Engineer.

Type C (Subbase Course, Type 4.) Shoulder backup material of this type shall meet the material requirements of Subbase Course, Type 4 of the Standard Specifications, except the material furnished shall consist of sand and gravel or a blend of sand and gravel and stone. The Regional Geotechnical Engineer will examine each proposed source of material for compliance with these specification requirements, and submit an evaluation of the material including any limiting conditions to the Engineer.

Type D (Recycled Asphalt Concrete.) Material provided under this option shall consist of uncontaminated recycled asphalt concrete pavement produced on the contract or from other sources as approved by the Engineer. Recycled asphalt concrete pavement shall be substantially free of pieces larger than 1.5 inches.

Type E (Select Structural or Granular Fill.) Material provided under this option shall consist of material conforming to the soundness, gradation, and pH requirements for Select Structural Fill or Select Granular Fill, except top size shall not exceed that for Type C.

ITEM 203.24010017 - SHOULDER BACKUP MATERIAL

CONSTRUCTION DETAILS:

The material shall be placed on the grade in a manner to minimize segregation using equipment and procedures approved by the Engineer. Uncontrolled spreading from piles dumped on the grade resulting

in segregation will not be permitted. Maximum loose lift thickness prior to compaction shall be 6 inches. The contractor's compaction methods and equipment shall be approved by the Engineer. After compaction, the finished surface of the compacted material at the shoulder edge shall not extend above the edge of the shoulder nor be more than 0.4 inches below the shoulder. Tolerance elsewhere shall be 1½ inch, except the surface shall be graded to drain at every location.

If the final grade of the material is not in reasonable close conformity to the lines and grades indicated in the contract documents, or to those directed by the Engineer, the material shall be trimmed to achieve reasonably close conformance. Additional material shall be brought in to fill deficiencies, and excess material (trimmings) shall be removed. Trimmings may be incorporated into the shoulder backup work at other locations along the project if such opportunities exist and provided gradation of the resulting material remains in conformance with the gradation requirement for the selected option. When it is not possible to incorporate the trimmings in the shoulder backup work the trimmings shall be disposed of or used elsewhere in the contract in a manner approved by the Engineer.

METHOD OF MEASUREMENT:

Shoulder Backup Material will be measured for payment as the number of tons evidenced by delivery tickets, properly placed, graded, compacted, and trimmed along the edge of shoulder in accordance with these specifications and the directions of the Engineer.

When truck scales are not available within reasonable distance of the source of the material, as determined by the Engineer, the quantity paid for will be determined using conversion factors and the loose volume of shoulder backup material determined by measuring the dump truck bodies. The Contractor shall select the trucks to be used for delivery of the material with the approval of the Engineer. Once the trucks are selected and approved by the Engineer, no other trucks shall be used for delivery of this material. The trucks shall be uniformly loaded to the satisfaction of the Engineer.

Additional material brought in as part of the trimming operation to fill deficiencies will be measured for payment. The quantity of trimmings removed from the shoulder backup operation and not incorporated into the shoulder backup work elsewhere, however, will not be measured for payment under this pay item, and the Engineer will make an appropriate adjustment to the measured quantity.

Unless other conversion factors are indicated in the Contract Documents, the conversion factor will be 0.05tons per cubic foot, loose measure.

BASIS OF PAYMENT:

The unit price bid per ton for Shoulder Backup Material shall include the cost of all labor, materials, and equipment necessary to satisfactorily furnish, place, grade, compact, and trim Shoulder Backup Material.

ITEM 595.50000018 – SHEET-APPLIED WATERPROOFING MEMBRANE

DESCRIPTION

Furnish and install a manually or machine-applied sheet waterproofing membrane in accordance with the contract documents. Include all surface preparation.

MATERIALS

Use a sheet-applied waterproofing membrane meeting the requirements of §717-02.

CONSTRUCTION DETAILS

General - On new structural concrete, the provisions of §557-3.11, Curing, shall be met prior to membrane system placement. Work will not be done during wet-weather conditions. No work will be done when the concrete structural slab surface temperature is below 50°F, or ambient temperatures are below 50°F. The concrete structural slab shall be surface dry at the time of application of the membrane. The Engineer will verify that atmospheric conditions are favorable for placement of the system based on the manufacturer's recommendations.

Arrange for the membrane manufacturer to have a competent technical representative at the job site during all phases of preparation and installation.

Supply Material Safety Data Sheets (MSDS) and approved Material Detail Sheets prepared by the membrane manufacturer to the Engineer a minimum of two (2) weeks prior to the scheduled commencement of work. The Material Detail Sheets will contain all material requirements and installation information for each specific waterproofing membrane. The Material Detail Sheets will be accessible at the Department's Approved List website for reference.

(Bridge Decks) – Begin work no less than (7) calendar days after placement of Portland cement concrete, Portland cement mortar, or epoxy mortar for structural concrete repair. The Engineer may waive the seven-day requirement if the areas of repair can sustain loads without damage or deformation. Subject to the concurrence of the Engineer, if an alternate concrete repair material is used, follow the manufacturer's instructions for allowable loading.

(Culverts) - Fill the joints between precast culvert sections flush to the culvert slab and sidewall surfaces with a grout conforming to §701-08 Vertical and Overhead Patching Material. In areas where the joints do not line up evenly, taper the grout with a maximum slope of 2:1, from the high side of the joint to the low side, to provide a smooth transition from one unit to the next.

Place the waterproofing membrane over the joints of precast or cast-in-place units following the guidelines of Chapter 19 of the Highway Design Manual, or as indicated on the contract plans and Material Detail Sheets.

1. On vertical surfaces, the waterproofing membrane will be covered with material conforming to §705-07 Premoulded Resilient Joint Filler.
2. On horizontal surfaces.

ITEM 595.50000018 – SHEET-APPLIED WATERPROOFING MEMBRANE

Membrane Protection (Culverts) – To protect the waterproofing membrane from punctures, the following procedures will be used:

- a. If select granular fill is specified over the culvert, a 6 inch thick protective layer of concrete sand, meeting the requirements of §703-07 Concrete Sand, will be placed on the membrane.

Or

- b. If asphalt pavement using aggregate larger than 3/8 inch is specified directly above the membrane, or if clearances don't allow for 6 inches of concrete sand, a 1 inch thick (minimum) course of HMA with a maximum nominal aggregate size of 3/8 inch will be placed on top of the membrane. The hot mix asphalt will be thoroughly compacted with mechanical tampers.

METHOD OF MEASUREMENT

This work will be measured as the number of square feet of sheet-applied, waterproofing membrane satisfactorily installed (measured to the nearest 1 sq ft.). No separate measurement of the vertical faces of curbs, joints, concrete barriers, headers, scuppers, or for the inside surfaces of subdrainage outlets, shall be made. No deductions will be made for holes less than 1 square foot in area.

BASIS OF PAYMENT

The unit price bid per square foot for this item shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work.

No additional payments will be made for any re-priming done in conformance with the requirements of the manufacturer's detail sheets.

ITEM 603.63XXYY15 PRECAST CONCRETE BOX CULVERT (Fill Height Less than 2' – 0")

ITEM 603.64XXYY15 PRECAST CONCRETE BOX CULVERT (Fill Height 2' – 0" or Greater)

ITEM 603.65XXYY15 PRECAST CONCRETE BOX CULVERT (Bridge Size, Fill Height Less than 2' – 0")

ITEM 603.66XXYY15 PRECAST CONCRETE BOX CULVERT (Bridge Size, Fill Height 2' – 0" or Greater)

DESCRIPTION

This work shall consist of furnishing and placing single or multi-cell precast reinforced concrete box culvert sections of the type indicated in the plans in accordance with these specifications in the locations indicated and in a manner approved by the Engineer.

MATERIALS

Precast concrete box culvert shall meet the requirements of Section 706-17 Precast Concrete Box Culverts.

CONSTRUCTION DETAILS

- A. Inspection, Storage and Handling** – Precast box sections will be inspected at the construction site to determine any damage during shipment and for conformance to the dimensional tolerances. An additional inspection will be made prior to placement of precast box sections to determine any damage during storage.
- B. Installation**
 - 1. Excavation.** The requirements specified in Section 206 Trench, Culvert and Structure Excavation, that apply to culverts and storm drains shall govern, except as modified in the plans.
 - 2. Placement.** The precast manufacturer shall have a representative available to assist in the installation of the box culvert. Precast box sections shall be installed, true to line and grade, in accordance with the contract plans. Placement of the box sections shall start at the downstream end and proceed upstream, unless otherwise indicated in the contract plans.
 - 3. Joints.** Precast box sections shall be installed with the female end upstream and the male joints fully entered therein. The joint openings between adjacent precast units shall not exceed 3/4". The joints shall be sealed with a continuous gasket installed at the precast plant. Joints shall be drawn together with mechanical connectors, as shown on the approved working drawings. Culverts with a clear rise greater than 4' shall have a minimum of four connectors per joint. Smaller culverts shall have a minimum of two connectors per joint. The number of mechanical connectors supplied shall be equal to the number of connectors required per joint multiplied by the number of joints unless otherwise approved by the Engineer. After installation, connectors may be left on or removed at the contractor's option, unless otherwise noted in the contract plans. When the contract plans require, or the contractor chooses to leave the connectors in place, they shall be located so that they do not create an obstruction inside the culvert. Gaps which occur on the interior surfaces of the culvert due to misalignment or grade difference shall be filled as ordered by the Engineer, with an approved concrete repair material so as to produce a smooth continuous surface.

ITEM 603.63XXYY15 PRECAST CONCRETE BOX CULVERT (Fill Height Less than 2' – 0")

ITEM 603.64XXYY15 PRECAST CONCRETE BOX CULVERT (Fill Height 2' – 0" or Greater)

ITEM 603.65XXYY15 PRECAST CONCRETE BOX CULVERT (Bridge Size, Fill Height Less than 2' – 0")

ITEM 603.66XXYY15 PRECAST CONCRETE BOX CULVERT (Bridge Size, Fill Height 2' – 0" or Greater)

4. **Backfilling.** The types of materials to be used in backfilling and the procedure of placement shall conform to the contract plans and the applicable provisions of Subsection 203-3.15.

METHOD OF MEASUREMENT

The quantity to be measured for concrete box culvert sections shall be the number of linear feet (laying length) furnished and installed in the work. Linear feet (laying length) shall be measured by multiplying the number of whole units by the nominal length of each unit and adding, thereto to the length of any fractional units incorporated in the work. The nominal length of a unit or fractional unit shall be the inside measured length from one butting end to the other butting end measured along the bottom centerline of the unit.

BASIS OF PAYMENT

The quantity to be paid for shall be the number of linear feet of each size box culvert section incorporated in the work. The unit price bid shall include the cost of furnishing all labor, materials, equipment and installation supervision by the precast manufacturer's representative, necessary to satisfactorily complete the work. The cost of furnishing and installing headwalls and cut off walls shall also be included in the unit price bid.

Payment shall be made under Item 603.63XXYY15, 603.64XXYY15, 603.65XXYY15, and 603.66XXYY15, where XX and YY, as indicated in the itemized proposal shall mean the inside span and rise dimensions respectively in feet, to the nearest whole foot, of the precast section.

Maximum XX value = 24 feet

Maximum YY value = above 10 feet consult Materials Bureau.

ITEM 603.67000001 - PRECAST CONCRETE WINGWALL UNITS FOR BOX CULVERTS

DESCRIPTION

This work shall consist of furnishing and placing wingwall units in accordance with these specifications in the locations indicated on the plans and in a manner approved by the Engineer.

MATERIALS

Precast concrete wingwall units shall meet the requirements of Section 706-17 Precast Concrete Box Culverts, except as noted herein.

Design - When the contract plans contain complete design details for the wingwall, alternate designs will not be considered. When the contract plans do not contain complete design details for the wingwall, the contractor shall be responsible for providing them.

CONSTRUCTION DETAILS

A. Inspection, Storage and Handling - Precast wingwall units will be inspected at the construction site to determine if any damage occurred during shipment and for conformance to the dimensional tolerances. An additional inspection will be made prior to placement of wingwall units to determine if any damage occurred during storage.

B. Installation

- 1. Excavation.** The requirements specified in Section 206 Trench, Culvert and Structure Excavation that apply to structures shall govern, except as modified in the plans.
- 2. Placement.** The precast manufacturer shall have a representative available to assist in the installation of the wingwall unit. Wingwalls shall be installed, true to line and grade, in accordance with the contract plans.
- 3. Closure Pour.** The connection between the box culvert and each wingwall shall be formed and poured in place, using a 555 Substructure mix per Materials Procedure MP 501-2 Mix Design and Approval Procedure for Performance Engineered Mixtures – Structural Concrete, Table 2. Wingwalls shall be backfilled prior to placing the closure pour.
- 4. Sealing and Grouting.** Joints between precast wingwall units shall be sealed and or grouted in accordance with the working drawings. Wingwalls shall be backfilled prior to grouting.
- 5. Backfilling.** The types of materials to be used in backfilling and the procedure of placement shall conform to the contract plans and the applicable provisions of Subsection 203-3.15.

METHOD OF MEASUREMENT

Measurement will be taken as the number of square yards of vertical plane projection of wall installed in accordance with the contract documents inclusive of the footing.

BASIS OF PAYMENT

The unit price bid shall include the cost of furnishing all labor, materials, equipment and installation supervision by the precast manufacturer's representative, necessary to satisfactorily complete the work. The cost of all excavation and backfill necessary to complete said work, shall be included in the unit price bid.

ITEM 607.41010010 - TEMPORARY PLASTIC BARRIER FENCE

DESCRIPTION

This work shall consist of furnishing, installing, and maintaining Temporary Plastic Barrier Fences of the type and at the locations shown in the plans or where directed by the Engineer.

MATERIALS

Materials for Temporary Plastic Barrier Fences shall meet the following requirements:

- **Fence:** High-density polyethylene mesh, ultraviolet-stabilized min. 2 years; minimum height 4.0 feet. Color: high-visibility orange or green. When used to protect trees or other vegetation, color shall be high-visibility orange.
- **Posts:** Rigid metal or wood posts, minimum length 6.0 feet.
- **Ties:** Steel wire, #14 gauge or nylon cable ties.
- **Warning signs:** Sheet metal, plastic or other rigid, waterproof material, 1.5 feet by 2.0 feet with 4 inch black letters on a white background. Text shall be: "Protected Site - Keep Out" unless otherwise specified.

CONSTRUCTION DETAILS

Fences shall be erected prior to moving construction equipment onto any area designated for protection.

The line of fences as indicated on the plans shall be staked or marked out on the ground by the Contractor and approved by the Engineer before any fence is installed. Where used for protection of individual trees, fence shall be placed at the drip line (extent of canopy). If not possible, placement shall be as close to the drip line as possible and in no case less than 5.0 feet away from the tree trunk.

On approval of the stakeout, posts shall be securely driven on 6.0 foot-maximum centers, normal to the ground, to a depth 1/3 of the total post length. Plastic barrier fence shall be placed along the side of all posts. Ends of fencing segments shall overlap a distance of at least one half the fence height.

Fencing shall be secured to posts with wire or cable ties at top, middle and bottom of post. Fastener shall be tight enough to prevent the fencing from slipping down. Overlaps shall also be securely fastened.

Barrier fence which is not orange in color shall be flagged at 6.0 foot intervals with red or orange florescent tape. Warning signs shall be mounted on the fence at no more than 100 foot intervals.

Maintenance shall commence immediately after erection of the fence and continue until one week prior to acceptance of the contract, and shall consist of: replacing damaged post(s) and fencing; re-fastening and tightening fencing; and restoring fence to its intended height.

Fencing used for tree or other vegetation protection shall not be temporarily removed to allow equipment access over a protected area, except as required for items of work specifically shown on the plans and approved by the Engineer in writing.

ITEM 607.41010010 - TEMPORARY PLASTIC BARRIER FENCE

METHOD OF MEASUREMENT

The quantity to be measured for payment will be the number of feet of Temporary Plastic Barrier Fence erected, measured along the top, to the nearest whole foot.

BASIS OF PAYMENT

The unit price bid shall include the cost of all labor, materials and equipment necessary to satisfactorily complete the work. Relocation of a fence from one location to another as directed by the Engineer shall be considered as a new location and will be separately paid.

Seventy percent (70%) of the price bid will be paid after satisfactory installation of the fence. The remaining Thirty percent (30%) will be paid after complete removal of the fence.

ITEM 613.04000001 - STOCKPILING AND PLACING EXISTING STREAM BED MATERIALS

DESCRIPTION

This work shall consist of stockpiling and placing existing stream bed materials in conformance with the lines, grades and thickness shown in the Contract Documents or as directed by the Engineer.

MATERIALS

Stream bed materials shall come from the existing stream bed areas within the work limits as shown in the Contract Documents or as determined by the Engineer.

Stream bed materials shall be the surface layer of the native stream bed and shall be free of refuse and debris.

CONSTRUCTION DETAILS

1. Work Plan. The Contractor shall submit a work plan to the Engineer describing the methodology and equipment that will be utilized to complete the stripping, stockpiling, and placing of the stream bed materials. The work plan shall also identify the Contractor's protection of all watercourses from water borne sediment or other pollutants. No work shall commence in the stream bed until the Engineer has reviewed and provided the Contractor with written acceptance of the work plan.
2. Stripping of Existing Stream bed Materials. Stream bed materials shall be stripped from the areas and to the depth designated in the Contract Documents or as directed by the Engineer. The stream bed materials shall be stripped prior to starting the general excavation in the area. After stripping, the stream bed materials shall be immediately placed or stockpiled in a location approved by the Engineer and surrounded with an appropriate erosion control measure.
3. Preparation of Areas to Receive Stream bed Materials. The surface within the areas to be covered by stream bed materials shall be de-watered and graded so that the completed work after the stream bed material is placed, shall conform to the specified lines and grades. The Contractor shall chink the voids in these areas as necessary to the satisfaction of the Engineer, prior to the placement of the stream bed materials.
4. Placing and Spreading of Stream bed Materials. The stream bed materials shall be placed to the thickness and grade lines designated as shown in the contract documents and in a manner consistent with the approved work plan, unless otherwise directed by the Engineer.
5. Restoration. The sites of all stockpiles and areas adjacent thereto which have been disturbed by the Contractor shall be graded as required by the Engineer and put into a condition acceptable for seeding. Surplus stream bed materials shall be disposed of in accordance with the provisions of 203-Disposal of Surplus Excavated Material.

ITEM 613.04000001 - STOCKPILING AND PLACING EXISTING STREAM BED MATERIALS

METHOD OF MEASUREMENT

Stream bed material quantities shall be measured in cubic yards, computed from the final (in place) payment lines shown on the plans except where revised payment lines are established by the Engineer.

BASIS OF PAYMENT

The unit price bid shall include the cost of furnishing all equipment, labor, and materials necessary to complete the work as specified. The stripping (excavation) of the stream bed materials shall be paid for under the appropriate excavation item(s) as noted in the Contract Documents.

ITEM 627.50140008 - CUTTING PAVEMENT

DESCRIPTION:

The contractor shall cut existing asphalt pavement, concrete pavement, asphalt surface course, or asphalt concrete overlay on concrete pavement at the locations indicated and detailed on the plans and as directed by the Engineer.

MATERIALS:

None specified.

CONSTRUCTION DETAILS:

Existing pavement and overlay shall be cut perpendicular to the roadway surface along neat lines, and to the depth indicated on the plans and typical sections, using appropriate equipment. After the pavement has been cut through, the Contractor may use pry bars, pneumatic tools or other methods, to pry loose the pavement to be removed from the pavement that is to remain. A pavement breaker may be used to break up the pavement to be removed after the pavement has been completely cut through and completely free from the pavement to remain.

When pavement cutting is called for in the Contract documents, if a neat vertical face with minimal shatter is obtained by performing an adjacent operation (such as milling) which eliminates the need to perform a separate pavement cutting operation, payment will be made for both the pavement cutting item and the item for the adjacent operation.

Any existing pavements and curbs not indicated to be removed that are damaged by the contractor's operations, shall be repaired at no additional cost to the State. Pavement cutting that the contractor chooses to do for his/her own convenience shall not receive any additional payment from the State.

METHOD OF MEASUREMENT:

The quantity to be measured will be the number of linear feet of pavement cutting satisfactorily completed.

BASIS OF PAYMENT:

The unit price bid per linear foot of pavement cutting shall include the cost of all labor, materials, and equipment necessary to satisfactorily complete the work.

Payment for prying, breaking, removal and disposal of cut pavement shall be made through other appropriate items.

IV. STATE REQUIREMENTS FOR PUBLIC WORK

The Contractor is advised that the latest Schedules of the Prevailing Hourly Wage Rates and the Prevailing Hourly Supplements as published by the State of New York, Department of Labor, and Bureau of Public Works are a part of these Contract Documents along with information pertaining to Davis-Bacon work on federally assisted construction projects. The Contractor is also advised that the rates provided by the NYSDOL and the U.S. Department of Housing and Urban Development are subject to change during the course of the project and must be updated accordingly.

For additional guidance regarding use of prevailing wage rates on this project, the contractor's attention is directed to NYS Standard Specification, Section 102-10.



Kathy Hochul, Governor

Roberta Reardon, Commissioner

Oneida County

Daniel Eckert
21 Corporate Dr
Halfmoon NY 12065

Schedule Year 2025 through 2026
Date Requested 01/15/2026
PRC# 2026000828

Location Simmons Road
Project ID# 2754.83
Project Type Replacing the existing CMP that carries Simmons Road over Dix Brook with a new precast box culvert with precast wingwalls.

PREVAILING WAGE SCHEDULE FOR ARTICLE 8 PUBLIC WORK PROJECT

Attached is the current schedule(s) of the prevailing wage rates and prevailing hourly supplements for the project referenced above. A unique Prevailing Rate Case Number (PRC#) has been assigned to the schedule(s) for your project.

The schedule is effective from July 2025 through June 2026. All updates, corrections, posted on the 1st business day of each month, and future copies of the annual determination are available on the Department's website www.labor.ny.gov. Updated PDF copies of your schedule can be accessed by entering your assigned PRC# at the proper location on the website.

It is the responsibility of the contracting agency or its agent to annex and make part, the attached schedule, to the specifications for this project, when it is advertised for bids and /or to forward said schedules to the successful bidder(s), immediately upon receipt, in order to insure the proper payment of wages.

Please refer to the "General Provisions of Laws Covering Workers on Public Work Contracts" provided with this schedule, for the specific details relating to other responsibilities of the Department of Jurisdiction.

Upon completion or cancellation of this project, enter the required information and mail **OR** fax this form to the office shown at the bottom of this notice, **OR** fill out the electronic version via the NYSDOL website.

NOTICE OF COMPLETION / CANCELLATION OF PROJECT

Date Completed: _____ Date Cancelled: _____

Name & Title of Representative: _____

Phone: (518) 457-5589 Fax: (518) 485-1870
W. Averell Harriman State Office Campus, Bldg. 12, Room 130, Albany, NY 12240

General Provisions of Laws Covering Workers on Article 8 Public Work Contracts

Introduction

The Labor Law requires public work contractors and subcontractors to pay laborers, workers, or mechanics employed in the performance of a public work contract not less than the prevailing rate of wage and supplements (fringe benefits) in the locality where the work is performed.

Contractor Registry

Effective December 30, 2024 all contractors and subcontractors submitting bids or performing construction work on public work projects, or private projects covered by Article 8 of the Labor Law, are required to register with the New York State Department of Labor (NYSDOL) under Labor Law Section 220-i. To register, contractors and subcontractors must submit an application through NYSDOL's Contractor Registry portal which is available through the agency's Management System for Protecting Worker Rights (MPWR) <https://mpwr-public.labor.ny.gov/en/login>.

For additional information, please visit [online](#).

Responsibilities of the Department of Jurisdiction

A Department of Jurisdiction (Contracting Agency) includes a state department, agency, board or commission; a county, city, town or village; a school district, board of education or board of cooperative educational services; a sewer, water, fire, improvement and other district corporation; a public benefit corporation; and a public authority awarding a public work contract.

The Department of Jurisdiction (Contracting Agency) awarding a public work contract MUST obtain a Prevailing Rate Schedule listing the hourly rates of wages and supplements due the workers to be employed on a public work project. This schedule may be obtained by completing and forwarding a "Request for wage and Supplement Information" form (PW 39) to the Bureau of Public Work. The Prevailing Rate Schedule MUST be included in the specifications for the contract to be awarded and is deemed part of the public work contract.

Upon the awarding of the contract, the law requires that the Department of Jurisdiction (Contracting Agency) furnish the following information to the Bureau: the name and address of the contractor, the date the contract was let and the approximate dollar value of the contract. To facilitate compliance with this provision of the Labor Law, a copy of the Department's "Notice of Contract Award" form (PW 16) is provided with the original Prevailing Rate Schedule.

The Department of Jurisdiction (Contracting Agency) is required to notify the Bureau of the completion or cancellation of any public work project. The Department's PW 200 form is provided for that purpose.

Both the PW 16 and PW 200 forms are available for completion [online](#).

Hours

No laborer, worker, or mechanic in the employ of a contractor or subcontractor engaged in the performance of any public work project shall be permitted to work more than eight hours in any day or more than five days in any week, except in cases of extraordinary emergency. The contractor and the Department of Jurisdiction (Contracting Agency) may apply to the Bureau of Public Work for a dispensation permitting workers to work additional hours or days per week on a particular public work project.

Wages and Supplements

The wages and supplements to be paid and/or provided to laborers, workers, and mechanics employed on a public work project shall be not less than those listed in the current Prevailing Rate Schedule for the locality where the work is performed. If a prime contractor on a public work project has not been provided with a Prevailing Rate Schedule, the contractor must notify the Department of Jurisdiction (Contracting Agency) who in turn must request an original Prevailing Rate Schedule form the Bureau of Public Work. Requests may be submitted by: mail to NYSDOL, Bureau of Public Work, State Office Bldg. Campus, Bldg. 12, Rm. 130, Albany, NY 12226; Fax to Bureau of Public Work (518) 485-1870; or electronically at the NYSDOL website www.labor.ny.gov.

Upon receiving the original schedule, the Department of Jurisdiction (Contracting Agency) is REQUIRED to provide complete copies to all prime contractors who in turn MUST, by law, provide copies of all applicable county schedules to each subcontractor and obtain from each subcontractor, an affidavit certifying such schedules were received. If the original schedule expired, the contractor may obtain a copy of the new annual determination from the NYSDOL website www.labor.ny.gov.

The Commissioner of Labor makes an annual determination of the prevailing rates. This determination is in effect from July 1st through June 30th of the following year. The annual determination is available on the NYSDOL website

Payrolls and Payroll Records

Every contractor and subcontractor **MUST** keep original payrolls or transcripts subscribed and affirmed as true under penalty of perjury. As per Article 6 of the Labor law, contractors and subcontractors are required to establish, maintain, and preserve for not less than six (6) years, contemporaneous, true, and accurate payroll records. At a minimum, payrolls must show the following information for each person employed on a public work project: Name, Address, Last 4 Digits of Social Security Number, Classification(s) in which the worker was employed, Hourly wage rate(s) paid, Supplements paid or provided, and Daily and weekly number of hours worked in each classification.

The filing of payrolls to the Department of Jurisdiction is a condition of payment. Every contractor and subcontractor shall submit to the Department of Jurisdiction (Contracting Agency), within thirty (30) days after issuance of its first payroll and every thirty (30) days thereafter, a transcript of the original payrolls, subscribed and affirmed as true under penalty of perjury. The Department of Jurisdiction (Contracting Agency) shall collect, review for facial validity, and maintain such payrolls.

In addition, the Commissioner of Labor may require contractors to furnish, with ten (10) days of a request, payroll records sworn to as their validity and accuracy for public work and private work. Payroll records include, but are not limited to time cards, work description sheets, proof that supplements were provided, cancelled payroll checks and payrolls. Failure to provide the requested information within the allotted ten (10) days will result in the withholding of up to 25% of the contract, not to exceed \$100,000.00. If the contractor or subcontractor does not maintain a place of business in New York State and the amount of the contract exceeds \$25,000.00, payroll records and certifications must be kept on the project worksite.

The prime contractor is responsible for any underpayments of prevailing wages or supplements by any subcontractor.

All contractors or their subcontractors shall provide to their subcontractors a copy of the Prevailing Rate Schedule specified in the public work contract as well as any subsequently issued schedules. A failure to provide these schedules by a contractor or subcontractor is a violation of Article 8, Section 220-a of the Labor Law.

All subcontractors engaged by a public work project contractor or its subcontractor, upon receipt of the original schedule and any subsequently issued schedules, shall provide to such contractor a verified statement attesting that the subcontractor has received the Prevailing Rate Schedule and will pay or provide the applicable rates of wages and supplements specified therein. (See NYS Labor Laws, Article 8 . Section 220-a).

Determination of Prevailing Wage and Supplement Rate Updates Applicable to All Counties

The wages and supplements contained in the annual determination become effective July 1st whether or not the new determination has been received by a given contractor. Care should be taken to review the rates for obvious errors. Any corrections should be brought to the Department's attention immediately. It is the responsibility of the public work contractor to use the proper rates. If there is a question on the proper classification to be used, please call the district office located nearest the project. Any errors in the annual determination will be corrected and posted to the NYSDOL website on the first business day of each month. Contractors are responsible for paying these updated rates as well, retroactive to July 1st.

When you review the schedule for a particular occupation, your attention should be directed to the dates above the column of rates. These are the dates for which a given set of rates is effective. To the extent possible, the Department posts rates in its possession that cover periods of time beyond the July 1st to June 30th time frame covered by a particular annual determination. Rates that extend beyond that instant time period are informational **ONLY** and may be updated in future annual determinations that actually cover the then appropriate July 1st to June 30th time period.

Withholding of Payments

When a complaint is filed with the Commissioner of Labor alleging the failure of a contractor or subcontractor to pay or provide the prevailing wages or supplements, or when the Commissioner of Labor believes that unpaid wages or supplements may be due, payments on the public work contract shall be withheld from the prime contractor in a sufficient amount to satisfy the alleged unpaid wages and supplements, including interest and civil penalty, pending a final determination.

When the Bureau of Public Work finds that a contractor or subcontractor on a public work project failed to pay or provide the requisite prevailing wages or supplements, the Bureau is authorized by Sections 220-b and 235.2 of the Labor Law to so notify the financial officer of the Department of Jurisdiction (Contracting Agency) that awarded the public work contract. Such officer **MUST** then withhold or cause to be withheld from any payment due the prime contractor on account of such contract the amount indicated by the Bureau as sufficient to satisfy the unpaid wages and supplements, including interest and any civil penalty that may be assessed by the Commissioner of Labor. The withholding continues until there is a final determination of the underpayment by the Commissioner of Labor or by the court in the event a legal proceeding is instituted for review of the determination of the Commissioner of Labor.

The Department of Jurisdiction (Contracting Agency) shall comply with this order of the Commissioner of Labor or of the court with respect to the release of the funds so withheld.

Summary of Notice Posting Requirements

The current Prevailing Rate Schedule must be posted in a prominent and accessible place on the site of the public work project. The prevailing wage schedule must be encased in, or constructed of, materials capable of withstanding adverse weather conditions and be titled "PREVAILING RATE OF WAGES" in letters no smaller than two (2) inches by two (2) inches.

The **"Public Work Project"** notice must be posted at the beginning of the performance of every public work contract, on each job site.

Every employer providing workers' compensation insurance and disability benefits must post notices of such coverage in the format prescribed by the Workers' Compensation Board in a conspicuous place on the jobsite.

Every employer subject to the NYS Human Rights Law must conspicuously post at its offices, places of employment, or employment training centers, notices furnished by the State Division of Human Rights.

Employers liable for contributions under the Unemployment Insurance Law must conspicuously post on the jobsite notices furnished by the NYS Department of Labor.

Apprentices

Employees cannot be paid apprentice rates unless they are individually registered in a program registered with the NYS Commissioner of Labor. The allowable ratio of apprentices to journeymen in any craft classification can be no greater than the statewide building trade ratios promulgated by the Department of Labor and included with the Prevailing Rate Schedule. An employee listed on a payroll as an apprentice who is not registered as above or is performing work outside the classification of work for which the apprentice is indentured, must be paid the prevailing journeyworker's wage rate for the classification of work the employee is actually performing.

NYSDOL Labor Law, Article 8, Section 220-3, require that only apprentices individually registered with the NYS Department of Labor may be paid apprenticeship rates on a public work project. No other Federal or State Agency of office registers apprentices in New York State.

Persons wishing to verify the apprentice registration of any person must do so in writing by mail, to the NYSDOL Office of Employability Development / Apprenticeship Training, State Office Bldg. Campus, Bldg. 12, Albany, NY 12226 or by Fax to NYSDOL Apprenticeship Training (518) 457-7154. All requests for verification must include the name and social security number of the person for whom the information is requested.

The only conclusive proof of individual apprentice registration is written verification from the NYSDOL Apprenticeship Training Albany Central office. Neither Federal nor State Apprenticeship Training offices outside of Albany can provide conclusive registration information.

It should be noted that the existence of a registered apprenticeship program is not conclusive proof that any person is registered in that program. Furthermore, the existence or possession of wallet cards, identification cards, or copies of state forms is not conclusive proof of the registration of any person as an apprentice.

Interest and Penalties

In the event that an underpayment of wages and/or supplements is found:

- Interest shall be assessed at the rate then in effect as prescribed by the Superintendent of Banks pursuant to section 14-a of the Banking Law, per annum from the date of underpayment to the date restitution is made.
- A Civil Penalty may also be assessed, not to exceed 25% of the total of wages, supplements, and interest due.

Debarment

Any contractor or subcontractor and/or its successor shall be ineligible to submit a bid on or be awarded any public work contract or subcontract with any state, municipal corporation or public body for a period of five (5) years when:

- Two (2) willful determinations have been rendered against that contractor or subcontractor and/or its successor within any consecutive six (6) year period.
- There is any willful determination that involves the falsification of payroll records or the kickback of wages or supplements.

Criminal Sanctions

Willful violations of the Prevailing Wage Law (Article 8 of the Labor Law) may be a felony punishable by fine or imprisonment of up to 15 years, or both.

Discrimination

No employee or applicant for employment may be discriminated against on account of age, race, creed, color, national origin, sex, disability or marital status.

No contractor, subcontractor nor any person acting on its behalf, shall by reason of race, creed, color, disability, sex or national origin discriminate against any citizen of the State of New York who is qualified and available to perform the work to which the employment relates (NYS Labor Law, Article 8, Section 220-e(a)).

No contractor, subcontractor, nor any person acting on its behalf, shall in any manner, discriminate against or intimidate any employee on account of race, creed, color, disability, sex, or national origin (NYS Labor Law, Article 8, Section 220-e(b)).

The Human Rights Law also prohibits discrimination in employment because of age, marital status, or religion.

There may be deducted from the amount payable to the contractor under the contract a penalty of \$50.00 for each calendar day during which such person was discriminated against or intimidated in violation of the provision of the contract (NYS Labor Law, Article 8, Section 220-e(c)).

The contract may be cancelled or terminated by the State or municipality. All monies due or to become due thereunder may be forfeited for a second or any subsequent violation of the terms or conditions of the anti-discrimination sections of the contract (NYS Labor Law, Article 8, Section 220-e(d)).

Every employer subject to the New York State Human Rights Law must conspicuously post at its offices, places of employment, or employment training centers notices furnished by the State Division of Human Rights.

Workers' Compensation

In accordance with Section 142 of the State Finance Law, the contractor shall maintain coverage during the life of the contract for the benefit of such employees as required by the provisions of the New York State Workers' Compensation Law.

A contractor who is awarded a public work contract must provide proof of workers' compensation coverage prior to being allowed to begin work.

The insurance policy must be issued by a company authorized to provide workers' compensation coverage in New York State. Proof of coverage must be on form C-105.2 (Certificate of Workers' Compensation Insurance) and must name this agency as a certificate holder.

If New York State coverage is added to an existing out-of-state policy, it can only be added to a policy from a company authorized to write workers' compensation coverage in this state. The coverage must be listed under item 3A of the information page.

The contractor must maintain proof that subcontractors doing work covered under this contract secured and maintained a workers' compensation policy for all employees working in New York State.

Every employer providing worker's compensation insurance and disability benefits must post notices of such coverage in the format prescribed by the Workers' Compensation Board in a conspicuous place on the jobsite.

Unemployment Insurance

Employers liable for contributions under the Unemployment Insurance Law must conspicuously post on the jobsite notices furnished by the New York State Department of Labor.



Kathy Hochul, Governor

Roberta Reardon, Commissioner

Oneida County

Daniel Eckert
21 Corporate Dr
Halfmoon NY 12065

Schedule Year 2025 through 2026
Date Requested 01/15/2026
PRC# 2026000828

Location Simmons Road
Project ID# 2754.83
Project Type Replacing the existing CMP that carries Simmons Road over Dix Brook with a new precast box culvert with precast wingwalls.

Notice of Contract Award

New York State Labor Law, Article 8, Section 220.3a requires that certain information regarding the awarding of public work contracts, be furnished to the Commissioner of Labor. One "Notice of Contract Award" (PW 16, which may be photocopied), **MUST** be completed for **EACH** prime contractor on the above referenced project.

Upon notifying the successful bidder(s) of this contract, enter the required information and mail **OR** fax this form to the office shown at the bottom of this notice, **OR** fill out the electronic version via the NYSDOL website.

Contractor Information

All information must be supplied

Federal Employer Identification Number: _____		
Name: _____		
Address: _____ _____		
City: _____	State: _____	Zip: _____
Amount of Contract: \$ _____	Contract Type:	
Approximate Starting Date: ____/____/____	☐ (01) General Construction	
Approximate Completion Date: ____/____/____	☐ (02) Heating/Ventilation	
	☐ (03) Electrical	
	☐ (04) Plumbing	
	☐ (05) Other : _____	

Phone: (518) 457-5589 Fax: (518) 485-1870
W. Averell Harriman State Office Campus, Bldg. 12, Room 130, Albany, NY 12226

Social Security Numbers on Certified Payrolls:

The Department of Labor is cognizant of the concerns of the potential for misuse or inadvertent disclosure of social security numbers. Identity theft is a growing problem and we are sympathetic to contractors' concern regarding inclusion of this information on payrolls if another identifier will suffice.

For these reasons, the substitution of the use of the last four digits of the social security number on certified payrolls submitted to contracting agencies on public work projects is now acceptable to the Department of Labor. This change does not affect the Department's ability to request and receive the entire social security number from employers during its public work/ prevailing wage investigations.

Construction Industry Fair Play Act: Required Posting for Labor Law Article 25-B § 861-d

Construction industry employers must post the "Construction Industry Fair Play Act" notice in a prominent and accessible place on the job site. Failure to post the notice can result in penalties of up to \$1,500 for a first offense and up to \$5,000 for a second offense. The posting is included as part of this wage schedule. Additional copies may be obtained from the NYS DOL website, <https://dol.ny.gov/public-work-and-prevailing-wage>

If you have any questions concerning the Fair Play Act, please call the State Labor Department toll-free at 1-866-435-1499 or email us at: dol.misclassified@labor.ny.gov .

Worker Notification: (Labor Law §220, paragraph a of subdivision 3-a)

Effective June 23, 2020

This provision is an addition to the existing wage rate law, Labor Law §220, paragraph a of subdivision 3-a. It requires contractors and subcontractors to provide written notice to all laborers, workers or mechanics of the *prevailing wage and supplement rate* for their particular job classification *on each pay stub**. It also requires contractors and subcontractors to *post a notice* at the beginning of the performance of every public work contract *on each job site* that includes the telephone number and address for the Department of Labor and a statement informing laborers, workers or mechanics of their right to contact the Department of Labor if he/she is not receiving the proper prevailing rate of wages and/or supplements for his/her job classification. The required notification will be provided with each wage schedule, may be downloaded from our website www.labor.ny.gov or be made available upon request by contacting the Bureau of Public Work at 518-457-5589. *In the event the required information will not fit on the pay stub, an accompanying sheet or attachment of the information will suffice.

**To all State Departments, Agency Heads and Public Benefit Corporations
IMPORTANT NOTICE REGARDING PUBLIC WORK ENFORCEMENT FUND**

Budget Policy & Reporting Manual

B-610

Public Work Enforcement Fund

effective date December 7, 2005

1. Purpose and Scope:

This Item describes the Public Work Enforcement Fund (the Fund, PWEF) and its relevance to State agencies and public benefit corporations engaged in construction or reconstruction contracts, maintenance and repair, and announces the recently-enacted increase to the percentage of the dollar value of such contracts that must be deposited into the Fund. This item also describes the roles of the following entities with respect to the Fund:

- New York State Department of Labor (DOL),
- The Office of the State of Comptroller (OSC), and
- State agencies and public benefit corporations.

2. Background and Statutory References:

DOL uses the Fund to enforce the State's Labor Law as it relates to contracts for construction or reconstruction, maintenance and repair, as defined in subdivision two of Section 220 of the Labor Law. State agencies and public benefit corporations participating in such contracts are required to make payments to the Fund.

Chapter 511 of the Laws of 1995 (as amended by Chapter 513 of the Laws of 1997, Chapter 655 of the Laws of 1999, Chapter 376 of the Laws of 2003 and Chapter 407 of the Laws of 2005) established the Fund.

3. Procedures and Agency Responsibilities:

The Fund is supported by transfers and deposits based on the value of contracts for construction and reconstruction, maintenance and repair, as defined in subdivision two of Section 220 of the Labor Law, into which all State agencies and public benefit corporations enter.

Chapter 407 of the Laws of 2005 increased the amount required to be provided to this fund to .10 of one-percent of the total cost of each such contract, to be calculated at the time agencies or public benefit corporations enter into a new contract or if a contract is amended. The provisions of this bill became effective August 2, 2005.

To all State Departments, Agency Heads and Public Benefit Corporations
IMPORTANT NOTICE REGARDING PUBLIC WORK ENFORCEMENT FUND

OSC will report to DOL on all construction-related ("D") contracts approved during the month, including contract amendments, and then DOL will bill agencies the appropriate assessment monthly. An agency may then make a determination if any of the billed contracts are exempt and so note on the bill submitted back to DOL. For any instance where an agency is unsure if a contract is or is not exempt, they can call the Bureau of Public Work at the number noted below for a determination. Payment by check or journal voucher is due to DOL within thirty days from the date of the billing. DOL will verify the amounts and forward them to OSC for processing.

For those contracts which are not approved or administered by the Comptroller, monthly reports and payments for deposit into the Public Work Enforcement Fund must be provided to the Administrative Finance Bureau at the DOL within 30 days of the end of each month or on a payment schedule mutually agreed upon with DOL.

Reports should contain the following information:

- Name and billing address of State agency or public benefit corporation;
- State agency or public benefit corporation contact and phone number;
- Name and address of contractor receiving the award;
- Contract number and effective dates;
- Contract amount and PWEF assessment charge (if contract amount has been amended, reflect increase or decrease to original contract and the adjustment in the PWEF charge); and
- Brief description of the work to be performed under each contract.

Checks and Journal Vouchers, payable to the "New York State Department of Labor" should be sent to:

Department of Labor
Administrative Finance Bureau-PWEF Unit
Building 12, Room 464
State Office Campus
Albany, NY 12226

Any questions regarding billing should be directed to NYSDOL's Administrative Finance Bureau-PWEF Unit at (518) 457-3624 and any questions regarding Public Work Contracts should be directed to the Bureau of Public Work at (518) 457-5589.

Required Notice under Article 25-B of the Labor Law

**Attention All Employees, Contractors and Subcontractors:
You are Covered by the Construction Industry Fair Play Act**

The law says that you are an employee unless:

- You are free from direction and control in performing your job, **and**
- You perform work that is not part of the usual work done by the business that hired you, **and**
- You have an independently established business.

Your employer cannot consider you to be an independent contractor unless all three of these facts apply to your work.

It is against the law for an employer to misclassify employees as independent contractors or pay employees off the books.

Employee Rights: If you are an employee, you are entitled to state and federal worker protections. These include:

- Unemployment Insurance benefits, if you are unemployed through no fault of your own, able to work, and otherwise qualified,
- Workers' compensation benefits for on-the-job injuries,
- Payment for wages earned, minimum wage, and overtime (under certain conditions),
- Prevailing wages on public work projects,
- The provisions of the National Labor Relations Act, and
- A safe work environment.

It is a violation of this law for employers to retaliate against anyone who asserts their rights under the law. Retaliation subjects an employer to civil penalties, a private lawsuit or both.

Independent Contractors: If you are an independent contractor, **you must pay all taxes and Unemployment Insurance contributions required by New York State and Federal Law.**

Penalties for paying workers off the books or improperly treating employees as independent contractors:

- **Civil Penalty**
 - First offense: Up to \$2,500 per employee
 - Subsequent offense(s): Up to \$5,000 per employee
- **Criminal Penalty**
 - First offense: Misdemeanor - up to 30 days in jail, up to a \$25,000 fine and debarment from performing public work for up to one year.
 - Subsequent offense(s): Misdemeanor - up to 60 days in jail or up to a \$50,000 fine and debarment from performing public work for up to 5 years.

If you have questions about your employment status or believe that your employer may have violated your rights and you want to file a complaint, call the Department of Labor at (866) 435-1499 or send an email to dol.misclassified@labor.ny.gov. All complaints of fraud and violations are taken seriously. You can remain anonymous.

Employer Name:

IA 999 (09/16)



Attention Employees

THIS IS A: **PUBLIC WORK PROJECT**

If you are employed on this project as a **worker, laborer, or mechanic** you are entitled to receive the **prevailing wage and supplements rate** for the classification at which you are working.

Your pay stub and wage notice received upon hire must clearly state your wage rate and supplement rate.

Chapter 629 of
the Labor Laws
of 2007:

These wages are set by law and must be posted at the work site. They can also be found at:
<https://dol.ny.gov/bureau-public-work>



If you feel that you have not received proper wages or benefits, please call our nearest office.*

Albany	(518) 457-2744	Patchogue	(631) 687-4882
Binghamton	(607) 721-8005	Rochester	(585) 258-4505
Buffalo	(716) 847-7159	Syracuse	(315) 428-4056
Garden City	(516) 228-3915	Utica	(315) 793-2314
New York City	(212) 932-2419	White Plains	(914) 997-9507
Newburgh	(845) 568-5287		

* For New York City government agency construction projects, please contact the Office of the NYC Comptroller at (212) 669-4443, or www.comptroller.nyc.gov – click on Bureau of Labor Law.

Contractor Name: _____

Project Location: _____

Requirements for OSHA 10 Compliance

Article 8 §220-h requires that when the advertised specifications, for every contract for public work, is \$250,000.00 or more the contract must contain a provision requiring that every worker employed in the performance of a public work contract shall be certified as having completed an OSHA 10 safety training course. The clear intent of this provision is to require that all employees of public work contractors, required to be paid prevailing rates, receive such training "prior to the performing any work on the project."

The Bureau will enforce the statute as follows:

All contractors and sub contractors must attach a copy of proof of completion of the OSHA 10 course to the first certified payroll submitted to the contracting agency and on each succeeding payroll where any new or additional employee is first listed.

Proof of completion may include but is not limited to:

- Copies of bona fide course completion card (*Note: Completion cards do not have an expiration date.*)
- Training roster, attendance record or other documentation from the certified trainer pending the issuance of the card.
- Other valid proof

**A certification by the employer attesting that all employees have completed such a course is not sufficient proof that the course has been completed.

Any questions regarding this statute may be directed to the New York State Department of Labor, Bureau of Public Work at 518-457-5589.

WICKS

Public work projects are subject to the Wicks Law requiring separate specifications and bidding for the plumbing, heating and electrical work, when the total project's threshold is \$3 million in Bronx, Kings, New York, Queens and, Richmond counties; \$1.5 million in Nassau, Suffolk and Westchester counties; and \$500,000 in all other counties.

For projects below the monetary threshold, bidders must submit a sealed list naming each subcontractor for the plumbing, HVAC and electrical and the amount to be paid to each. The list may not be changed unless the public owner finds a legitimate construction need, including a change in specifications or costs or the use of a Project Labor Agreement (PLA), and must be open to public inspection.

Allows the state and local agencies and authorities to waive the Wicks Law and use a PLA if it will provide the best work at the lowest possible price. If a PLA is used, all contractors shall participate in apprentice training programs in the trades of work it employs that have been approved by the Department of Labor (DOL) for not less than three years. They shall also have at least one graduate in the last three years and use affirmative efforts to retain minority apprentices. PLA's would be exempt from Wicks, but deemed to be public work subject to prevailing wage enforcement.

The Commissioner of Labor shall have the power to enforce separate specification requirements on projects, and may issue stop-bid orders against public owners for non-compliance.

Other new monetary thresholds, and similar sealed bidding for non-Wicks projects, would apply to certain public authorities including municipal housing authorities, NYC Construction Fund, Yonkers Educational Construction Fund, NYC Municipal Water Finance Authority, Buffalo Municipal Water Finance Authority, Westchester County Health Care Association, Nassau County Health Care Corp., Clifton-Fine Health Care Corp., Erie County Medical Center Corp., NYC Solid Waste Management Facilities, and the Dormitory Authority.

Contractors must pay subcontractors within a 7 days period.

(07.19)

Introduction to the Prevailing Rate Schedule

Information About Prevailing Rate Schedule

This information is provided to assist you in the interpretation of particular requirements for each classification of worker contained in the attached Schedule of Prevailing Rates.

Classification

It is the duty of the Commissioner of Labor to make the proper classification of workers taking into account whether the work is heavy and highway, building, sewer and water, tunnel work, or residential, and to make a determination of wages and supplements to be paid or provided. It is the responsibility of the public work contractor to use the proper rate. If there is a question on the proper classification to be used, please call the district office located nearest the project. District office locations and phone numbers are listed below. Prevailing Wage Schedules are issued separately for "General Construction Projects" and "Residential Construction Projects" on a county-by-county basis.

General Construction Rates apply to projects such as: Buildings, Heavy & Highway, and Tunnel and Water & Sewer rates. Residential Construction Rates generally apply to construction, reconstruction, repair, alteration, or demolition of one family, two family, row housing, or rental type units intended for residential use. Some rates listed in the Residential Construction Rate Schedule have a very limited applicability listed along with the rate. Rates for occupations or locations not shown on the residential schedule must be obtained from the General Construction Rate Schedule. Please contact the local Bureau of Public Work office before using Residential Rate Schedules, to ensure that the project meets the required criteria.

*Contractor Registry (LL 220-I): Effective December 30th, 2024

Labor Law Section 220-i(6) prohibits contractors from bidding on public work and prohibits both contractors and subcontractors from commencing work on private and public projects subject to prevailing wage requirements. This section requires contractors to submit their Certificate of Registration with their bid materials. Each Certificate of Registration will have a unique registration number. Failure to provide proof of registration, as required by Labor Law Section 220-i, as a minimum qualification will result in the bidder being deemed non-responsive. There is a public database of registered contractors and subcontractors available online at data.ny.gov to confirm registration validity. For additional information on how to register and the requirements, visit <https://dol.ny.gov/public-work-contractor-and-subcontractor-registry-landing>

*Electronic Certified Payroll (LL 220-J): Effective December 31st, 2025

Effective December 31, 2025, all contractors and subcontractors who perform public work, or covered private work subject to the prevailing wage, will be required to submit certified payrolls electronically to the Bureau of Public Work and Prevailing Wage Enforcement. Additional information about the electronic certified payroll submission system will be made available on the Department's Website at <https://dol.ny.gov/Electronic-Payroll>

Payrolls and Payroll Records

Every contractor and subcontractor MUST keep original payrolls or transcripts subscribed and affirmed as true under penalty of perjury. Payrolls must be maintained for at least three (3) years from the projects date of completion. Additionally, as per Article 6 of the Labor Law, contractors and subcontractors are required to establish, maintain, and preserve for not less than six (6) years, contemporaneous, true, and accurate payroll records.

At a minimum, payrolls must show the following information for each person employed on a public work project: Name; Address, Last 4 Digits of Social Security number, Classification(s) in which the worker was employed, Hourly wage rate(s) paid, Supplements paid or provided, and Daily and weekly number of hours worked in each classification.

Payroll records and transcripts are required to be kept on site during all the time that work under that contract is being performed.

NOTE: For more detailed information regarding Article 9 prevailing wage contracts, please refer to "General Provisions of Laws Covering Workers on Article 9 Public Work Building Service Contracts".

If you have any questions concerning the attached schedule or would like additional information, please write to:

New York State Department of Labor
Bureau of Public Work
State Office Campus, Bldg. 12
Albany, NY 12240

OR

Contact the nearest BUREAU of PUBLIC WORK District Office

District Office Locations:	Telephone #	FAX #
Bureau of Public Work - Albany	518-457-2744	518-485-0240
Bureau of Public Work - Binghamton	607-721-8005	607-721-8004

Bureau of Public Work - Buffalo	716-847-7159	716-847-7650
Bureau of Public Work - Garden City	516-228-3915	516-794-3518
Bureau of Public Work - Newburgh	845-568-5287	845-568-5332
Bureau of Public Work - New York City	212-932-2419	212-775-3579
Bureau of Public Work - Patchogue	631-687-4882	631-687-4902
Bureau of Public Work - Rochester	585-258-4505	585-258-4708
Bureau of Public Work - Syracuse	315-428-4056	315-428-4671
Bureau of Public Work - Utica	315-793-2314	315-793-2514
Bureau of Public Work - White Plains	914-997-9507	914-997-9523
Bureau of Public Work - Central Office	518-457-5589	518-485-1870

Paid Holidays

Paid Holidays are days for which an eligible employee receives a regular day's pay, but is not required to perform work. If an employee works on a day listed as a paid holiday, this remuneration is in addition to payment of the required prevailing rate for the work actually performed.

Overtime

At a minimum, all work performed on a public work project in excess of eight hours in any one day or more than five days in any workweek is overtime. However, the specific overtime requirements for each trade or occupation on a public work project may differ. Specific overtime requirements for each trade or occupation are contained in the prevailing rate schedules.

Overtime holiday pay is the premium pay that is required for work performed on specified holidays. It is only required where the employee actually performs work on such holidays.

The applicable holidays are listed under HOLIDAYS: OVERTIME. The required rate of pay for these covered holidays can be found in the OVERTIME PAY section listings for each classification.

Supplemental Benefits

Particular attention should be given to the supplemental benefit requirements. Although in most cases the payment or provision of supplements is straight time for all hours worked, some classifications require the payment or provision of supplements, or a portion of the supplements, to be paid or provided at a premium rate for premium hours worked. Supplements may also be required to be paid or provided on paid holidays, regardless of whether the day is worked. The Overtime Codes and Notes listed on the particular wage classification will indicate these conditions as required.

Effective Dates

When you review the schedule for a particular occupation, your attention should be directed to the dates above the column of rates. These are the dates for which a given set of rates is effective. The rate listed is valid until the next effective rate change or until the new annual determination which takes effect on July 1 of each year.

All contractors and subcontractors are required to pay the current prevailing rates of wages and supplements. If you have any questions please contact the Bureau of Public Work or visit the New York State Department of Labor website (www.labor.ny.gov) for current wage rate information.

Shift Work

If the timeline of the contract requires shift work be performed to meet deadlines, the BPWE will enforce the shift work rate as the required rate on the project whether or not shift work is specifically addressed in the contract.

Paid Prenatal Leave

Every employer shall be required to provide to its employees twenty hours of paid prenatal personal leave during any fifty-two week calendar period. Paid prenatal personal leave shall mean leave taken for the health care services received by an employee during their pregnancy or related to such pregnancy, including physical examinations, medical procedures, monitoring and testing, and discussions with a healthcare provider related to the pregnancy. Paid prenatal personal leave may be taken in hourly increments. Benefits for paid prenatal personal leave shall be paid in hourly installments. Employees shall receive compensation at the employee's regular rate of pay, or the applicable minimum wage established by the labor law, whichever is greater, for the use of Paid Prenatal leave.

Apprentice Training Ratios

The following are the allowable ratios of registered Apprentices to Journey-workers.

For example, the ratio 1:1,1:3 indicates the allowable initial ratio is one Apprentice to one Journeyworker. The Journeyworker must be in place on the project before an Apprentice is allowed. Then three additional Journeyworkers are needed before a second Apprentice is allowed. The last ratio repeats indefinitely. Therefore, three more Journeyworkers must be present before a third Apprentice can be hired, and so on.

Please call Apprentice Training Central Office at (518) 457-6820 if you have any questions.

Title (Trade)	Ratio
Boilermaker (Construction)	1:1,1:4
Boilermaker (Shop)	1:1,1:3
Carpenter (Bldg.,H&H, Pile Driver/Dockbuilder)	1:1,1:4
Carpenter (Residential)	1:1,1:3
Electrical (Outside) Lineman	1:1,1:2
Electrician (Inside)	1:1,1:3
Elevator/Escalator Construction & Modernizer	1:1,1:2
Glazier	1:1,1:3
Insulation & Asbestos Worker	1:1,1:3
Iron Worker	1:1,1:4
Laborer	1:1,1:3
Mason	1:1,1:4
Millwright	1:1,1:4
Op Engineer	1:1,1:5
Painter	1:1,1:3
Plumber & Steamfitter	1:1,1:3
Roofer	1:1,1:2
Sheet Metal Worker	1:1,1:3
Sprinkler Fitter	1:1,1:2

If you have any questions concerning the attached schedule or would like additional information, please contact the nearest BUREAU of PUBLIC WORK District Office or write to:

New York State Department of Labor
Bureau of Public Work
State Office Campus, Bldg. 12
Albany, NY 12226

District Office Locations:	Telephone #	FAX #
Bureau of Public Work - Albany	518-457-2744	518-485-0240
Bureau of Public Work - Binghamton	607-721-8005	607-721-8004
Bureau of Public Work - Buffalo	716-847-7159	716-847-7650
Bureau of Public Work - Garden City	516-228-3915	516-794-3518
Bureau of Public Work - Newburgh	845-568-5287	845-568-5332
Bureau of Public Work - New York City	212-932-2419	212-775-3579
Bureau of Public Work - Patchogue	631-687-4882	631-687-4902
Bureau of Public Work - Rochester	585-258-4505	585-258-4708
Bureau of Public Work - Syracuse	315-428-4056	315-428-4671
Bureau of Public Work - Utica	315-793-2314	315-793-2514
Bureau of Public Work - White Plains	914-997-9507	914-997-9523
Bureau of Public Work - Central Office	518-457-5589	518-485-1870

Oneida County General Construction

Boilermaker	01/01/2026
-------------	------------

JOB DESCRIPTION Boilermaker

DISTRICT 7

ENTIRE COUNTIES

Cayuga, Clinton, Cortland, Franklin, Jefferson, Lewis, Madison, Oneida, Onondaga, Oswego, Seneca, St. Lawrence, Tompkins

WAGES

Per hour:	07/01/2025	01/01/2026	01/01/2027
		Additional	Additional
Boilermaker	\$ 40.50	\$ 2.50*	\$ 2.50*

* To be allocated at a later date.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 26.60*
	+ 1.49

*This portion of the benefits subject to the same premium rate as shown for overtime wages.

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6, 15, 25) on HOLIDAY PAGE

NOTE: When a holiday falls on Sunday, the day observed by the State or Nation shall be observed. When a holiday falls on Saturday, Friday will be observed as the holiday.

REGISTERED APPRENTICES

WAGES per hour: Six (6) month terms at the following percentage of Journeyworker's wage.

1st	2nd	3rd	4th	5th	6th	7th	8th
65%	65%	70%	75%	80%	85%	90%	95%

SUPPLEMENTAL BENEFITS per hour:

\$ 19.76*	\$ 19.76*	\$ 20.74*	\$ 21.71*	\$ 22.67*	\$ 23.66*	\$ 24.66*	\$ 25.62*
+ 1.49	+ 1.49	+ 1.49	+ 1.49	+ 1.49	+ 1.49	+ 1.49	+ 1.49

*This portion of the benefits subject to the same premium rate as shown for overtime wages.

7-175

Broadband	01/01/2026
-----------	------------

JOB DESCRIPTION Broadband

DISTRICT 4

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

PARTIAL COUNTIES

Orange: Only in the Village of Greenwood Lake, Village of Highland Falls, Town of Tuxedo, and Town of Patterson

WAGES

NOTE: Applies to all public work and covered private projects, including those receiving ConnectAll funding subject to New York State Labor Law §224-E, solicited on or after July 1, 2025. For all other projects solicited prior to July 1, 2025 please see LINEMAN ELECTRICIAN-TELEDATA

Per Hour:	07/01/2025	08/04/2025
Field Tech	\$ 51.31	\$ 52.85
Install/Repair		

For outside work (excluding installation on building construction/alteration/renovation projects), stopping at first point of attachment (demarcation), installing/maintaining/repairing broadband internet service.

"Broadband", "Broadband Service", or "Broadband Internet" means mass-market retail service by wire or radio that provides the capability to transmit data to and receive data from all or substantially all internet endpoints, including any capabilities that are incidental to and enable the operation of the communications service, but excluding dial-up internet access service.

Note: EXCLUDES work within ten (10) feet of High Voltage (600 Volts and over) transmission lines for this work, please see LINEMAN

SUPPLEMENTAL BENEFITS

Per Hour:

\$ 23.24

OVERTIME PAY

See (B, K, *R) on OVERTIME PAGE

* Two and one half times the hourly rate after the 8th hour

HOLIDAY

Paid: See (5, 6, 7, 11, 12) on HOLIDAY PAGE

Overtime: See (5, 6, 7, 11, 12) on HOLIDAY PAGE

4-CWA-Dist2

Carpenter - Building

01/01/2026

JOB DESCRIPTION Carpenter - Building

DISTRICT 6

ENTIRE COUNTIES

Cayuga, Herkimer, Madison, Oneida, Seneca, Yates

WAGES

Per hour:	07/01/2025	01/01/2026	07/01/2026 Additional	07/01/2027 Additional
Carpenter	\$ 32.64	\$ 33.14	\$ 5.00*	\$ 4.25*
Floor Coverer	32.64	33.14	5.00*	4.25*
Carpet Layer	32.64	33.14	5.00*	4.25*
Drywall	32.64	33.14	5.00*	4.25*
Diver - Wet Day	57.64	58.14	5.00*	4.25*
Diver - Dry Day	33.64	34.14	5.00*	4.25*
Dive Tender	33.64	34.14	5.00*	4.25*

* To be allocated at a later date.

NOTE ADDITIONAL AMOUNTS PAID FOR THE FOLLOWING WORK LISTED BELOW (per hour worked):

- Pile Drivers & Dock Builders shall receive \$ 0.25 per hour over the Journeyworker's rate of pay when performing piledriving & dock building work.
- Certified Welders shall receive \$ 3.00 per hour over the Journeyworker's rate of pay when the employee is required to be certified and performs DOT or ABS specified welding work.
- When an employee performs work within a contaminated area on a State and/or Federally designated hazardous waste site, and where relevant State and/or Federal regulations require employees to be furnished and use or wear required forms of personal protection, then the employee shall receive his regular hourly rate plus \$ 1.50 per hour.
- Depth pay for Divers based upon deepest depth on the day of the dive (per diem payment):
 - 0' to 80' no additional fee
 - 81' to 100' additional \$ 0.50 per foot
 - 101' to 150' additional \$ 0.75 per foot
 - 151' and deeper additional \$ 1.25 per foot
- Penetration pay for Divers based upon deepest penetration on the day of the dive (per diem payment):
 - 0' to 50' no additional fee
 - 51' to 100' additional \$ 0.75 per foot
 - 101' and deeper additional \$ 1.00 per foot
- Diver rates apply to all hours worked on dive day.

SHIFT WORK

On Agency/Owner mandated shift work, the following rates will be applicable:

1st Shift - Regular Rate

2nd Shift - Premium of 10% of base wage per hour

3rd Shift - Premium of 15% of base wage per hour

Shift work shall be defined as implementing at least two (2) shifts in a twenty-four (24) consecutive hour period. Shift work must be for a minimum of three (3) consecutive days.

SUPPLEMENTAL BENEFITS

Per hour:

	07/01/2025	01/01/2026
Journeyworker	\$ 22.20	\$ 22.20

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: Any holiday which occurs on Sunday shall be observed the following Monday. If Christmas falls on a Saturday, it shall be observed on the prior Friday.

REGISTERED APPRENTICES

Wages per hour (1300 hour terms at the following percentage of Journeyworker's base wage):

1st	2nd	3rd	4th
65%	70%	75%	80%

Supplemental Benefits per hour:

\$ 13.11	\$ 13.11	\$ 15.71	\$ 15.72
----------	----------	----------	----------

NOTE ADDITIONAL AMOUNTS PAID TO APPRENTICES FOR THE FOLLOWING WORK LISTED BELOW (per hour worked):

- Pile Driving & Dock Builder apprentices shall receive an additional \$ 0.25 per hour worked when performing piledriving & dock building work.
- Certified Welders shall receive \$ 3.00 per hour over the apprentice's rate of pay when the apprentice is required to be certified and performs DOT or ABS specified welding work.
- When an apprentice performs work within a contaminated area on a State and/or Federally designated hazardous waste site, and where relevant State and/or Federal regulations require the apprentice to be furnished and use or wear required forms of personal protection, then the apprentice shall receive his regular hourly rate plus \$ 1.50 per hour.

6-277B-Cay

Carpenter - Building / Heavy&Highway

01/01/2026

JOB DESCRIPTION Carpenter - Building / Heavy&Highway

DISTRICT 2

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

PARTIAL COUNTIES

Orange: The area lying on Northern side of Orange County demarcated by a line drawn from the Bear Mountain Bridge continuing west to the Bear Mountain Circle, continue North on 9W to the town of Cornwall where County Road 107 (also known as Quaker Rd) crosses under 9W, then east on County Road 107 to Route 32, then north on Route 32 to Orrs Mills Rd, then west on Orrs Mills Rd to Route 94, continue west and south on Route 94 to the Town of Chester, to the intersection of Kings Highway, continue south on Kings Highway to Bellvale Rd, west on Bellvale Rd to Bellvale Lakes Rd, then south on Bellvale Lakes Rd to Kain Rd, southeast on Kain Rd to Route 17A, then north and southeast along Route 17A to Route 210, then follow Route 210 to NJ Border.

WAGES

Wages per hour:	07/01/2025	07/01/2026 Additional	07/01/2027 Additional
Carpenter - ONLY for Artificial Turf/Synthetic Sport Surface	\$ 37.94	\$ 2.25*	\$ 2.25*

* To be allocated at a later date.

Note - Does not include the operation of equipment. Please see Operating Engineers rates.

SUPPLEMENTAL BENEFITS

Per hour worked:

Journeyworker	\$ 27.34
---------------	----------

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5) on HOLIDAY PAGE
Overtime: See (5, 6, 16) on HOLIDAY PAGE

Notes:

When a holiday falls upon a Saturday, it shall be observed on the preceding Friday. When a holiday falls upon a Sunday, it shall be observed on the following Monday.

An employee taking an unexcused day off the regularly scheduled day before or after a paid Holiday shall not receive Holiday pay.

REGISTERED APPRENTICES

Wages per hour (1300 hour terms at the following percentage of Journeyworker's wage):

1st	2nd	3rd	4th
65%	70%	75%	80%

Supplemental Benefits per hour worked:
\$19.10 \$19.69 \$21.83 \$22.42

2-42AtSS

Carpenter - Heavy&Highway

01/01/2026

JOB DESCRIPTION Carpenter - Heavy&Highway

DISTRICT 2

ENTIRE COUNTIES

Chenango, Herkimer, Madison, Oneida, Otsego

WAGES

Per hour	07/01/2025	07/01/2026 Additional	07/01/2027 Additional
Carpenter	\$ 44.52	\$ 3.00*	\$ 3.24*
Piledriver	44.52	3.00*	3.24*
Dockbuilder	44.52	3.00*	3.24*
Diver-Wet Day	69.52	3.00*	3.24*
Diver-Dry Day	45.52	3.00*	3.24*
Diver-Tender	45.52	3.00*	3.24*

*To be allocated at a later date.

NOTE ADDITIONAL AMOUNTS PAID FOR THE FOLLOWING WORK LISTED BELOW (per hour worked):

- State or Federal designated hazardous site, requiring protective gear shall be an additional \$2.50 per hour.
- Certified welders when required to perform welding work will receive an additional \$5.00 per hour.

ADDITIONAL NOTES PERTAINING TO DIVERS/TENDERS:

- Divers and Tenders shall receive one and one half (1 1/2) times their regular diver and tender rate of pay for Effluent and Slurry diving.
- Divers and tenders being paid at the specified rate for Effluent and Slurry diving shall have all overtime rates based on the specified rate plus the appropriate overtime rates (one and one half or two times the specified rate for Slurry and Effluent divers and tenders).
- The pilot of an ADS or submersible will receive one and one-half (1 1/2) times the Diver-Wet Day Rate for time submerged.
- All crew members aboard a submersible shall receive the Diver-Wet Day rate.
- Depth pay for Divers based upon deepest depth on the day of the dive (per diem payment):
 - 0' to 50' no additional fee
 - 51' to 100' additional \$0.50 per foot
 - 101' to 150' additional \$0.75 per foot
 - 151' to 200' additional \$1.25 per foot
 - 201' and deeper additional \$1.50 per foot
- Penetration pay for Divers based upon deepest penetration on the day of the dive (per diem payment):
 - 0' to 50' no additional fee
 - 51' to 100' additional \$0.75 per foot
 - 101' to 200' additional \$1.00 per foot
 - Over 201' additional \$1.25 per foot
- Diver rates applies to all hours worked on dive day.

SHIFT WORK

When project owner mandates a single irregular work shift, the Journeyworkers and Apprentices will receive an additional \$4.00 per hour. A single irregular work shift can start any time from 5:00 p.m. to 1:00 a.m.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker \$ 27.31

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

- In the event a Holiday falls on a Saturday, the Friday before will be observed as a Holiday. If a Holiday falls on a Sunday, then Monday will be observed as a Holiday.

- The employee must work their scheduled workday before and their scheduled workday after the holiday to receive holiday pay.

REGISTERED APPRENTICES

CARPENTER/PILEDRIIVER/DOCKBUILDER APPRENTICES

Wages per hour (1300 hour terms at the following percentage of journeyworker's base wage):

1st	2nd	3rd	4th
65%	70%	75%	80%
Supplemental Benefits per hour:			
\$ 19.07	\$ 19.66	\$ 21.75	\$ 22.34

NOTE ADDITIONAL AMOUNTS PAID PER HOUR WORKED TO APPRENTICES FOR SPECIFIC TYPES OF WORK PERFORMED:

- State or Federal designated hazardous site, requiring protective gear shall be an additional \$2.50 per hour.
- Certified welders when required to perform welding work will receive an additional \$5.00 per hour.

2-277HH-CHMOO

Electrician

01/01/2026

JOB DESCRIPTION Electrician

DISTRICT 6

ENTIRE COUNTIES

Cortland, Herkimer, Madison, Oneida, Oswego

PARTIAL COUNTIES

Cayuga: Townships of Ira, Locke, Sempronius, Sterling, Summerhill and Victory.

Chenango: Only the Townships of Columbus, New Berlin and Sherburne.

Onondaga: Entire County except Townships of Elbridge and Skaneateles.

Otsego: Only the Townships of Plainfield, Richfield, Springfield, Cherry Valley, Roseboom, Middlefield, Otsego, Exeter, Edmeston, Burlington, Pittsfield and New Lisbon.

Tompkins: Only the Township of Groton.

Wayne: Only the Townships of Huron, Wolcott, Rose and Butler.

WAGES

Per hour:	07/01/2025	06/01/2026 Additional
Electrician	\$ 50.50	\$ 5.25*
Teledata	50.50	5.25*
Cable Splicer	55.55	5.25*

* To be allocated at a later date.

NOTE: Additional amounts, subject to overtime premiums, due for the following work (applicable to all employees):

- Additional \$2.50 per hour for work performed over 35 feet above the ground, floor, or roof levels or where work is required in tunnels, shafts, or under compressed air 35 feet below the ground level.
- Additional \$3.00 per hour for working over 50 feet above or below ground, floor, or roof level. This includes work on ladders, "toothpicks", scaffolds, boatswain chairs, towers, smokestacks or other open structures, or mechanical lifts used over 60 feet.

Occupied Conditions: When necessary to perform alteration and/or renovation work and owner mandates (due to occupied conditions) prevent the work from being performed during "normal" working hours (defined as between 6:00 a.m. and 4:30 p.m. Monday through Friday), alternate hours may be worked, provided: 1) The hours are established for a minimum of five (5) days duration or the length of the job, whichever is shorter; and 2) An entire work scope within a job-site area is performed utilizing the varied hours. If these conditions are satisfied, all hours worked Monday through Friday of a shift that starts before or ends after the "normal" hours, shall be paid at the appropriate rate plus fifteen percent (15%). However, the following restrictions shall apply:

- 1) "Alternate" hours shall consist of a minimum of eight (8) consecutive hours per day.
- 2) Hours worked in excess of eight (8) hours per day, Monday through Friday, shall be paid at a rate of one and one-half times the applicable rate (dayshift + 15%).
- 3) Hours worked on Saturday shall be paid at time and one-half the applicable rate.
- 4) Hours worked on Sundays and Holidays shall be paid at double the straight time rate.
- 5) Work of a new construction nature may not be worked under these conditions.

SHIFT WORK

THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTS OF EIGHT (8) HOURS FOR AT LEAST FIVE (5) DAYS DURATION WHICH MAY HAVE BEEN WORKED. WHEN TWO (2) SHIFTS OR THREE (3) SHIFTS ARE WORKED:

1ST SHIFT	8:00AM - 4:30PM:	Regular wage rate
2ND SHIFT	4:30 PM - 1:00 AM:	Regular wage rate plus 15%
3RD SHIFT	12:30 AM - 9:00 AM:	Regular wage rate plus 25%

SUPPLEMENTAL BENEFITS

Per hour:	\$ 33.52 plus
Journeyworker	3% of hourly wage paid*

*NOTE: The 3% is based on the hourly wage paid, straight time or premium rate.

OVERTIME PAY

See (B, *E, Q) on OVERTIME PAGE

* NOTE: On Saturday the first 8 hours worked shall be paid at a rate of one and one-half times the applicable rate. All additional hours are payable at double the straight time rate.

WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6, 15, 26) on HOLIDAY PAGE

NOTE: If any of the above holidays fall on Saturday, Friday shall be observed as the holiday. If any of the above holidays fall on Sunday, Monday shall be observed as the holiday.

REGISTERED APPRENTICES

WAGES per hour: Hourly terms at the following wage.

1st period (0-1000 hrs)	\$ 20.20
2nd period (1001-2000)	22.75
3rd period (2001-3500)	25.25
4th period (3501-5000)	30.30
5th period (5001-6500)	35.35
6th Period (6501-8000)	40.40

SUPPLEMENTAL BENEFITS per hour:

1st period	\$ 14.69*
2nd period	14.69*
3rd period	30.02*
4th period	30.72*
5th period	31.42*
6th period	32.12*

* PLUS 3% OF HOURLY WAGE PAID, STRAIGHT TIME RATE OR PREMIUM RATE.

6-43

Elevator Constructor

01/01/2026

JOB DESCRIPTION Elevator Constructor

DISTRICT 6

ENTIRE COUNTIES

Broome, Cayuga, Chenango, Cortland, Franklin, Jefferson, Lewis, Onondaga, Oswego, St. Lawrence, Tioga, Tompkins

PARTIAL COUNTIES

Delaware: Only the towns of: Tompkins, Walton, Masonville, Sidney, Franklin and Deposit.

Madison: Only the towns of: Cazenovia, DeRuyter, Eaton, Fenner, Georgetown, Lebanon, Lenox, Nelson and Sullivan.

Oneida: Only the towns of: Camden, Florence and Vienna.

WAGES

Per hour:	07/01/2025	01/01/2026	01/01/2027
Mechanic	\$ 58.44	\$ 61.003	\$ 63.719
Helper	40.91	42.70	44.60

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 38.435*	\$ 38.985*	39.535*
---------------	------------	------------	---------

*NOTE - add 6% of regular hourly rate for all hours worked. Add 8% of regular hourly rate if more than 5 years of service.

OVERTIME PAY

See (D, O) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 15, 16) on HOLIDAY PAGE
Overtime: See (5, 6, 15, 16) on HOLIDAY PAGE

NOTE: When a holiday falls on a Saturday, it shall be observed on Friday. When a holiday falls on Sunday, it shall be observed on Monday.

REGISTERED APPRENTICES

WAGES per hour: 1 year terms at the following percentage of the Elevator Constructor wage.

0-6	6-12	2nd	3rd	4th
months	months	year	year	year
50%	55%	65%	70%	80%

SUPPLEMENTAL BENEFITS per hour:

0-6 months: 6% of the hourly apprentice rate paid, no additional supplemental benefits.

All other terms: Same as Journeyworker

6-62.1

Elevator Constructor**01/01/2026**

JOB DESCRIPTION Elevator Constructor**DISTRICT 1****ENTIRE COUNTIES**

Albany, Clinton, Essex, Fulton, Hamilton, Herkimer, Montgomery, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Warren, Washington

PARTIAL COUNTIES

Madison: Madison Only the towns of: Brookfield, Hamilton, Lincoln, Madison, Smithfield, Stockbridge and the City of Oneida
Oneida: Entire county except the towns of: Camden, Florence, and Vienna.

WAGES

Per hour

07/01/2025

01/01/2026

Mechanic

\$ 57.73

\$ 60.26

Helper

70% of Mechanic
Wage Rate70% of Mechanic
Wage Rate**SUPPLEMENTAL BENEFITS**

Per hour

07/01/2025

01/01/2026

Journeyworker/Helper

\$ 38.435*

\$ 38.985*

(*)Plus 6% of hourly rate, if less than 5 years of service. Plus 8% of hourly rate, if more than 5 years of service.

OVERTIME PAY

See (D, O) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 15, 16) on HOLIDAY PAGE

Overtime: See (5, 6, 15, 16) on HOLIDAY PAGE

Note: When a paid holiday falls on Saturday, it shall be observed on Friday. When a paid holiday falls on Sunday, it shall be observed on Monday.

REGISTERED APPRENTICES

Wages per hour:

0-6 mo*	6-12 mo	2nd yr	3rd yr	4th yr
50%	55 %	65 %	70 %	80 %

(*)Plus 6% of the hourly rate, no additional supplemental benefits.

Supplemental Benefits - per hour worked:

Same as Journeyperson/Helper

1-35

Glazier**01/01/2026**

JOB DESCRIPTION Glazier**DISTRICT 5****ENTIRE COUNTIES**

Cayuga, Cortland, Herkimer, Madison, Oneida, Onondaga, Oswego

WAGES

Per Hour:

07/01/2025

Glazier

\$ 30.00

SUPPLEMENTAL BENEFITS

Per hour:

Journeyman

\$ 28.74

OVERTIME PAY

See (B,E,E2*,Q) on OVERTIME PAGE.

*Note - Or circumstances beyond the control of the employer.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

1000 hour terms:

Appr. 1st term	\$ 20.00
Appr. 2nd term	21.00
Appr. 3rd term	22.00
Appr. 4th term	23.00
Appr. 5th term	24.00
Appr. 6th term	25.00
Appr. 7th term	26.00
Appr. 8th term	27.00

Supplemental Benefits per hour:

Appr. 1st term	\$ 12.92
Appr. 2nd term	12.92
Appr. 3rd term	18.92
Appr. 4th term	18.92
Appr. 5th term	19.92
Appr. 6th term	19.92
Appr. 7th term	20.92
Appr. 8th term	20.92

5-677.Z-2

Insulator - Heat & Frost

01/01/2026

JOB DESCRIPTION Insulator - Heat & Frost

DISTRICT 7

ENTIRE COUNTIES

Broome, Cayuga, Chemung, Chenango, Cortland, Herkimer, Jefferson, Lewis, Madison, Oneida, Onondaga, Oswego, Otsego, Schuyler, Seneca, St. Lawrence, Tioga, Tompkins

WAGES

Per hour: 07/01/2025

Asbestos Installer	\$ 43.25
Insulation Installer	43.25
(On mechanical systems only)	

SHIFT WORK

The following rates will apply on all contracting agency-mandated shifts worked:

1st Shift	\$ 43.25
2nd Shift	49.74
3rd Shift	51.90

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 27.34
---------------	----------

OVERTIME PAY

See (*B1, **K, P) on OVERTIME PAGE

*NOTE: First 10 hours on Saturday.

**NOTE: Holidays that fall on Sunday are subject to double time.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (2*, 4, 6, 28) on HOLIDAY PAGE
*Triple time for Labor Day if worked.

REGISTERED APPRENTICES

WAGES per hour: One (1) year terms at the following percentage of Journeyworker's wage.

1st	2nd	3rd	4th
60%	70%	80%	90%

SUPPLEMENTAL BENEFITS per hour:

\$ 24.09 \$ 24.09 \$ 27.34 \$ 27.34

7-30-Syracuse

Ironworker

01/01/2026

JOB DESCRIPTION Ironworker

DISTRICT 7

ENTIRE COUNTIES

Franklin, Herkimer, Lewis, Oneida, St. Lawrence

PARTIAL COUNTIES

Chenango: Only the Townships of Columbus, New Berlin, North Norwich, Plymouth, Sherburne and Smyrna.

Fulton: Only the Townships of Caroga, Ephratah, Oppenheim, and Stratford.

Hamilton: Only the Townships of Arietta, Indian Lake, Inlet, Lake Pleasant, Long Lake and Morehouse.

Jefferson: Only the Townships of Antwerp, Champion, Philadelphia and Wilna.

Madison: Only the Townships of Brookfield, Eaton, Hamilton, Lebanon, Madison, Oneida and Stockbridge.

Montgomery: Only the Townships of Canajoharie, Minden, Palatine and St. Johnsville.

Otsego: Only the Townships of Burlington, Cherry Valley, Decatur, Edmeston, Exeter, Hartwick, Middlefield, New Lisbon, Otsego, Pittsfield, Plainfield, Richfield, Roseboom, Springfield and Westford, and the Village of Cooperstown.

WAGES

Per hour:	07/01/2025	07/01/2026 Additional
Structural/Reinforcing	\$ 35.50	\$ 2.74*
Mach. Mover/Ornamental	35.50	2.74*
Stone Derrickman	35.50	2.74*
Chain Link Fence	35.50	2.74*
Sheeter Ironworker	35.50	2.74*
Pre-Engineered Building	35.50	2.74*
Window Erector	35.50	2.74*
Precast Erector	35.50	2.74*
Welder	35.50	2.74*

* To be allocated at a later date.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker \$ 32.91

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: Any holiday which occurs on Sunday shall be observed the following Monday. Any holiday which occurs on Saturday shall be observed the previous Friday.

REGISTERED APPRENTICES

WAGES per hour: 1500 hour terms at the following wage.

1-1500hrs	\$ 21.50
1501-3000hrs	23.50
3001-4500hrs	25.50
4501-6000hrs	27.50

SUPPLEMENTAL BENEFITS per hour:

1-1500hrs	\$ 14.19
1501-3000hrs	22.67
3001-4500hrs	23.88
4501-6000hrs	25.09

7-440

Laborer - Building

01/01/2026

JOB DESCRIPTION Laborer - Building

DISTRICT 1

ENTIRE COUNTIES

Hamilton, Herkimer, Madison, Oneida

PARTIAL COUNTIES

Fulton: Only the Townships of Stratford, Oppenheim, Caroga and Ephratah

Montgomery: Only the Townships of Minden, St. Johnsville, Canajoharie, Palatine and Root

WAGES

GROUP #1: Basic
GROUP #2: Pipe Layer, Mortar Mixer, Walk behind Mortar Buggy and Power Lift
GROUP #3: Wagon Drill(Where separate air compressor unit supplies power.)
GROUP #4: Blaster, Formsetter, Riding Mortar Buggy
GROUP #5: Hazardous Waste Removal
GROUP #6: Asbestos and Lead Removal

WAGES per hour:	07/01/2025
Building Laborer:	
Group # 1	\$ 35.64
Group # 2	35.64
Group # 3	36.14
Group # 4	36.14
Group # 5	36.99
Group # 6	36.99

SHIFT WORK

Second shift work will be paid at the base wage plus 10% Third shift work will be paid at the base wage plus 15%

SUPPLEMENTAL BENEFITS

Per hour:

	07/01/2025
All groups	\$ 26.91

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour
1000 Hour terms at the following percentage of Journeyperson's basic hourly wage.

1st	2nd	3rd	4th
65 %	75 %	85 %	95 %

Supplemental Benefits per hour worked

	07/01/2025
Apprentices	\$ 26.91

1-190z2B

Laborer - Heavy&Highway

01/01/2026

JOB DESCRIPTION Laborer - Heavy&Highway

DISTRICT 1

ENTIRE COUNTIES

Hamilton, Herkimer, Madison, Oneida

PARTIAL COUNTIES

Fulton: Only Townships of Stratford, Oppenheim, Caroga and Ephratah
Montgomery: Only Townships of Minden, St. Johnsville, Canajoharie, Palatine and Root.

WAGES

GROUP # A: Basic, Drill Helper, Flagman, Outboard and Hand Boats.

GROUP # B: Bull Float, Chain Saw, Concrete Aggregate Bin, Concrete Bootmen, Gin Buggy, Hand or Machine Vibrator, Jack Hammer, Mason Tender, Mortar Mixer, Pavement Breaker, Handlers of all SteelMash, Small Generators for Laborers Tools, Installation of Bridge Drainage Pipe, Pipe Layers, Vibrator Type Rollers, Tamper, Drill Doctor, Tail or Screw Operator on Asphalt Paver, Water Pump Operators(1-1/2" and Single Diaphragm), Nozzle (Asphalt, Gunite, Seeding, and Sand Blasting), Laborers on Chain Link Fence Erection, Rock Splitter and Power Unit, Pusher Type Concrete Saw and all other Gas, Electric, Oil and Air Tool Operators, Wrecking Laborer.

GROUP # C: Rock or Drilling Machine Operators (only where a separate air compressor unit supplies power), Acetylene Torch Operators, Asphalt Raker and Powderman.

GROUP # D: Blasters, Form Setters (prefab curb radius), Stone or Granite Curb Setters.

GROUP # E: Employees performing hazardous waste removal, lead abatement and removal, or asbestos abatement and removal on a State and/or Federally designated waste site & where relevant State or Federal regulations require employees to use or wear forms of personal protection.

Per hour: 07/01/2025

Heavy/Highway Laborer:

GROUP # A	\$ 42.65
GROUP # B	42.85
GROUP # C	43.05
GROUP # D	43.05
GROUP # E	45.35

SHIFT WORK

All employees who work a single irregular workday that starts from 5:00 pm to 1:00 am on a governmental mandated night shift shall be paid an additional 15% of base wage per hour.

SUPPLEMENTAL BENEFITS

Per hour: \$ 29.69

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

Note: If the holiday falls on Sunday, it will be celebrated on Monday. If the Monday Holiday is worked it will be paid at double time plus the Holiday pay. If the Holiday falls on a Saturday employer can choose to celebrate Saturday or give Friday off with pay. If the Saturday Holiday is worked it will be paid at double time plus the Holiday pay

REGISTERED APPRENTICES

Wages per hour

1000 hour terms at the following percentage of Journeyman's wage

1st	2nd	3rd	4th
65%	75%	85%	95%

SUPPLEMENTAL BENEFITS per hour worked

Apprentices \$ 28.69

1-190z2H/H

Laborer - Tunnel

01/01/2026

JOB DESCRIPTION Laborer - Tunnel

DISTRICT 1

ENTIRE COUNTIES

Albany, Fulton, Hamilton, Herkimer, Madison, Montgomery, Oneida, Rensselaer, Saratoga, Schenectady, Schoharie, Washington

WAGES

Class 1: All support laborers/sandhogs working above the shaft or tunnel. All laborers/sandhogs working inside a 350 foot radius from the center of a shaft/portal performing site work.

Class 2: All laborers/sandhogs working in the shaft or tunnel

Class 4: Safety Miners

Class 5: Site work related to Shaft/Tunnel working outside a 350 foot radius from the center of a shaft/portal unless required to enter the shaft, access manhole or tunnel.

Per Hour

07/01/2025

Class 1	\$ 48.75
Class 2	50.75
Class 4	53.00
Class 5	45.00

Toxic and hazardous waste, lead abatement and asbestos abatement work will be paid an additional \$ 3.00 an hour.

SHIFT WORK

On all government mandated irregular shift work: 1.5 x the base rate Monday - Friday, Saturday is paid at 1.65 x the base rate, Sunday is paid at 2.15 x the base rate

SUPPLEMENTAL BENEFITS

Per hour

Journeyworker \$ 30.50

OVERTIME PAY

See (B, E, Q, V) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 15, 25) on HOLIDAY PAGE

Overtime: See (5, 6, 15, 16, 25) on HOLIDAY PAGE

Note: When a holiday falls on Sunday, the following Monday shall be considered a holiday and all work performed on either day shall be at the double time rate. When a holiday falls on Saturday, the preceding Friday shall be considered a holiday and all work performed on either day shall be at the double time rate.

REGISTERED APPRENTICES

FOR APPRENTICE RATES, refer to the appropriate Laborer Heavy & Highway wage rate contained in the wage schedule for the County and Location where the work is to be performed.

1-190/157T

Lineman Electrician

01/01/2026

JOB DESCRIPTION Lineman Electrician

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

WAGES

A Lineman/Technician shall perform all overhead aerial work. A Lineman/Technician on the ground will install all electrical panels, connect all grounds, install and connect all electrical conductors, assembly of all electrical materials, conduit, pipe, or raceway; placing of fish wire; pulling of cables, wires or fiber optic cable through such raceways; splicing of conductors; dismantling of such structures, lines or equipment.

Crane Operators: Operation of any type of crane on line projects.

Crawler Backhoe: Operation of tracked excavator/crawler backhoe with 1/2 yard bucket or larger on line projects.

Digging Machine Operator: All other digging equipment and augering on line projects.

A Groundman/Truck Driver shall: Build and set concrete forms, handle steel mesh, set footer cages, transport concrete in a wheelbarrow, hand or machine concrete vibrator, finish concrete footers, mix mortar, grout pole bases, cover and maintain footers while curing in cold weather, operate jack hammer, operate hand pavement breaker, tamper, concrete and other motorized saws, as a drill helper, operate and maintain generators, water pumps, chainsaws, sand blasting, operate mulching and seeding machine, air tools, electric tools, gas tools, load and unload materials, hand shovel and/or broom, prepare and pour mastic and other fillers, assist digger operator/equipment operator in ground excavation and restoration, landscape work and painting. Only when assisting a lineman technician, a groundman/truck driver may assist in installing conduit, pipe, cables and equipment.

NOTE: Includes Teledata Work within ten (10) feet of High Voltage Transmission Lines. Also includes digging of holes for poles, anchors, footer, and foundations for electrical equipment.

-----Below rates applicable on all overhead and underground distribution and maintenance work, and all overhead and underground transmission line work and the installation of fiber optic cable where no other construction trades are or have been involved. Includes access matting for line work.

Per hour:	07/01/2025	05/04/2026	05/03/2027	05/01/2028
Group A:				
Lineman, Technician	\$ 61.56	\$ 64.37	\$ 66.84	\$ 69.47
Crane, Crawler Backhoe	61.56	64.37	66.84	69.47
Welder, Cable Splicer	61.56	64.37	66.84	69.47
Group B:				
Digging Mach. Operator	\$ 55.40	\$ 57.93	\$ 60.16	\$ 62.52
Group C:				
Tractor Trailer Driver	\$ 52.33	\$ 54.71	\$ 56.81	\$ 59.05
Groundman, Truck Driver	49.25	51.50	53.47	55.58
Equipment Mechanic	49.25	51.50	53.47	55.58
Group D:				
Flagger	\$ 33.86	\$ 35.40	\$ 36.76	\$ 38.21

Additional 3% per hour above regular rate for entire crew when a helicopter is used. This will increase to 5% on May 03, 2027.

-----Below rates applicable on all electrical sub-stations, switching structures, fiber optic cable and all other work not defined as "Utility outside electrical work." Includes access matting for line work.

Group A:				
Lineman, Technician	\$ 61.56	\$ 64.37	\$ 66.84	\$ 69.47
Crane, Crawler Backhoe	61.56	64.37	66.84	69.47
Cable Splicer	67.72	70.81	73.52	76.42
Certified Welder, Pipe Type Cable	\$ 64.64	\$ 67.59	\$ 70.18	\$ 72.94
Group B:				
Digging Mach. Operator	\$ 55.40	\$ 57.93	\$ 60.16	\$ 62.52
Group C:				
Tractor Trailer Driver	\$ 52.33	\$ 54.71	\$ 56.81	\$ 59.05
Groundman, Truck Driver	49.25	51.50	53.47	55.58
Equipment Mechanic	49.25	51.50	53.47	55.58
Group D:				
Flagger	\$ 33.86	\$ 35.40	\$ 36.76	\$ 38.12

Additional 3% per hour above regular rate for entire crew when a helicopter is used. This will increase to 5% on May 03, 2027.

-----Below rates applicable on all switching structures, maintenance projects, railroad catenary install/maintenance third rail installation, bonding of rails and pipe type cable and installation of fiber optic cable. Includes access matting for line work.

Group A:				
Lineman, Tech, Welder	\$ 62.94	\$ 65.81	\$ 68.34	\$ 71.03
Crane, Crawler Backhoe	62.94	65.81	68.34	71.03
Cable Splicer	69.23	72.39	75.17	78.13
Certified Welder, Pipe Type Cable	66.09	69.10	71.76	74.58
Group B:				
Digging Mach. Operator	\$ 56.65	\$ 59.23	\$ 61.51	\$ 63.93
Group C:				
Tractor Trailer Driver	\$ 53.50	\$ 55.94	\$ 58.09	\$ 60.38
Groundman, Truck Driver	50.35	52.65	54.67	56.82
Equipment Mechanic	50.35	52.65	54.67	56.82
Group D:				
Flagger	\$ 34.62	\$ 36.20	\$ 37.59	\$ 39.07

Additional 3% per hour above regular rate for entire crew when a helicopter is used. This will increase to 5% on May 03, 2027.

-----Below rates applicable on all overhead and underground transmission line work & fiber optic cable where other construction trades are or have been involved. This applies to transmission line work only, not other construction. Includes access matting for line work.

Group A:				
Lineman, Tech, Welder	\$ 64.18	\$ 67.10	\$ 69.68	\$ 72.43
Crane, Crawler Backhoe	64.18	67.10	69.68	72.43
Group B:				
Digging Mach. Operator	\$ 57.76	\$ 60.39	\$ 62.71	\$ 65.19
Group C:				
Tractor Trailer Driver	\$ 54.55	\$ 57.04	\$ 59.23	\$ 61.57
Groundman, Truck Driver	51.34	53.68	55.74	57.94
Equipment Mechanic	51.34	53.68	55.74	57.94
Group D:				
Flagger	\$ 35.30	\$ 36.91	\$ 38.32	\$ 39.84

Additional 3% per hour above regular rate for entire crew when a helicopter is used. This will increase to 5% on May 03, 2027.

SHIFT WORK

THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTS OF AT LEAST FIVE (5) DAYS DURATION WORKED BETWEEN THE HOURS LISTED BELOW:

1ST SHIFT	8:00 AM to 4:30 PM REGULAR RATE
2ND SHIFT	4:30 PM to 1:00 AM REGULAR RATE PLUS 17.3 %
3RD SHIFT	12:30 AM to 9:00 AM REGULAR RATE PLUS 31.4 %

SUPPLEMENTAL BENEFITS

Per hour:

	07/01/2025	05/04/2026	05/03/2027	05/01/2028
Group A	\$ 31.90*	\$ 32.90*	\$ 34.40*	\$ 35.90*
Group B	\$ 27.90*	\$ 28.90*	\$ 30.40*	\$ 31.90*
Group C	\$ 27.70*	\$ 28.50*	\$ 29.70*	\$ 30.90*
Group D	\$ 27.65*	\$ 28.40*	\$ 29.53*	\$ 30.66*

*Plus 7 % of the hourly wage paid. The 7% is based on straight time or premium time.

OVERTIME PAY

See (B, E, Q, X) on OVERTIME PAGE. NOTE: Double time for all emergency work designated by the Dept. of Jurisdiction.

WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid See (5, 6, 8, 15, 25) on HOLIDAY PAGE

Overtime See (5, 6, 8, 15, 25) on HOLIDAY PAGE

NOTE: All paid holidays falling on Saturday shall be observed on the preceding Friday. All paid holidays falling on Sunday shall be observed on the following Monday. Supplements for holidays paid at straight time.

REGISTERED APPRENTICES

WAGES per hour: 1000 hour terms at the following percentage of the applicable Journeyworker's Lineman wage.

1st	2nd	3rd	4th	5th	6th	7th
60%	65%	70%	75%	80%	85%	90%

SUPPLEMENTAL BENEFITS per hour:

	07/01/2025	05/04/2026	05/03/2027	05/01/2028
All terms:	\$ 27.65*	\$ 28.40*	\$ 29.53*	\$ 30.66*

*Plus 7% of the hourly wage paid. The 7% is based on straight time or premium time.

6-1249a

Lineman Electrician - Teledata

01/01/2026

JOB DESCRIPTION Lineman Electrician - Teledata

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Westchester, Wyoming, Yates

WAGES

NOTE: Applies to all public work and covered private projects, including those receiving ConnectAll funding subject to LL 224-E, solicited prior to July 1, 2025. For all projects, excluding dial-up internet access service, solicited on or after July 1, 2025, please see BROADBAND

Per hour: 07/01/2025

Cable Splicer	\$ 40.81
Installer, Repairman	\$ 38.73
Teledata Lineman	\$ 38.73
Tech., Equip. Operator	\$ 38.73
Groundman/Flagger	\$ 20.53

For outside work, stopping at first point of attachment (demarcation).

NOTE: EXCLUDES Teledata work within ten (10) feet of High Voltage (600 volts and over) transmission lines. For this work, please see LINEMAN.

SHIFT WORK

THE FOLLOWING RATES APPLY WHEN THE CONTRACTING AGENCY MANDATES MULTIPLE SHIFTS OF AT LEAST FIVE (5) DAYS DURATION ARE WORKED. WHEN TWO (2) OR THREE (3) SHIFTS ARE WORKED THE FOLLOWING RATES APPLY:

1ST SHIFT	REGULAR RATE
2ND SHIFT	REGULAR RATE PLUS 10%
3RD SHIFT	REGULAR RATE PLUS 15%

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 5.77
	*plus 3% of the hour wage paid

*The 3% is based on the hourly wage paid, straight time rate or premium rate.

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid:	See (1) on HOLIDAY PAGE
Overtime:	See (5, 6, 16) on HOLIDAY PAGE

6-1249LT - Teledata

Lineman Electrician - Traffic Signal, Lighting

01/01/2026

JOB DESCRIPTION Lineman Electrician - Traffic Signal, Lighting

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Warren, Washington, Wayne, Wyoming, Yates

WAGES

Lineman/Technician shall perform all overhead aerial work. A Lineman/Technician on the ground will install all electrical panels, connect all grounds, install and connect all electrical conductors which includes, but is not limited to road loop wires; conduit and plastic or other type pipes that carry conductors, flex cables and connectors, and to oversee the encasement or burial of such conduits or pipes.

Crane Operators: Operation of any type of crane on Traffic Signal/Lighting projects.

Crawler Backhoe: Operation of tracked excavator/crawler backhoe with 1/2 yard bucket or larger on Traffic Signal/Lighting projects.

Digging Machine Operator: All other digging equipment and augering on Traffic Signal/Lighting projects.

A Groundman/Truck Driver shall: Build and set concrete forms, handle steel mesh, set footer cages, transport concrete in a wheelbarrow, hand or machine concrete vibrator, finish concrete footers, mix mortar, grout pole bases, cover and maintain footers while curing in cold weather, operate jack hammer, operate hand pavement breaker, tamper, concrete and other motorized saws, as a drill helper, operate and maintain generators, water pumps, chainsaws, sand blasting, operate mulching and seeding machine, air tools, electric tools, gas tools, load and unload materials, hand shovel and/or broom, prepare and pour mastic and other fillers, assist digger operator/equipment operator in ground excavation and restoration, landscape work and painting. Only when assisting a lineman technician, a groundman/truck driver may assist in installing conduit, pipe, cables and equipment.

A flagger's duties shall consist of traffic control only.

Per hour:	07/01/2025	05/04/2026	05/03/2027	05/01/2028
Group A:				
Lineman, Technician	\$ 52.86	\$ 55.31	\$ 57.40	\$ 59.64
Crane, Crawler Backhoe	52.86	55.31	57.40	59.64
Certified Welder	55.50	58.08	60.27	62.62
Group B:				
Digging Machine	\$ 47.57	\$ 49.78	\$ 51.66	\$ 53.68
Group C:				
Tractor Trailer Driver	\$ 44.93	\$ 47.01	\$ 48.79	\$ 50.69
Groundman, Truck Driver	42.29	44.25	45.92	47.71
Equipment Mechanic	42.29	44.25	45.92	47.71

Group D:

Flagger	\$ 31.72	\$ 33.19	\$ 34.44	\$ 35.78
---------	----------	----------	----------	----------

Above rates are applicable for installation, testing, operation, maintenance and repair on all Traffic Control (Signal) and Illumination (Lighting) projects, Traffic Monitoring Systems, and Road Weather Information Systems. Includes digging of holes for poles, anchors, footer foundations for electrical equipment; assembly of all electrical materials or raceway; placing of fish wire; pulling of cables, wires or fiber optic cable through such raceways; splicing of conductors; dismantling of such structures, lines or equipment.

SHIFT WORK

THE FOLLOWING RATES WILL APPLY ON ALL CONTRACTING AGENCY MANDATED MULTIPLE SHIFTS OF AT LEAST FIVE (5) DAYS DURATION WORKED BETWEEN THE HOURS LISTED BELOW:

1ST SHIFT	8:00 AM TO 4:30 PM	REGULAR RATE
2ND SHIFT	4:30 PM TO 1:00 AM	REGULAR RATE PLUS 17.3%
3RD SHIFT	12:30 AM TO 9:00 AM	REGULAR RATE PLUS 31.4%

SUPPLEMENTAL BENEFITS

Per hour worked:

	07/01/2025	05/04/2026	05/03/2027	05/01/2028
Group A	\$ 31.90*	\$ 32.90*	\$ 34.40*	\$ 35.90*
Group B	\$ 27.90*	\$ 28.90*	\$ 30.40*	\$ 31.90*
Group C	\$ 27.70*	\$ 28.50*	\$ 29.70*	\$ 30.90*
Group D	\$ 27.65*	\$ 28.40*	\$ 29.53*	\$ 30.66*

* Plus 7% of the hourly wage paid. The 7% is based on straight time or premium time.

OVERTIME PAY

See (B, E, Q, X) on OVERTIME PAGE. NOTE: Double time for all emergency work designated by the Dept. of Jurisdiction.

WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid: See (5, 6, 8, 15, 25) on HOLIDAY PAGE

Overtime: See (5, 6, 8, 15, 25) on HOLIDAY PAGE

NOTE: All paid holidays falling on Saturday shall be observed on the preceding Friday. All paid holidays falling on Sunday shall be observed on the following Monday. Supplements for holidays paid at straight time.

REGISTERED APPRENTICES

WAGES per hour: 1000 hour terms at the following percentage of the applicable Journeyworker's Lineman wage.

1st	2nd	3rd	4th	5th	6th	7th
60%	65%	70%	75%	80%	85%	90%

SUPPLEMENTAL BENEFITS per hour:

	07/01/2025	05/04/2026	05/03/2027	05/01/2028
All terms:	\$ 27.65*	\$ 28.40*	\$ 29.53*	\$ 30.66*

* Plus 7% of the hourly wage paid. The 7% is based on straight time or premium time.

6-1249a-LT

Lineman Electrician - Tree Trimmer

01/01/2026

JOB DESCRIPTION Lineman Electrician - Tree Trimmer

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Rensselaer, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

WAGES

Applies to line clearance, tree work and right-of-way preparation on all new or existing energized overhead or underground electrical, telephone and CATV lines. This also includes stump removal near underground energized electrical lines including telephone and CATV lines.

Per hour:	07/01/2025	01/01/2026	01/04/2026	01/03/2027
Tree Trimmer	\$ 33.18	\$ 33.18	\$ 34.67	\$ 36.23
Equipment Operator	29.35	29.35	30.67	32.05
Equipment Mechanic	29.35	29.35	30.67	32.05

Truck Driver	23.85	23.85	24.93	26.05
Groundman	19.64	19.64	20.53	21.45
Flagger	15.50	16.00	16.20	16.93

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 10.98*	\$ 10.98*	\$ 11.23*	\$ 11.48*
---------------	-----------	-----------	-----------	-----------

* Plus 4.5% of the hourly wage paid. The 4.5% is based on straight time rate or premium rate.

OVERTIME PAY

See (B, E, Q, X) on OVERTIME PAGE

WAGE CAP - Double the straight time hourly base wage shall be the maximum hourly wage compensation for any hour worked. Contractor is still responsible to pay the hourly benefit amount for each hour worked.

HOLIDAY

Paid: See (5, 6, 8, 15, 16, 25) on HOLIDAY PAGE

Overtime: See (5, 6, 8, 15, 16, 25) on HOLIDAY PAGE

NOTE: All paid holidays falling on a Saturday shall be observed on the preceding Friday. All paid holidays falling on a Sunday shall be observed on the following Monday.

6-1249TT

Mason - Building

01/01/2026

JOB DESCRIPTION Mason - Building

DISTRICT 12

ENTIRE COUNTIES

Herkimer, Jefferson, Lewis, Oneida, St. Lawrence

PARTIAL COUNTIES

Madison: Entire County except the Townships of Sullivan & Cazenovia

WAGES

Per hour 07/01/2025

Tile/Marble/Terrazzo

Setter	\$ 37.10
Finisher	29.52

SUPPLEMENTAL BENEFITS

Per hour worked

Journeyman Setters	\$ 20.31
Journeyman Finishers	19.54

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour

Hour terms at the following percentage of journeyman's wage

Setter:	
1st term 500 hours	60%
2nd term 1000 hours	70%
3rd term 1000 hours	80%
4th term 1000 hours	85%
5th term 1000 hours	90%
6th term 1500 hours	95%

Finisher;	
1st term 500 HOURS	70%
2ND term 1000 HOURS	80%
3RD term 1000 HOURS	90%
4TH term 1200 HOURS	95%

Supplemental Benefits per hour worked

Setter:	
1st & 2nd Term	\$ 12.66
3rd & 4th Term	16.49
5th Term	18.40
6th Term	20.31

Finishers:	
1st & 2nd Term	\$ 11.95
All others	15.74

12-2TS.2

Mason - Building	01/01/2026
-------------------------	-------------------

JOB DESCRIPTION Mason - Building

DISTRICT 12

ENTIRE COUNTIES

Herkimer, Oneida

PARTIAL COUNTIES

Lewis: The townships of Lewis, Leyden, Osceola, Turin and West Turin

Madison: Entire County except the Townships of Sullivan and Cazenovia

WAGES

Per hour 07/01/2025

Bricklayer/Blocker	\$ 39.99
Cement Mason(Bldg)	39.99
Plasterer/Fireproofing*	39.99
Stone Mason	39.99
Concrete Cutter	39.99
Pointer/Caulker/Cleaner	39.99

Additional \$.25 per hr. for work in restricted radiation area of atomic plant.

Additional \$5.00 per day more for employees working on a two-point suspension scaffold (Pointer, Caulker, and Cleaner are excluded).

(*)Fireproofing on Structural only.

SUPPLEMENTAL BENEFITS

Per hour worked

Journeyman \$ 22.13

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour

750 hour terms at the following percentage of Journey's wage

1st	2nd	3rd	4th	5th	6th	7th	8th
60%	60%	65%	70%	75%	80%	85%	90%

Supplemental Benefits per hour worked:

All Terms \$ 22.13

12-2b.2

Mason - Heavy&Highway	01/01/2026
----------------------------------	-------------------

JOB DESCRIPTION Mason - Heavy&Highway

DISTRICT 12

ENTIRE COUNTIES

Albany, Cayuga, Clinton, Columbia, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Madison, Montgomery, Oneida, Oswego, Rensselaer, Saratoga, Schenectady, Schoharie, St. Lawrence, Warren, Washington

PARTIAL COUNTIES

Onondaga: For Heavy & Highway Cement Mason or Plaster Work in Onondaga County, refer to Mason-Heavy&Highway tag 12-2h/h on.

WAGES

Per hour
07/01/2025
Mason &
Bricklayer \$ 43.01

Additional \$1.00 per hour for work on any swing scaffold or staging suspended by means of ropes or cables.

SUPPLEMENTAL BENEFITS

Per hour worked

Journeyman
\$ 22.93

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour

750 HR TERMS at the following percent of Journeyman's wage

1st	2nd	3rd	4th	5th	6th	7th	8th
60%	60%	65%	70%	75%	80%	85%	90%

Supplemental Benefits per hour worked

0 to 500 Hours	\$ 14.13
All Other	22.93

12-2hh.1

Millwright

01/01/2026

JOB DESCRIPTION Millwright

DISTRICT 6

ENTIRE COUNTIES

Albany, Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Wyoming, Yates

WAGES

THE FOLLOWING RATE APPLIES TO ANY GAS/STEAM TURBINE AND OR RELATED COMPONENT WORK, INCLUDING NEW INSTALLATIONS OR MAINTENANCE AND ANY/ALL WORK PERFORMED WITHIN THE PROPERTY LIMITS OF A NUCLEAR FACILITY.

Per hour: 07/01/2025

Millwright - \$ 47.00
Power Generation

NOTE: ADDITIONAL PREMIUMS PAID FOR THE FOLLOWING WORK LISTED BELOW (amount subject to any overtime premiums):

- Certified Welders shall receive an additional \$1.75 per hour provided they are directed to perform Certified Welding.
- If a work site has been declared a hazardous site by the Owner and the use of protective gear (including, as a minimum, air purifying canister-type chemical respirators) is required, then that employee shall receive an additional \$1.50 per hour.
- An employee performing the work of a machinist shall receive an additional \$2.00 per hour. For the purposes of this premium to apply, a "machinist" is a person who uses a lathe, Bridgeport, milling machine or similar type of tool to make or modify parts.
- When performing work underground at 500 feet and below, the employee shall receive an additional \$1.00 per hour.

SUPPLEMENTAL BENEFITS

Per hour paid:

Journeyworker \$ 28.45*

*NOTE: Subject to OT premium

OVERTIME PAY

See (B, E, E2, Q, V) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: Any holiday that falls on Sunday shall be observed the following Monday. Any holiday that falls on Saturday shall be observed the preceding Friday.

REGISTERED APPRENTICES

WAGES per hour: One year terms at the following percentage of Journeyworker's wage:

Appr. 1st year	65%*
Appr. 2nd year	75%*
Appr. 3rd year	80%*
Appr. 4th year	90%*

*NOTE: Additional premium for the following work listed below:

Certified Welder	\$ 1.75
Hazardous Waste Work	1.50
Machinist	2.00
Underground	1.00
(500' and below)	

SUPPLEMENTAL BENEFITS per hour:

Appr. 1st year	\$ 11.95
Appr. 2nd year	23.50
Appr. 3rd year	25.15
Appr. 4th year	26.80

6-1163Power

Millwright

01/01/2026

JOB DESCRIPTION Millwright

DISTRICT 2

ENTIRE COUNTIES

Clinton, Essex, Franklin, Hamilton, Jefferson, Lewis, Oneida, Onondaga, Oswego, St. Lawrence, Warren, Washington

WAGES

Per hour: 07/01/2025

Building	\$ 38.41
Heavy & Highway	41.91

NOTE ADDITIONAL PREMIUMS PAID FOR THE FOLLOWING WORK LISTED BELOW (amount subject to any overtime premiums):

- Certified Welders shall receive \$1.75 per hour in addition to the current Millwrights rate provided he/she is directed to perform certified welding.
- For Building work if a work site has been declared a hazardous site by the Owner and the use of protective gear (including, as a minimum, air purifying canister-type chemical respirators) are required, then that employee shall receive a \$1.50 premium per hour for Building work.
- For Heavy & Highway work if the work is performed at a State or Federally designated hazardous waste site where employees are required to wear protective gear, the employees performing the work shall receive an additional \$2.00 per hour over the millwright heavy and highway wage rate for all hours worked on the day protective gear was worn.
- An employee performing the work of a machinist shall receive \$2.00 per hour in addition to the current Millwrights rate. For the purposes of this premium to apply, a "machinist" is a person who uses a lathe, Bridgeport, milling machine or similar type of tool to make or modify parts.
- When performing work underground at 500 feet and below, the employee shall receive an additional \$1.00.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 27.50
---------------	----------

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

Note: Any holiday that falls on Sunday shall be observed the following Monday. Any holiday that falls on Saturday shall be observed the preceding Friday.

REGISTERED APPRENTICES

Wages per hour:

(1)year terms at the following percentage of Journeyworker's rate.

1st	2nd	3rd	4th
-----	-----	-----	-----

65% 75% 80% 90%

NOTE ADDITIONAL PREMIUMS PAID FOR THE FOLLOWING WORK LISTED BELOW (amount subject to any overtime premiums):

- Certified Welders shall receive \$1.75 per hour in addition to the current Millwrights rate provided he/she is directed to perform certified welding.
- For Building work if a work site has been declared a hazardous site by the Owner and the use of protective gear (including, as a minimum, air purifying canister-type chemical respirators) are required, then that employee shall receive a \$1.50 premium per hour for Building work.
- For Heavy & Highway work if the work is performed at a State or Federally designated hazardous waste site where employees are required to wear protective gear, the employees performing the work shall receive an additional \$2.00 per hour over the millwright heavy and highway wage rate for all hours worked on the day protective gear was worn.
- An employee performing the work of a machinist shall receive \$2.00 per hour in addition to the current Millwrights rate. For the purposes of this premium to apply, a "machinist" is a person who uses a lathe, Bridgeport, milling machine or similar type of tool to make or modify parts.
- When performing work underground at 500 feet and below, the employee shall receive an additional \$1.00.

SUPPLEMENTAL BENEFITS Benefits per hour:

Apprentices:

1st term	\$ 11.95
2nd term	22.84
3rd term	24.39
4th term	25.95

2-1163.2

Operating Engineer - Building

01/01/2026

JOB DESCRIPTION Operating Engineer - Building

DISTRICT 6

ENTIRE COUNTIES

Cayuga, Cortland, Jefferson, Lewis, Madison, Oneida, Onondaga, Oswego, Seneca, St. Lawrence, Tompkins

WAGES

NOTE:

---If a prime contract is let for site work only, meaning no buildings are involved in their site contract, the Heavy/Highway rates would be applicable. When a prime contract is let for site work and building excavation is part of that contract, the Building rates would be applicable for the Operators classification.

---In the event that equipment listed below is operated by robotic control, the classification covering the operation will be the same as if manually operated.

---If a second employee is required by the employer for operation of any covered machine, they shall be an Engineer Class C.

CLASS A1*: All Cranes (A1 Includes Boom Trucks over 5 tons, Cableway, Cherry Picker, Derrick, Dragline, Dredge, Overhead Crane, Pile Driver, Tower Crane**, Truck Crane, Whirlies).

CLASS A: Air Plako, Asphalt & Blacktop Roller, Automated Concrete Spreader (CMI or equivalent), Automated Fine Grade Machine (CMI), Backhoe, Barrel Shredder, Belt Placer, Blacktop Spreader (such as Barber-Greene & Blaw Knox), Blacktop Plant (automated), Blast or Rotary Drill (Truck or Cat mounted), Boom Trucks (5 ton and under), Burning Plant Operator, Caisson Auger, Central Mix Plant (automated), Concrete Pump, Crusher (Rock), De-watering Press, Diesel Power Unit, Dirt Filter Press with Operation Equipment, Dredge, Dual Drum Paver, Elevating Grader (self-propelled or towed), Elevator Hoist - Two Cage, Excavator - all purpose hydraulically operated, Forklift (Loed/Lull and other rough terrain type), Front End Loader (4 c.y. and over), Gradall, Grader (Power), Head Tower (Saurman or equal), Hoist (2 or 3 Drum), Hydroblaster (Laser Pump), Light Plants - Compressors and Generators, Locomotive, Maintenance Engineer, Maintenance Welder, Mine Hoist, Mucking Machine or Mole, Quarry Master or Equivalent, Refrigeration Equipment (for soil stabilization), Scraper, Sea Mule, Shovel, Side Boom, Slip Form Paver, Straddle Buggy (Ross Carrier, Lumber Carrier), Tractor Drawn Belt Type Loader (Euclid Loader), Trenching Machine (digging capacity of over 4ft. depth), Truck or Trailer Mounted Log Chipper (self-feeder), Tug Operator (Manned, rented equipment excluded), Tunnel Shovel, Vibro or Sonic Hammer Controls (when not mounted in proximity to Rig Operator), Work Boat Operator including LCM's.

CLASS B: "A" Frame Truck, Back Dumps, Blacktop Plant (non-automatic), Boring Machine, Bulldozer, Cage-Hoist, Central Mix Plant (non-automated), Compressor, Pump, Generator or Welding machine (when used in battery of not more than five (5)), Concrete Paver (single drum over 16'), Core boring machine, Drill Rigs - tractor mounted, Elevator - as material hoist, Farm Tractor (with or without accessories), Forklift (over 10 ton with or without attachments), Front End Loader (under 4 c.y.), Grout Pump, Gunit Machine, High Pressure Boiler (15 lbs. & over), Hoist (one drum), Hydraulic Breaking Hammer (Drop Hammer), Kolman Plant Loader (screening gravel), Maintenance Grease Man, Mixer for stabilized base - self-propelled (Seaman Mixer), Monorail Machine, Parapet Concrete or Pavement Grinder, Parts Man, Post Driver (truck or tractor mounted), Post Hole Digger (truck or tractor mounted), Power Sweeper (Wayne or similar), Pump-Crete or Squeeze-Crete, Road Widener (front end of Grader or self-propelled), Roller, Self-contained hydraulic bench drill, Shell Winder (motorized), Skid steer (Bobcat type loader), Snorkel (overhead arms), Snowblower control man, Tractor (with or without accessories), Trenching Machine (digging capacity of 4 ft. or less), Tugger Hoist, Vacuum Machine (self-propelled or mounted), Vibro Tamp, Well Drill / Well Point System (Submersible pumps when used in lieu of Well Point System), Winch (Motor driven), Winch Cat, Winch Truck.

CLASS C: Compressor (up to 500 cfm), Concrete Paver or Mixer (under 16'), Concrete Pavement Spreaders & Finishers (not automated), Conveyor (over 12 ft), Electric Submersible Pump (4" and over), Fine Grade Machine (not automated), Fireman, Forklift ("with or without" attachments, 10 ton and under), Form Tamper, Generator (2,500 watts and over), Hydraulic Pump, Mechanical Heaters (More than two (2) Mechanical Heaters or any Mechanical Heater or Heaters whose combined output exceeds 640,000 BTU per hour (manufacturer's rating) plus one self-contained heating unit - i.e. Sundog or Air Heat type - New Holland Hay Dryer type excluded), Mulching Machine, Oiler, Power Driven Welding Machine (300 amp and over, other than all electric. One Welding Machine under 300 amp will not require an engineer unless in a battery), Power Heaterman (hay dryer), Pumps (water and trash), Revinus Widener (road widener), Single Light Plant, Steam Cleaner or Jenny.

Per hour: 07/01/2025

Building	
Class A1*	\$ 49.61
Class A	48.11
Class B	45.99
Class C	41.77

Additional \$2.50 per hour if work requires Personal Protective Equipment for hazardous waste site activities with a level C or over rating.

(*) TONNAGE PREMIUMS:

All cranes up to 64 ton capacity - A1 rate
All cranes 65 ton to 110 ton capacity - A1 rate plus \$ 1.50
All cranes 111 ton to 199 ton capacity - A1 rate plus \$ 2.00
All cranes 200 ton to 399 ton capacity - A1 rate plus \$ 3.00
All cranes 400 ton to 599 ton capacity - A1 rate plus \$ 4.00
All cranes 600 ton to 799 ton capacity - A1 rate plus \$ 5.00
All cranes 800 ton to 999 ton capacity - A1 rate plus \$ 6.00
All cranes 1000 ton capacity and over - A1 rate plus \$ 7.00

(**) Tower Cranes - A1 rate plus \$2.50 (no tonnage premiums apply)

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker \$ 32.12

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: If the holiday falls on Sunday, it will be celebrated on Monday.

REGISTERED APPRENTICES

WAGES per hour: One thousand hour terms at the following percentage of Journeyworker's CLASS A wage:

1st: 60%
2nd: 65%
3rd: 70%
4th: 80%

Additional \$2.50 per hour if work requires Personal Protective Equipment for hazardous waste site activities with a level C or over rating.

SUPPLEMENTAL BENEFITS per hour:

07/01/2025

All terms: \$ 32.05

6-158-545b.s

Operating Engineer - Heavy&Highway

01/01/2026

JOB DESCRIPTION Operating Engineer - Heavy&Highway

DISTRICT 6

ENTIRE COUNTIES

Cayuga, Cortland, Jefferson, Lewis, Madison, Oneida, Onondaga, Oswego, Seneca, St. Lawrence, Tompkins

WAGES

NOTE:

---In the event that equipment listed below is operated by robotic control, the classification covering the operation will be the same as if manually operated.

---If a second employee is required by the employer for operation of any covered machine, they shall be an Engineer Class C.

CLASS A1*: All Cranes that require a NYS Crane License (Boom Truck, Cherry Picker, Derrick, Dragline, Overhead Crane (Gantry or Straddle Type), Pile Driver, Tower Cranes (including self-erecting)**, Truck Crane).

CLASS A: Asphalt Curb Machine (self-propelled, slipform); Asphalt Paver; Automated Concrete Spreader (CMI type); Automatic Fine Grader; Backhoe (except tractor mounted, rubber tired); Backhoe Excavator, Full Swing (CAT 212 or similar type); Back Filling Machine; Belt Placer (CMI type); Blacktop Plant (automated); Blacktop Roller; Bull Dozer being operated with active GPS; Cableway; Caisson Auger; Central Mix Concrete Plant (automated); Concrete Curb Machine (self-propelled, slipform); Concrete Pump; Cranes - listed in A1 that do not require a NYS Crane License; Directional Boring/Drilling Machine; Dredge; Dual Drum Paver; Excavator (all purpose-hydraulic, Gradall or similar); Front End Loader (4 cu. yd. & over); Head Tower (Sauerman or equal); Hoist (two or three drum); Holland Loader; Maintenance Engineer; Mine Hoist; Mucking Machine or Mole; Pavement Breaker (SP Wertgen; PB-4 and similar type); Profiler/Milling Machine (over 105 h.p.); Power Grader; Quad 9; Quarry Master (or equivalent); Rotating Telehandler; Scraper (including challenger type); Shovel; Side Boom; Slip Form Paver; Tractor Drawn Belt-Type Loader; Truck or Trailer Mounted Chipper (self-feeder); Tug Operator (manned rented equipment excluded); Tunnel Shovel.

CLASS B: Backhoe (tractor mounted, rubber tired); Bituminous Recycler Machine; Bituminous Spreader and Mixer; Blacktop Plant (non-automated); Blast or Rotary Drill (truck or tractor mounted); Boring Machine; Bridge Deck Finishing Machine; Brokk; Cage Hoist; Central Mix Plant (non-automated) and All Concrete Batching Plants; Concrete Paver (over 16'); Crawler Drill (self-contained); Crusher; Diesel Power Unit; Drill Rigs (truck or tractor mounted); Front End Loader (under 4 cu. yd.); Greaseman - Lubrication Engineer; HiPressure Boiler (15 lbs & over); Hoist (one drum); Hydro-Axe; Kolman Plant Loader & similar type loaders; Locomotive; Material Handling Knuckle Boom; Mini Excavators (under 18,000 lbs.); Mixer (for stabilized base, self-propelled); Monorail Machine; Profiler/Milling Machine (105 h.p. and under); Plant Engineer; Prentice Loader; Pug Mill; Pump Crete; Ready Mix Concrete Plant; Refrigeration Equipment (for soil stabilization); Road Widener; Roller (all above subgrade, See Class A for Blacktop Roller); Sea Mule; Self-contained ride-on Rock Drill (excluding Air-Track type drill); Skidder; Tractor with Dozer and/or Pusher; Trencher; Tugger Hoist; Vacuum Machine (mounted or towed); Vermeer Saws (ride-on, any size or type); Welder; Winch and Winch Cat; Work Boat Operator including L.C.M.'s.

CLASS C: "A" Frame Winch Hoist (On Truck); Aggregate Plant; Articulated Heavy Hauler; Asphalt or Concrete Grooving Machine (ride-on); Ballast Regulator (ride-on); Bituminous Heater (self-propelled); Boat (powered); Boiler (used in conjunction with production); Cement & Bin Operator; Compressors***; Concrete Pavement Spreader and Finisher; Concrete Paver or Mixer (16' & under); Concrete Saw (self-propelled); Conveyor; Deck Hand; Directional Boring/Drilling Machine Locator; Drill (Core); Drill (Well); Dust Collectors***; Electric Pump When Used in Conjunction with Well Point System; Farm Tractor with accessories; Fine Grade Machine; Fireman; Forklift; Form Tamper; Generators***; Grout Pump; Gunitite Machine; Hammers (hydraulic self-propelled); Heaters***; Hydra-Spiker (ride-on); Hydraulic Pump (jacking system); Hydro-Blaster (water); Light Plants***; Mulching Machine; Oiler; Parapet Concrete or Pavement Grinder; Post Hole Digger (excluding hand-held); Post Driver; Power Broom (towed); Power Heaterman; Power Sweeper; Pumps***; Revinius Widener; Roller (subgrade & fill); Scarifier (ride-on); Shell Winder; Skid Steer Loader (Bobcat or similar, including all attachments); Span Saw (ride-on); Steam Cleaner; Tamper (ride-on); Tie Extractor (ride-on); Tie Handlers (ride-on); Tie Inserters (ride-on); Tie Spacers (ride-on); Tire Repair; Track Liner (ride-on); Tractor; Tractor (with towed accessories); Vacuum Machine (self-propelled); Vibratory Compactor; Vibro Tamp; Welding Machines***; Well Point.

***CLASS C NOTE: Considered Hands-Off (unmanned). Includes only operation and maintenance of the equipment.

Per hour: 07/01/2025

H/H	
CLASS A1*	\$ 58.85
CLASS A	55.85
CLASS B	54.97
CLASS C	51.69

(*) TONNAGE PREMIUMS:

All cranes up to 64 ton capacity - A1 rate
All cranes 65 ton to 110 ton capacity - A1 rate plus \$ 1.50
All cranes 111 ton to 199 ton capacity- A1 rate plus \$ 2.00
All cranes 200 ton to 399 ton capacity - A1 rate plus \$ 3.00
All cranes 400 ton to 599 ton capacity - A1 rate plus \$ 4.00
All cranes 600 ton to 799 ton capacity - A1 rate plus \$ 5.00
All cranes 800 ton to 999 ton capacity - A1 rate plus \$ 6.00
All cranes 1000 ton capacity and over - A1 rate plus \$ 7.00

(**) Tower Cranes - A1 rate plus \$3.00 (no tonnage premiums apply)

- Cranes in Luffer Configuration - A1 rate plus \$ 5.00
- Cranes with external ballast (Tray or Wagon) - A1 rate plus \$ 5.00

Additional \$2.50 per hour for hazardous waste removal work on a State and/or Federally designated waste site which requires employees to wear Level C or above forms of personal protection.

SHIFT WORK

SINGLE IRREGULAR WORK SHIFT: Additional \$2.50 per hour for all employees who work a single irregular work shift starting from 5:00 PM to 1:00 AM that is mandated by the Contracting Agency.

SUPPLEMENTAL BENEFITS

Per hour: 07/01/2025

Journeyworker \$ 33.55

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: If a holiday falls on Sunday, it will be celebrated on Monday. If an employee works on this Monday, they shall be compensated at double time plus the holiday pay (triple time). If a holiday falls on a Saturday, employees who work a Saturday Holiday shall be paid double time plus the holiday pay.

REGISTERED APPRENTICES

WAGES per hour: One thousand hour terms at the following percentage of Journeyworker's CLASS B wage.

1st: 60%

2nd: 70%

3rd: 80%

4th: 90%

Additional \$2.50 per hour for hazardous waste removal work on a State and/or Federally designated waste site which requires employees to wear Level C or above forms of personal protection.

SUPPLEMENTAL BENEFITS per hour: Same as Journeyworker

6-158-545h

Operating Engineer - Survey Crew

01/01/2026

JOB DESCRIPTION Operating Engineer - Survey Crew

DISTRICT 12

ENTIRE COUNTIES

Albany, Allegany, Broome, Cayuga, Chemung, Chenango, Clinton, Columbia, Cortland, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Oneida, Onondaga, Ontario, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Warren, Washington, Wayne, Yates

PARTIAL COUNTIES

Dutchess: The northern portion of the county from the northern boundary line of the City of Poughkeepsie, north.

Genesee: Only the portion of the county that lies east of a line down the center of Route 98 to include all area that lies within the City of Batavia.

WAGES

These rates apply to Building, Tunnel and Heavy Highway.

Per hour:

SURVEY CLASSIFICATIONS:

Party Chief - One who directs a survey party.

Instrument Person - One who operates the surveying instruments.

Rod Person - One who holds the rods and assists the Instrument Person.

07/01/2025

Party Chief \$ 52.91

Instrument Person 48.67

Rod Person 36.29

Additional \$3.00/hr. for Tunnel Work

Additional \$2.50/hr. for Hazardous Work Site

SUPPLEMENTAL BENEFITS

Per hour worked:

Journeyman \$ 30.10

OVERTIME PAY

See (B, E, P, *X) on OVERTIME PAGE

*Note: \$25.10/Hr. Only for "ALL" premium hours paid when worked.

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

WAGES: 1000 hour terms based on the Percentage of Rod Persons Wage:

07/01/2025

0-1000	60%
1001-2000	70%
2001-3000	80%

SUPPLEMENTAL BENEFIT per hour worked:

0-1000	\$ 21.88 / PHP \$18.03
1001-2000	24.90 / " 20.45
2001-3000	27.93/ " 22.93

NOTE: PHP is premium hours paid when worked.

12-158-545 D.H.H.

Operating Engineer - Survey Crew - Consulting Engineer

01/01/2026

JOB DESCRIPTION Operating Engineer - Survey Crew - Consulting Engineer

DISTRICT 12

ENTIRE COUNTIES

Albany, Allegany, Broome, Cayuga, Chemung, Chenango, Clinton, Columbia, Cortland, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Oneida, Onondaga, Ontario, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Warren, Washington, Wayne, Yates

PARTIAL COUNTIES

Dutchess: The northern portion of the county from the northern boundary line of the City of Poughkeepsie, north.

Genesee: Only the portion of the county that lies east of a line down the center of Route 98 to include all area that lies within the City of Batavia.

WAGES

These rates apply to feasibility and preliminary design surveying, line and grade surveying for inspection or supervision of construction when performed under a Consulting Engineer Agreement.

Per hour:

SURVEY CLASSIFICATIONS:

Party Chief - One who directs a survey party.

Instrument Person - One who operates the surveying instruments.

Rod Person - One who holds the rods and assists the Instrument Person.

07/01/2025

Party Chief	\$ 52.91
Instrument Person	48.67
Rod Person	36.29

Additional \$3.00/hr. for Tunnel Work.

Additional \$2.50/hr. for EPA or DEC certified toxic or hazardous waste work.

SUPPLEMENTAL BENEFITS

Per hour worked:

Journeyman	\$ 30.10
------------	----------

OVERTIME PAY

See (B, E, Q, *X) on OVERTIME PAGE

*Note: \$25.10/Hr. Only for "ALL" premium hours paid when worked.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

WAGES: 1000 hour terms based on percentage of Rod Persons Wage:

07/01/2025

0-1000	60%
1001-2000	70%

2001-3000 80%

SUPPLEMENTAL BENEFIT per hour worked:

0-1000	\$ 21.88 / PHP \$18.03
1001-2000	\$ 24.90 / " 20.45
2001-3000	\$ 27.93 / " 22.93

NOTE: PHP is premium hours paid when worked.

12-158-545 DCE

Operating Engineer - Tunnel

01/01/2026

JOB DESCRIPTION Operating Engineer - Tunnel

DISTRICT 7

ENTIRE COUNTIES

Albany, Allegany, Broome, Cayuga, Chemung, Chenango, Clinton, Columbia, Cortland, Essex, Franklin, Fulton, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Oneida, Onondaga, Ontario, Oswego, Otsego, Rensselaer, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Warren, Washington, Wayne, Yates

PARTIAL COUNTIES

Dutchess: Northern part of Dutchess, to the northern boundary line of the City of Poughkeepie, then due east to Route 115 to Bedell Road, then east along Bedell Road to VanWagner Road, then north along VanWagner Road to Bower Road, then east along Bower Road to Rte. 44 east to Rte. 343, then along Rte. 343 east to the northern boundary of the Town of Dover Plains and east along the northern boundary of the Town of Dover Plains, to the borderline of the State of Connecticut.

Genesee: Only that portion of the county that lies east of a line drawn down the center of Route 98 and the entirety of the City of Batavia.

WAGES

CLASS A: Automatic Concrete Spreader (CMI Type); Automatic Fine Grader; Backhoe (except tractor mounted, rubber tired); Belt Placer (CMI Type); Blacktop Plant (automated); Cableway; Caisson Auger; Central Mix Concrete Plant (automated); Concrete Curb Machine (self-propelled slipform); Concrete Pump (8" or over); Dredge; Dual Drum Paver; Excavator; Front End Loader (4 cu. yd & over); Gradall; Head Tower (Sauerman or Equal); Hoist (shaft); Hoist (two or three Drum); Log Chipper/Loader (self-feeder); Maintenance Engineer (shaft and tunnel); any Mechanical Shaft Drill; Mine Hoist; Mining Machine(Mole and similar types); Mucking Machine or Mole; Overhead Crane (Gantry or Straddle Type); Pile Driver; Power Grader; Remote Controlled Mole or Tunnel Machine; Scraper; Shovel; Side Boom; Slip Form Paver (If a second man is needed, they shall be an Oiler); Tripper/Maintenance Engineer (shaft & tunnel); Tractor Drawn Belt-Type Loader; Tug Operator (manned rented equipment excluded); Tunnel Shovel.

CLASS B: Automated Central Mix Concrete Plant; Backhoe (topside); Backhoe (track mounted, rubber tired); Backhoe (topside); Bituminous Spreader and Mixer, Blacktop Plant (non-automated); Blast or Rotary Drill (truck or tractor mounted); Boring Machine; Cage Hoist; Central Mix Plant(non-automated); all Concrete Batching Plants; Compressors (4 or less exceeding 2,000 c.f.m. combined capacity); Concrete Pump; Crusher; Diesel Power Unit; Drill Rigs (tractor mounted); Front End Loader (under 4 cu. yd.); Grayco Epoxy Machine; Hoist (One Drum); Hoist (2 or 3 drum topside); Knuckle Boom material handler; Kolman Plant Loader & similar type Loaders (if employer requires another person to clean the screen or to maintain the equipment, they shall be an Oiler); L.C.M. Work Boat Operator; Locomotive; Maintenance Engineer (topside); Maintenance Grease Man; Mixer (for stabilized base-self-propelled); Monorail Machine; Plant Engineer; Personnel Hoist; Pump Crete; Ready Mix Concrete Plant; Refrigeration Equipment (for soil stabilization); Road Widener; Roller (all above sub-grade); Sea Mule; Shotcrete Machine; Shovel (topside); Tractor with Dozer and/or Pusher; Trencher; Tugger Hoist; Tunnel Locomotive; Vacuum Machine (mounted or towed); Welder; Winch; Winch Cat.

CLASS C: A Frame Truck; All Terrain Telescoping Material Handler; Ballast Regulator (ride-on); Compressors (4 not to exceed 2,000 c.f.m. combined capacity; or 3 or less with more than 1200 c.f.m. but not to exceed 2,000 c.f.m.); Compressors ((any size, but subject to other provisions for compressors), Dust Collectors, Generators, Pumps, Welding Machines, Light Plants (4 or any type combination)); Concrete Pavement Spreaders and Finishers; Conveyor; Drill (core); Drill (well); Electric Pump used in conjunction with Well Point System; Farm Tractor with Accessories; Fine Grade Machine; Fork Lift; Grout Pump (over 5 cu. ft.); Gunite Machine; Hammers (hydraulic-self-propelled); Hydra-Spiker (ride-on); Hydra-Blaster (water); Hydro-Blaster; Motorized Form Carrier; Post Hole Digger and Post Driver; Power Sweeper; Roller grade & fill); Scarifer (ride-on); Span-Saw (ride-on); Submersible Electric Pump (when used in lieu of well points); Tamper (ride-on); Tie-Extractor (ride-on), Tie Handler (ride-on), Tie Insertor (ride-on), Tie Spacer (ride-on); Track Liner (ride-on); Tractor with towed accessories; Vibratory Compactor; Vibro Tamp, Well Point.

CLASS D: Aggregate Plant; Cement & Bin Operator; Compressors (3 or less not to exceed 1,200 c.f.m. combined capacity); Compressors ((any size, but subject to other provisions for compressors), Dust Collectors, Generators, Pumps, Welding Machines, Light Plants (3 or less or any type or combination)); Concrete Saw (self-propelled); Form Tamper; Greaseman; Hydraulic Pump (jacking system); Junior Engineer; Light Plants; Mulching Machine; Oiler; Parapet Concrete or Pavement Grinder; Power Broom (towed); Power Heaterman (when used for production); Revinius Widener; Shell Winder; Steam Cleaner; Tractor.

Per hour: 07/01/2025

CLASS A	\$ 58.44
CLASS B	57.22
CLASS C	54.43
CLASS D	51.42

Additional \$5.00 per hour for Hazardous Waste Work on a state or federally designated hazardous waste site where the Operating Engineer is in direct contact with hazardous material and when personal protective equipment is required for respiratory, skin and eye protection.

CRANES:

Crane 1: All cranes, including self-erecting.

Crane 2: All Lattice Boom Cranes and all cranes with a manufacturer's rating of fifty (50) ton and over.

Crane 3: All hydraulic cranes and derricks with a manufacturer's rating of forty nine (49) ton and below, including boom trucks.

Crane 1	\$ 62.44
Crane 2	61.44
Crane 3	60.44

SUPPLEMENTAL BENEFITS

Per hour:

\$ 25.90
+ 10.10*

* This portion of the benefits subject to SAME PREMIUM as shown for overtime wages.

OVERTIME PAY

See (B, B2, E, Q, X) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: If a holiday falls on Sunday, it shall be observed on Monday.

REGISTERED APPRENTICES

WAGES:(1000) hours terms at the following percentage of Journeyworker's Class B wage.

1st term	60%
2nd term	65%
3rd term	70%
4th term	75%

SUPPLEMENTAL BENEFITS per hour: Same as Journeyworker

7-158-832TL.

Painter

01/01/2026

JOB DESCRIPTION Painter

DISTRICT 6

ENTIRE COUNTIES

Cayuga, Herkimer, Madison, Oneida, Onondaga, Seneca

PARTIAL COUNTIES

Lewis: Only the Townships of High Market, Lewis, Leyden, Lyonsdale, Osceola, Turin and West Turin.

Ontario: The City and Township of Geneva.

Oswego: Only the Townships of Amboy, Constantia, Williamstown and Oneida Lake.

WAGES

Per hour:	07/01/2025	05/01/2026 Additional
Basic Rate (Brush & Roll)	\$ 28.32	\$ 1.85*
Sign Painting	28.32	1.85*
Lead Based Paint Abatement	28.32	1.85*
Drywall Taper/ Finisher	29.32	1.85*
Wallcovering	29.32	1.85*
Drywall Machine Operator	29.82	1.85*
Spray	28.82	1.85*
Parking Lot, Hwy Striping	28.82	1.85*
Epoxy (Brush-Roller)	28.82	1.85*
Epoxy (Spray)	28.82	1.85*
Sandblasting (Operator)	28.82	1.85*
Boatswain Chair	28.82	1.85*
Swing Scaffold	28.82	1.85*
Structural Steel	28.82	1.85*
(except bridges, tanks, tunnel)		
Coal Tar epoxy	29.82	1.85*
Asbestos Encapsulation	30.52	1.85*

* To be allocated at a later date.

NOTE - SEE BRIDGE PAINTER RATES FOR BRIDGES, TANKS, OR TUNNELS.

SHIFT WORK

FOR ANY SHIFT WHICH STARTS PRIOR TO 6:00 AM OR AFTER 3:00 PM, ALL EMPLOYEES WHO WORK A SINGLE IRREGULAR WORK SHIFT ON GOVERNMENTAL MANDATED WORK SHALL BE PAID AN ADDITIONAL \$2.00 PER HOUR ABOVE THE APPLICABLE WAGE SCALE.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker \$ 27.20

OVERTIME PAY

See (B, *E2, F, R) on OVERTIME PAGE

* NOTE - On exterior work only.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: A holiday that falls on a Saturday will be celebrated on the preceding Friday. A holiday that falls on a Sunday will be celebrated on the following Monday.

REGISTERED APPRENTICES

WAGES per hour:

Painter/Decorator: 750 hour terms at the following wage rate:

1st	2nd	3rd	4th	5th	6th	7th	8th
\$ 18.00	\$ 18.50	\$ 19.00	\$ 19.50	\$ 20.00	\$ 21.00	\$ 22.00	\$ 23.00

Drywall Taper/ Finisher: 750 hour terms at the following wage rate:

1st	2nd	3rd	4th	5th	6th
\$ 20.00	\$ 20.50	\$ 21.00	\$ 21.50	\$ 22.00	\$ 23.00

SUPPLEMENTAL BENEFITS per hour:

Painter/Decorator:

1st	2nd	3rd	4th	5th	6th	7th	8th
\$ 6.50	\$ 6.50	\$ 7.50	\$ 7.50	\$ 10.50	\$ 10.50	\$ 13.00	\$ 13.00

Drywall Taper/ Finisher:

1st	2nd	3rd	4th	5th	6th
\$ 7.50	\$ 7.50	\$ 7.50	\$ 10.00	\$ 10.00	\$ 12.00

6-31

Painter

01/01/2026

JOB DESCRIPTION Painter

DISTRICT 3

ENTIRE COUNTIES

Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Cortland, Delaware, Erie, Genesee, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Wayne, Wyoming, Yates

WAGES

Per hour:	07/01/2025	05/01/2026
Bridge	\$ 46.19	Additional \$ 2.50
Tunnel	46.19	
Tank*	44.19	

For Bridge Painting Contracts, ALL WORKERS on and off the bridge (including Flagmen) are to be paid Painter's Rate; the contract must be ONLY for Bridge Painting.

*Tank rate applies to indoor and outdoor tanks, tank towers, standpipes, digesters, waste water treatment tanks, chlorinator tanks, etc. Covers all types of tanks including but not limited to steel tanks, concrete tanks, fiberglass tanks, etc.

SHIFT WORK

Note an additional \$1.50 per hour is required when the contracting agency or project specification requires any shift to start prior to 6:00am or after 12:00 noon.

SUPPLEMENTAL BENEFITS

Per hour:

\$ 31.51

OVERTIME PAY

Exterior work only See (B, E2, E4, F, R) on OVERTIME PAGE.

All other work See (B, F, R) on OVERTIME PAGE.

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour:

750 hour terms at the following wage:

1st	2nd	3rd	4th	5th	6th
\$ 24.00	\$ 26.00	\$ 28.00	\$ 30.00	\$ 34.00	\$ 38.00

Supplemental benefits per hour:

1st	2nd	3rd	4th	5th	6th
\$ 6.60	\$ 6.95	\$ 7.30	\$ 7.65	\$ 8.00	\$ 8.35

3-4-Bridge, Tunnel, Tank

Painter - Metal Polisher

01/01/2026

JOB DESCRIPTION Painter - Metal Polisher

DISTRICT 8

ENTIRE COUNTIES

Albany, Allegany, Bronx, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Kings, Lewis, Livingston, Madison, Monroe, Montgomery, Nassau, New York, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Queens, Rensselaer, Richmond, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Suffolk, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Westchester, Wyoming, Yates

WAGES

	07/01/2025
Metal Polisher	\$ 40.33
Metal Polisher*	41.43
Metal Polisher**	44.33

*Note: Applies on New Construction & complete renovation

** Note: Applies when working on scaffolds over 34 feet.

SUPPLEMENTAL BENEFITS

Per Hour: 07/01/2025

Journeyworker:	
All classification	\$ 13.44

OVERTIME PAY

See (B, E, P, T) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6, 11, 15, 16, 25, 26) on HOLIDAY PAGE
Overtime: See (5, 6, 11, 15, 16, 25, 26) on HOLIDAY PAGE

REGISTERED APPRENTICES

Wages per hour:

One (1) year term at the following wage rates:

07/01/2025

1st year	\$ 20.17
2nd year	22.18
3rd year	24.20
1st year*	\$ 20.56
2nd year*	22.62
3rd year*	24.74
1st year**	\$ 22.67
2nd year**	24.68
3rd year**	26.70

*Note: Applies on New Construction & complete renovation

** Note: Applies when working on scaffolds over 34 feet.

Supplemental benefits:

Per hour:

1st year	\$ 8.94
2nd year	8.94
3rd year	8.94

8-8A/28A-MP

Plumber

01/01/2026

JOB DESCRIPTION Plumber

DISTRICT 7

ENTIRE COUNTIES

Herkimer, Oneida

PARTIAL COUNTIES

Hamilton: Only the Town of Inlet.

Lewis: Towns of Lewis, Leyden, Lyonsdale, and West Turin.

Madison: Towns of Brookfield, Eaton, Fenner, Hamilton, Lebanon, Lenox, Lincoln, Madison, Nelson, Oneida, Smithfield, and Stockbridge.

Otsego: Towns of Cherry Valley, Exeter, Middlefield, Otsego, Plainfield, Richfield, Roseboom, and Springfield.

WAGES

Per hour:	07/01/2025	05/01/2026
		Additional
Plumber	\$ 45.93	\$ 3.45*
Steamfitter	45.93	3.45*

* To be allocated at a later date

SHIFT WORK

Agency-mandated shift operations:

1. Shift work shall start no earlier than 6AM Monday and will conclude no later than 9AM Saturday (overtime premiums applicable after 8 hours in a shift).
2. Single irregular shiftwork, less than 3 consecutive days will be paid at the rate of time and one-half of the regular hourly rate.
3. 3 consecutive work days or more:
 - First Shift - Regular hourly rate.
 - Second Shift - Regular hourly rate plus 12%.
 - Third Shift - Regular hourly rate plus 18%.

SUPPLEMENTAL BENEFITS

Per hour:

Journeyworker	\$ 15.15
	+ 18.67**

** This portion of the benefit is subject to the SAME PREMIUM as shown for overtime on projects over \$100 million in total construction cost (including engineering & architecture).

OVERTIME PAY

See (B, E, Q, *V) on OVERTIME PAGE

*Portion of supplemental benefits subject to V code when project cost is over \$100 million (including engineering & architecture).

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

NOTE: If a holiday falls on Sunday, it will be observed the following day. If a holiday falls on Saturday, it will be observed that day unless so determined by the Federal Government to be celebrated on a different day.

REGISTERED APPRENTICES

WAGES: Yearly terms at the following percentages of Journeyworker's wage.

1st	2nd	3rd	4th	5th
50%	55%	60%	70%	85%

SUPPLEMENTAL BENEFITS per hour:

1st Term:	\$ 15.15
	+ 8.92**

All others:	\$ 15.15
	+ 14.21**

** This portion of the benefit is subject to the SAME PREMIUM as shown for overtime on projects over \$100 million in total construction cost (including engineering & architecture).

7-112n-SF

Roofer	01/01/2026
---------------	-------------------

JOB DESCRIPTION Roofer

DISTRICT 6

ENTIRE COUNTIES

Cayuga, Cortland, Franklin, Herkimer, Jefferson, Lewis, Madison, Oneida, Onondaga, Oswego, Seneca, St. Lawrence

WAGES

Per hour:	07/01/2025	06/01/2026	06/01/2027
		Additional	Additional
Roofer, Waterproofer	\$ 35.80	\$ 2.00*	\$ 2.00*

* To be allocated at a later date.

NOTE - Does not include metal roof flashings, gravel stop, or metal roofing; See Sheetmetal Worker wage schedule.

Additional per hour:

Green Roofing**	\$ 0.25
Pitch Removal & Appl.	1.50
Asbestos Abatement	1.50

** Green Roofing is any component of green technology or living roof above the roof membrane including, but not limited to, the fabric, dirt and plantings.

SHIFT WORK

WHEN MANDATED BY THE OWNER OR CONTRACTING AGENCY, THERE IS AN ADDITIONAL PREMIUM OF \$4.00/HR FOR HOURS WORKED BEFORE 5:30AM AND AFTER 5:30PM.

SUPPLEMENTAL BENEFITS

Per hour:	
Journeyworker	\$ 26.30

Additional contribution on any Asbestos Abatement work	0.75
---	------

OVERTIME PAY

See (B, E, E2*, Q) on OVERTIME PAGE

*NOTE - If a holiday falls in that week and 32 hours were worked, Saturday will be paid at 1 1/2 times the rate.

HOLIDAY

Paid:	See (1) on HOLIDAY PAGE
Overtime:	See (5, 6) on HOLIDAY PAGE

NOTE: When any of these holidays falls on Sunday, the following day shall be observed as a holiday.

REGISTERED APPRENTICES

WAGES per hour: 1000 hour terms at the following percentage of the Journeyworker's wage:

1st term (0 to 999)	65%
2nd term (1000 to 1999)	70%
3rd term (2000 to 2999)	75%
4th term (3000 to 3999)	85%

Additional per hour:

Green Roofing**	\$ 0.25
Pitch Removal & Appl.	1.50
Asbestos Abatement	1.50

SUPPLEMENTAL BENEFITS per hour:

1st term	\$ 19.93
2nd term	21.85
3rd term	25.30
4th term	26.30

Additional contribution on any Asbestos Abatement work	\$ 0.75
---	---------

6-195

Sheetmetal Worker	01/01/2026
--------------------------	-------------------

JOB DESCRIPTION Sheetmetal Worker

DISTRICT 6

ENTIRE COUNTIES

Cayuga, Chenango, Cortland, Herkimer, Jefferson, Lewis, Madison, Oneida, Onondaga, Oswego, St. Lawrence

WAGES

Per hour:	07/01/2025	11/01/2025	05/01/2026 Additional	05/01/2027 Additional
Sheetmetal Worker:				
** (under \$10 million)	\$ 36.29	\$ 37.54	\$ 3.25*	\$ 3.25*
** (over \$10 million)	\$ 42.29	\$ 43.54	3.25*	3.25*

* To be allocated at a later date.

** For total cost of Sheetmetal contract only.

TO INCLUDE METAL ROOF FLASHINGS, GRAVEL STOP, AND METAL STANDING SEAM ROOFING.

SUPPLEMENTAL BENEFITS

Per hour:	07/01/2025	11/01/2025
Journeyworker	\$ 23.31	\$ 23.56

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

When any holiday falls on a Saturday, the Friday before such holiday shall be recognized as the legal holiday. Any holiday falling on Sunday, the following Monday shall be recognized as the legal holiday.

REGISTERED APPRENTICES

WAGES per hour: One year terms at the following percentage of the Journeyworker's wage.

1st	2nd	3rd	4th	5th
55%	60%	70%	75%	85%

SUPPLEMENTAL BENEFITS per hour:

	1st	2nd	3rd	4th	5th
07/01/2025	\$ 14.84	\$ 15.45	\$ 16.54	\$ 18.18	\$ 19.27
11/01/2025	\$ 15.11	\$ 15.70	\$ 16.79	\$ 18.43	\$ 19.52

6-58

Sprinkler Fitter

01/01/2026

JOB DESCRIPTION Sprinkler Fitter

DISTRICT 1

ENTIRE COUNTIES

Allegany, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Lewis, Livingston, Madison, Monroe, Montgomery, Niagara, Oneida, Onondaga, Ontario, Orleans, Oswego, Otsego, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Tioga, Tompkins, Washington, Wayne, Wyoming, Yates

WAGES

Per hour 07/01/2025

Sprinkler \$ 45.06
Fitter

SUPPLEMENTAL BENEFITS

Per hour

Journeyworker \$ 29.41

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

Note: When a holiday falls on Sunday, the following Monday shall be considered a holiday and all work performed on either day shall be at the double time rate. When a holiday falls on Saturday, the preceding Friday shall be considered a holiday and all work performed on either day shall be at the double time rate.

REGISTERED APPRENTICES

Wages per hour

One Half Year terms at the following wage.

1st	2nd	3rd	4th	5th	6th	7th	8th	9th	10th
\$ 23.28	\$ 25.98	\$ 28.15	\$ 30.31	\$ 31.94	\$ 34.64	\$ 36.81	\$ 38.97	\$ 41.14	\$ 43.30

Supplemental Benefits per hour

1st	2nd	3rd	4th	5th	6th	7th	8th	9th	10th
\$ 9.57	\$ 9.57	\$ 21.49	\$ 21.49	\$ 21.74	\$ 21.74	\$ 21.74	\$ 21.74	\$ 21.74	\$ 21.74
1-669									

Teamster - Building	01/01/2026
----------------------------	-------------------

JOB DESCRIPTION Teamster - Building

DISTRICT 1

ENTIRE COUNTIES

Hamilton, Herkimer, Oneida

PARTIAL COUNTIES

Chenango: Entire county except the Townships of Afton, Bainbridge, Coventry, Greene, Guilford, Oxford and Smithville.

Lewis: Only the Township of Grieg, Lewis, Leyden, Lowville, Lyonsdale, Martinsburg, Turin, West Turin and Watson.

Madison: Only the Townships of Brookfield, Eaton, Hamilton, Lebanon, Lincoln, Madison, Smithfield, Stockbridge and the City of Oneida

Otsego: Entire county EXCEPT Townships of Butternuts, Laurens, Maryland, Milford, Morris, Oneonta, Otego, Unidilla and Worcester.

WAGES

GROUP # A:

Straight trucks, winch, transit mix on the site, road oilers,
dump trucks, pick-ups, panel, water trucks, fuel trucks on the site
(including nozzle).

GROUP # B:

Low boy or Low boy trailer, Euclids or similar equipment.

WAGES per hour

07/01/2025

Group A \$ 34.65

Group B 34.95

SUPPLEMENTAL BENEFITS

Per hour

Journeyworker \$ 29.56

OVERTIME PAY

See (B, E, E2, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (1) on HOLIDAY PAGE

Overtime: See (5, 6) on HOLIDAY PAGE

Note: Any holiday which occurs on Sunday shall be observed the following Monday.

1-294z2

Teamster - Heavy&Highway	01/01/2026
-------------------------------------	-------------------

JOB DESCRIPTION Teamster - Heavy&Highway

DISTRICT 1

ENTIRE COUNTIES

Albany, Columbia, Fulton, Greene, Hamilton, Herkimer, Montgomery, Oneida, Rensselaer, Saratoga, Schenectady, Schoharie, Washington

PARTIAL COUNTIES

Chenango: Entire county except the Townships of Afton, Bainbridge, Coventry, Greene, Guilford, Oxford and Smithville.

Lewis: Only the Township of Grieg, Lewis, Leyden, Lowville, Lyonsdale, Martinsburg, Turin, West Turin and Watson.

Madison: Only the Townships of Brookfield, Eaton, Hamilton, Lebanon, Lincoln, Madison, Smithfield, Stockbridge and the City of Oneida

Otsego: Entire county EXCEPT Townships of Butternuts, Laurens, Maryland, Milford, Morris, Oneonta, Otego, Unidilla and Worcester.

Warren: Only the Townships of Bolton, Warrensburg, Thurman, Stony Creek, Luzerne, Caldwell (Lake George), and Queensbury.

WAGES

GROUP #1:

Warehousemen, Yardmen, Truck Helpers, Pickups, Panel Trucks, Flatboy Material Trucks(straight jobs), Single Axel Dump Trucks,
Dumpsters, Material Checkers and Receivers, Greasers, Truck Tiremen, Mechanics Helpers and Parts Chasers.

GROUP #2:

Tandems and Batch Trucks, Mechanics, Dispatcher.

GROUP #3:

Semi-Trailers, Low-boy Trucks, Asphalt Distributor Trucks, and Agitator, Mixer Trucks and dumpcrete type vehicles, Truck Mechanic, Fuel Trucks.

GROUP #4:

Specialized Earth Moving Equipment, Euclid type, or similar off-highway, where not self-loading, Straddle (Ross) Carrier, and self-contained concrete mobile truck.

GROUP #5:

Off-highway Tandem Back-Dump, Twin Engine Equipment and Double-Hitched Equipment where not self-loading.

WAGES per hour	07/01/2025	07/01/2026	07/01/2027
Group #1	\$ 41.78	\$43.79	\$45.79
Group #2	41.84	43.85	45.85
Group #3	41.93	43.94	45.95
Group #4	42.07	44.09	46.10
Group #5	42.24	44.26	46.28

Hazardous waste projects that require a Level C or greater protection shall be paid an additional \$ 1.00 per hour.

SHIFT WORK

All employees who work a single irregular work shift starting between 5pm and 1 am on governmental mandated night shifts shall be paid an additional \$2.50 per hour.

SUPPLEMENTAL BENEFITS

Per hour:

\$ 29.87	\$ 30.77	\$ 31.64
+\$1.00 per*	+\$1.00 per*	+\$1.00 per*
hour worked	hour worked	hour worked

(*) not applicable to paid holidays

OVERTIME PAY

See (B, E, Q) on OVERTIME PAGE

HOLIDAY

Paid: See (5, 6) on HOLIDAY PAGE
Overtime: See (5, 6) on HOLIDAY PAGE

1-294h/h

Welder

01/01/2026

JOB DESCRIPTION Welder

DISTRICT 1

ENTIRE COUNTIES

Albany, Allegany, Bronx, Broome, Cattaraugus, Cayuga, Chautauqua, Chemung, Chenango, Clinton, Columbia, Cortland, Delaware, Dutchess, Erie, Essex, Franklin, Fulton, Genesee, Greene, Hamilton, Herkimer, Jefferson, Kings, Lewis, Livingston, Madison, Monroe, Montgomery, Nassau, New York, Niagara, Oneida, Onondaga, Ontario, Orange, Orleans, Oswego, Otsego, Putnam, Queens, Rensselaer, Richmond, Rockland, Saratoga, Schenectady, Schoharie, Schuyler, Seneca, St. Lawrence, Steuben, Suffolk, Sullivan, Tioga, Tompkins, Ulster, Warren, Washington, Wayne, Westchester, Wyoming, Yates

WAGES

Per hour 07/01/2025

Welder: To be paid the same rate of the mechanic performing the work.*

*EXCEPTION: If a specific welder certification is required, then the 'Certified Welder' rate in that trade tag will be paid.

OVERTIME PAY

HOLIDAY

1-As Per Trade

Overtime Codes

Following is an explanation of the code(s) listed in the OVERTIME section of each classification contained in the attached schedule. Additional requirements may also be listed in the HOLIDAY section.

NOTE: Supplemental Benefits are 'Per hour worked' (for each hour worked) unless otherwise noted

- (AA) Time and one half of the hourly rate after 7 and one half hours per day
- (A) Time and one half of the hourly rate after 7 hours per day
- (B) Time and one half of the hourly rate after 8 hours per day
- (B1) Time and one half of the hourly rate for the 9th & 10th hours week days and the 1st 8 hours on Saturday.
Double the hourly rate for all additional hours
- (B2) Time and one half of the hourly rate after 40 hours per week
- (B3) Time and one half of the hourly rate after 40 straight hours per week
- (C) Double the hourly rate after 7 hours per day
- (C1) Double the hourly rate after 7 and one half hours per day
- (D) Double the hourly rate after 8 hours per day
- (D1) Double the hourly rate after 9 hours per day
- (E) Time and one half of the hourly rate on Saturday
- (E1) Time and one half 1st 4 hours on Saturday; Double the hourly rate all additional Saturday hours
- (E2) Saturday may be used as a make-up day at straight time when a day is lost during that week due to inclement weather
- (E3) Between November 1st and March 3rd Saturday may be used as a make-up day at straight time when a day is lost during that week due to inclement weather, provided a given employee has worked between 16 and 32 hours that week
- (E4) Sunday may be used as a make-up day at straight time when a day is lost during that week due to inclement weather
- (E5) Double time after 8 hours on Saturdays
- (F) Time and one half of the hourly rate on Saturday and Sunday
- (G) Time and one half of the hourly rate on Saturday and Holidays
- (H) Time and one half of the hourly rate on Saturday, Sunday, and Holidays
- (I) Time and one half of the hourly rate on Sunday
- (J) Time and one half of the hourly rate on Sunday and Holidays
- (K) Time and one half of the hourly rate on Holidays
- (L) Double the hourly rate on Saturday
- (M) Double the hourly rate on Saturday and Sunday
- (N) Double the hourly rate on Saturday and Holidays
- (O) Double the hourly rate on Saturday, Sunday, and Holidays
- (P) Double the hourly rate on Sunday
- (Q) Double the hourly rate on Sunday and Holidays
- (R) Double the hourly rate on Holidays

- (S) Two and one half times the hourly rate for Holidays
- (S1) Two and one half times the hourly rate the first 8 hours on Sunday or Holidays One and one half times the hourly rate all additional hours.
- (T) Triple the hourly rate for Holidays
- (U) Four times the hourly rate for Holidays
- (V) Including benefits at SAME PREMIUM as shown for overtime
- (W) Time and one half for benefits on all overtime hours.
- (X) Benefits payable on Paid Holiday at straight time. If worked, additional benefit amount will be required for worked hours. (Refer to other codes listed.)

Holiday Codes

PAID Holidays:

Paid Holidays are days for which an eligible employee receives a regular day's pay, but is not required to perform work. If an employee works on a day listed as a paid holiday, this remuneration is in addition to payment of the required prevailing rate for the work actually performed.

OVERTIME Holiday Pay:

Overtime holiday pay is the premium pay that is required for work performed on specified holidays. It is only required where the employee actually performs work on such holidays. The applicable holidays are listed under HOLIDAYS: OVERTIME. The required rate of pay for these covered holidays can be found in the OVERTIME PAY section listings for each classification.

Following is an explanation of the code(s) listed in the HOLIDAY section of each classification contained in the attached schedule. The Holidays as listed below are to be paid at the wage rates at which the employee is normally classified.

- | | |
|--------|---|
| (1) | None |
| (2) | Labor Day |
| (3) | Memorial Day and Labor Day |
| (4) | Memorial Day and July 4th |
| (5) | Memorial Day, July 4th, and Labor Day |
| (6) | New Year's, Thanksgiving, and Christmas |
| (7) | Lincoln's Birthday, Washington's Birthday, and Veterans Day |
| (8) | Good Friday |
| (9) | Lincoln's Birthday |
| (10) | Washington's Birthday |
| (11) | Columbus Day |
| (12) | Election Day |
| (13) | Presidential Election Day |
| (14) | 1/2 Day on Presidential Election Day |
| (15) | Veterans Day |
| (16) | Day after Thanksgiving |
| (17) | July 4th |
| (18) | 1/2 Day before Christmas |
| (19) | 1/2 Day before New Years |
| (20) | Thanksgiving |
| (21) | New Year's Day |
| (22) | Christmas |
| (23) | Day before Christmas |
| (24) | Day before New Year's |
| (25) | Presidents' Day |
| (26) | Martin Luther King, Jr. Day |
| (27) | Memorial Day |
| (28) | Easter Sunday |

(29) Juneteenth

New York State Department of Labor - Bureau of Public Work
State Office Building Campus
Building 12 - Room 130
Albany, New York 12226

REQUEST FOR WAGE AND SUPPLEMENT INFORMATION

As Required by Articles 8 and 9 of the NYS Labor Law

Fax (518) 485-1870 or mail this form for new schedules or for determination for additional occupations.

This Form Must Be Typed

Submitted By:

(Check Only One)

☐

Contracting Agency

☐

Architect or Engineering Firm

☐

Public Work District Office

Date:

A. Public Work Contract to be let by: (Enter Data Pertaining to Contracting/Public Agency)

1. Name and complete address ☐ (Check if new or change)

Telephone

Fax

E-Mail:

2. NY State Units (see Item 5).

☐ 01 DOT

☐ 02 OGS

☐ 03 Dormitory Authority

☐ 04 State University
Construction Fund

☐ 05 Mental Hygiene
Facilities Corp.

☐ 06 OTHER N.Y. STATE UNIT

☐ 07 City

☐ 08 Local School District

☐ 09 Special Local District, i.e.,
Fire, Sewer, Water District

☐ 10 Village

☐ 11 Town

☐ 12 County

☐ 13 Other Non-N.Y. State
(Describe)

3. SEND REPLY TO ☐ (check if new or change)
Name and complete address:

Telephone

Fax

E-Mail:

4. SERVICE REQUIRED. Check appropriate box and provide project information.

☐ New Schedule of Wages and Supplements.

APPROXIMATE BID DATE :

☐ Additional Occupation and/or Redetermination

PRC NUMBER ISSUED PREVIOUSLY FOR
THIS PROJECT :

OFFICE USE ONLY

B. PROJECT PARTICULARS

5. Project Title _____

Description of Work _____

Contract Identification Number _____

Note: For NYS units, the OSC Contract No. _____

6. Location of Project:
Location on Site _____

Route No/Street Address _____

Village or City _____

Town _____

County _____

7. Nature of Project - Check One:

☐

1. New Building

☐

2. Addition to Existing Structure

☐

3. Heavy and Highway Construction (New and Repair)

☐

4. New Sewer or Waterline

☐

5. Other New Construction (Explain)

☐

6. Other Reconstruction, Maintenance, Repair or Alteration

☐

7. Demolition

☐

8. Building Service Contract

8. OCCUPATION FOR PROJECT :

☐ Construction (Building, Heavy
Highway/Sewer/Water)

☐ Tunnel

☐ Residential

☐ Landscape Maintenance

☐ Elevator maintenance

☐ Exterminators, Fumigators

☐ Fire Safety Director, NYC Only

☐ Fuel Delivery

☐ Guards, Watchmen

☐ Janitors, Porters, Cleaners,
Elevator Operators

☐ Moving furniture and
equipment

☐ Trash and refuse removal

☐ Window cleaners

☐ Other (Describe)

9. Does this project comply with the Wicks Law involving separate bidding? YES ☐ NO ☐

10. Name and Title of Requester

Signature



NEW YORK STATE DEPARTMENT OF LABOR
Bureau of Public Work - Debarment List

**LIST OF EMPLOYERS INELIGIBLE TO BID ON OR BE
AWARDED ANY PUBLIC WORK CONTRACT**

Under Article 8 and Article 9 of the NYS Labor Law, a contractor, sub-contractor and/or its successor shall be debarred and ineligible to submit a bid on or be awarded any public work or public building service contract/sub-contract with the state, any municipal corporation or public body for a period of five (5) years from the date of debarment when:

- Two (2) final determinations have been rendered within any consecutive six-year (6) period determining that such contractor, sub-contractor and/or its successor has WILLFULLY failed to pay the prevailing wage and/or supplements;
- One (1) final determination involves falsification of payroll records or the kickback of wages and/or supplements.

The agency issuing the determination and providing the information, is denoted under the heading 'Fiscal Officer'. DOL = New York State Department of Labor; NYC = New York City Comptroller's Office; AG = New York State Attorney General's Office; DA = County District Attorney's Office.

Debarment Database: To search for contractors, sub-contractors and/or their successors debarred from bidding or being awarded any public work contract or subcontract under NYS Labor Law Articles 8 and 9, or under NYS Workers' Compensation Law Section 141-b, access the database at this link: <https://apps.labor.ny.gov/EDList/searchPage.do>

For inquiries please call 518-457-5589.

NYSDOL Bureau of Public Work Debarment List 01/09/2026

Article 8

AGENCY	Fiscal Officer	FEIN	EMPLOYER NAME	EMPLOYER DBA NAME	ADDRESS	DEBARMENT START DATE	DEBARMENT END DATE
DOL	DOL	*****5754	0369 CONTRACTORS, LLC		515 WEST AVE UNIT PH 13NORWALK CT 06850	05/12/2021	05/12/2026
DOL	DOL	*****5784	A.J.M. TRUCKING, INC.		PO BOX 2064 MONROE NY 10950	02/12/2024	02/12/2029
DOL	DOL		AKHLAQ OULAKH		4307 28TH AVE ASTORIA NY 11103	10/11/2024	10/11/2029
DOL	DOL		ALEXANDER DELISA		411 THEODORE FREMND SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	NYC		ALL COUNTY SEWER & DRAIN, INC.		7 GREENFIELD DR WARWICK NY 10990	03/25/2022	03/25/2027
DOL	DOL	*****8387	AMERICAN PAVING & MASONRY, CORP.		8 FOREST AVE GLEN COVE NY 11542	05/24/2024	05/24/2029
DOL	DOL	*****8654	AMERICAN PAVING, INC.		8 FORREST AVE. GLEN COVE NY 11542	05/24/2024	05/24/2029
DOL	NYC		AMJED PARVEZ		401 HANOVER AVENUE STATEN ISLAND NY 10304	01/11/2021	01/11/2026
DOL	DOL		ANGELO GARCIA		515 WEST AVE UNIT PH 13NORWALK CT 06850	05/12/2021	05/12/2026
DOL	DOL		ANGELO STANCO		8 FOREST AVE. GLEN COVE NY 11542	05/24/2024	05/24/2029
DOL	DOL		ANGELO TONDO		449 WEST MOMBSHA ROAD MONROE NY 10950	06/06/2022	06/06/2027
DOL	DOL	*****4231	ANKER'S ELECTRIC SERVICE, INC.		10 SOUTH 5TH ST LOCUST VALLEY NY 11560	09/26/2022	09/26/2027
DOL	DOL		ANTHONY CASALE		20 HEATHER RIDGE ROAD TROY NY 12180	05/20/2025	05/20/2030
DOL	DOL		ANTHONY MONGELLI		PO BOX 2064 MONROE NY 10950	02/12/2024	02/12/2029
DOL	DOL	*****8421	B & B DRYWALL, INC		206 WARREN AVE APT 1WHITE PLAINS NY 10603	12/14/2021	12/14/2026
DOL	NYC	*****2113	BHW CONTRACTING, INC.		401 HANOVER AVENUE STATEN ISLAND NY 10304	01/11/2021	01/11/2026
DOL	DA	*****2404	BJA RENOVATION, CORP		33 DOLLARD DR NORTH BABYLON NY 11703	03/19/2025	03/19/2030
DOL	DOL	*****5078	BLACK RIVER TREE REMOVAL, LLC		29807 ANDREWS ROAD BLACK RIVER NY 13032	10/17/2023	10/17/2028
DOL	DOL		C.M.C CONTRACTORS, INC.		500 WEST PUTNAM AVE SUITE 400GREENWICH CT 06830	09/03/2025	09/03/2030
DOL	DOL	*****5161	CALADRI DEVELOPMENT CORP.		1223 PARK ST. PEEKSKILL NY 10566	05/17/2021	05/17/2026
DOL	DOL	*****3391	CALI ENTERPRISES, INC.		1223 PARK STREET PEEKSKILL NY 10566	05/17/2021	05/17/2026
DOL	DOL		CARLOS F. ESCOBAR		411 THEODORE FREMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL		CARLOS FIGUEROA		411 THEODORE FREMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL	*****4155	CASA BUILDERS, INC.	FRIEDLANDER CONSTRUCTI ON	64 N PUTT CONNERS ROAD NEW PALTZ NY 12561	05/10/2023	05/10/2028
DOL	AG	*****7247	CENTURY CONCRETE CORP		2375 RAYNOR ST RONKONKOMA NY 11779	08/04/2021	08/04/2026
DOL	DOL		CESAREO TULA		120 SEARS AVE ELMSFORD NY 10523	09/26/2025	09/26/2030
DOL	DOL	*****2292	CHAMPION MAINTENANCE CONTRACTORS, INC.		211 SOUTH RIDGE STREET RYE BROOK NY 10573	09/03/2025	09/03/2030
DOL	NYC	*****2117	CHARAN ELECTRICAL ENTERPRISES		9-11 40TH AVENUE LONG ISLAND CITY NY 11101	09/26/2023	09/26/2028
DOL	DOL		CHARLES CASALE		55 MAIN AVENUE WYNANTSKILL NY 12198	05/20/2025	05/20/2030
DOL	DOL		CHARLES CASALE		55 MAIN AVENUE WYNANTSKILL NY 12198	05/20/2025	05/20/2030
DOL	DOL		CHRISTOPHER GRECO		26 NORTH MYRTLE AVENUE SPRING VALLEY NY 10956	02/18/2021	02/18/2026
DOL	DOL		CHRISTOPHER PEROSI		5507 NESCONSET HIGHWAY MT. SINAI NY 11766	07/17/2025	07/17/2030
DOL	DOL	*****2281	CORRAO TRUCKING, INC.		PO BOX 393 NANUET NY 10954	09/17/2024	09/17/2029
DOL	DOL		CRAIG JOHANSEN		10 SOUTH 5TH ST LOCUST VALLEY NY 11560	09/26/2022	09/26/2027

NYSDOL Bureau of Public Work Debarment List 01/09/2026

Article 8

DOL	DOL	*****3228	CROSS-COUNTY LANDSCAPING AND TREE SERVICE, INC.	ROCKLAND TREE SERVICE	26 NORTH MYRTLE AVENUE SPRING VALLEY NY 10956	02/18/2021	02/18/2026
DOL	DOL	*****7619	DANCO CONSTRUCTION UNLIMITED INC.		485 RAFT AVENUE HOLBROOK NY 11741	10/19/2021	10/19/2026
DOL	DOL		DANIEL DELISA		211 SOUTH RIDGE STREET RYE BROOK NY 10573	09/03/2025	09/03/2030
DOL	DOL		DANIEL ROBERT MCNALLY		7 GREENFIELD DRIVE WARWICK NY 10990	03/25/2022	03/25/2027
DOL	DOL		DARWIN PEGUESE		6400 BALTIMORE NATIONAL SUITE 602CANTONSVILLE NY 21228	10/24/2024	10/24/2029
DOL	DOL		DAVID FRIEDLANDER		64 NORTH PUTT CORNERS RD NEW PALTZ NY 12561	05/10/2023	05/10/2028
DOL	DOL		DENISE NAGLE		36 OAKWOOD TRAIL S AL MONROE NY 10950	10/29/2025	10/29/2030
DOL	DOL		DINA TAYLOR		64 N PUTT CONNERS RD NEW PALTZ NY 12561	05/10/2023	05/10/2028
DOL	AG		EDWIN HUTZLER		23 NORTH HOWELLS RD BELLPORT NY 11713	08/04/2021	08/04/2026
DOL	DA		EDWIN HUTZLER		2375 RAYNOR STREET RONKONKOMA NY 11779	08/04/2021	08/04/2026
DOL	DOL	*****2337	EGL DRAINAGE SOLUTION & REPAIRS LLC		5507 NESCONSET HIGHWAY MT. SINAI NY 11766	07/17/2025	07/17/2030
DOL	DOL	*****0780	EMES HEATING & PLUMBING CONTR		5 EMES LANE MONSEY NY 10952	01/20/2002	01/20/3002
DOL	DOL		EMIL KISZKO		84 DIAMOND ST BROOKLYN NY 11222	07/18/2024	07/18/2029
DOL	DOL	*****3298	EMJACK CONSTRUCTION CORP.		84 DIAMOND ST BROOKLYN NY 11222	07/18/2024	07/18/2029
DOL	DOL	*****3298	EMJACK CONSTRUCTION LLC		4192 SIR ANDREW CIRCLE DOYLESTOWN PA 18902	07/18/2024	07/18/2029
DOL	DOL		EUGENIUSZ "GINO" KUCHAR		195 KINGSLAND AVE BROOKLYN NY 11222	12/22/2023	12/22/2028
DOL	DA		FREDERICK HUTZLER		2375 RAYNOR STREET RONKONKOMA NY 11779	08/04/2021	08/04/2026
DOL	DOL	*****2998	G.E.M. AMERICAN CONSTRUCTION CORP.		195 KINGSLAND AVE BROOKLYN NY 11222	12/22/2023	12/22/2028
DOL	DA		GEORGE LUCEY		150 KINGS STREET BROOKLYN NY 11231	01/19/1998	01/19/2998
DOL	DA		GIOVANNA TRAVALJA		3735 9TH ST LONG ISLAND CITY NY 11101	01/05/2023	01/05/2028
DOL	DA		GIOVANNI NAPOLITANO		2501 BAYVIEW AVENUE WANTAGH NY 11793	02/21/2024	02/21/2029
DOL	DA	*****0213	GORILLA CONTRACTING GROUP, LLC		505 MANHATTAN AVE WEST BABYLON NY 11704	10/05/2023	10/05/2028
DOL	DA	*****4760	GTX CONSTRUCTION ASSOCIATES, CORP		2501 BAYVIEW AVE WANTAGH NY 11793	02/21/2024	02/21/2029
DOL	DOL		HENRY WICKE A/K/A HENRY WICKE, JR.		36 OAKWOOD TRAIL S AL MONROE NY 10950	10/29/2025	10/29/2030
DOL	DOL		HERBERT CLEMEN		42 FOWLER AVENUE CORTLAND MANOR NY 10567	01/24/2023	01/24/2028
DOL	DOL		HERBERT CLEMEN		42 FOWLER AVENUE CORTLAND MANOR NY 10567	10/25/2022	10/25/2027
DOL	DOL	*****6961	HUNTER ELEVATOR COMPANY, INC.		36 OAKWOOD TRAIL S AL MONROE NY 10950	10/29/2025	10/29/2030
DOL	DOL	*****2397	ISLAND BREEZE MARINE, INC.		6400 BALTIMORE NATIONAL CANTONSVILLE MD 21228	10/24/2024	10/24/2029
DOL	DOL	*****5010	J. LINDSLEY ENTERPRISE, LLC		1002 STATE ROUTE 176 FULTON NY 13069	07/30/2025	07/30/2030
DOL	DOL	*****0241	J. LINDSLEY ROOFING, LLC		211 NORTH 2ND STREET FULTON NY 13069	07/30/2025	07/30/2030
DOL	DOL	*****9211	J. WASE CONSTRUCTION CORP.		8545 RT 9W ATHENS NY 12015	03/09/2021	03/09/2026
DOL	DOL		J.M.J CONSTRUCTION		151 OSTRANDER AVENUE SYRACUSE NY 13205	11/21/2022	11/21/2027
DOL	DOL		J.R. NELSON CONSTRUCTION		531 THIRD STREET ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL		J.R. NELSON CONSTRUCTION		531 THIRD STREET ALBANY NY 12206	12/22/2022	12/22/2027
DOL	DOL		J.R. NELSON CONSTRUCTION		531 THIRD STREET ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL		J.R. NELSON, LLC		531 THIRD STREET ALBANY NY 12206	12/22/2022	12/22/2027

NYSDOL Bureau of Public Work Debarment List 01/09/2026

Article 8

DOL	DOL		J.R. NELSON, LLC		531 THIRD STREET ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL		J.R. NELSON, LLC		531 THIRD STREET ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL		J.R.N COMPANIES, LLC		531 THIRD STREET ALBANY NY 12206	12/12/2022	12/12/2027
DOL	DOL		J.R.N COMPANIES, LLC		531 THIRD STREET ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL		J.R.N COMPANIES, LLC		531 THIRD STREET ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL	*****1147	J.R.N. CONSTRUCTION, LLC		531 THIRD ST ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL	*****1147	J.R.N. CONSTRUCTION, LLC		531 THIRD ST ALBANY NY 12206	12/22/2022	12/22/2027
DOL	DOL	*****1147	J.R.N. CONSTRUCTION, LLC		531 THIRD ST ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL		JAMES J. BAKER		7901 GEE ROAD CANASTOTA NY 13032	08/17/2021	08/17/2026
DOL	DOL		JAMES LINDSLEY		211 NORTH 2ND STREET FULTON NY 13069	07/30/2025	07/30/2030
DOL	DOL		JASON P. RACE		3469 STATE RT. 69 PERISH NY 13131	09/29/2021	09/29/2026
DOL	DOL		JASON P. RACE		3469 STATE RT. 69 PERISH NY 13131	02/09/2022	02/09/2027
DOL	DOL		JASON P. RACE		3469 STATE RT. 69 PERISH NY 13131	11/15/2022	11/15/2027
DOL	DOL		JASON P. RACE		3469 STATE RT. 69 PERISH NY 13131	03/01/2022	03/01/2027
DOL	DOL	*****7993	JBS DIRT, INC.		7901 GEE ROAD CANASTOTA NY 13032	08/17/2021	08/17/2026
DOL	DOL	*****2435	JEFFEL D. JOHNSON	JMJ7 AND SON	5553 CAIRNSTRAIL CLAY NY 13041	11/21/2022	11/21/2027
DOL	DOL		JEFFEL JOHNSON ELITE CARPENTER REMODEL AND CONSTRUCTION		C2 EVERGREEN CIRCLE LIVERPOOL NY 13090	11/21/2022	11/21/2027
DOL	DOL	*****2435	JEFFREY M. JOHNSON	JMJ7 AND SON	5553 CAIRNS TRAIL CLAY NY 13041	11/21/2022	11/21/2027
DOL	DOL		JENNIFER LINDSLEY		211 NORTH 2ND STREET FULTON NY 13069	07/30/2025	07/30/2030
DOL	DOL		JERRY DASTON		36 OAKWOOD TRAIL S AL MONROE NY 10950	10/29/2025	10/29/2030
DOL	DOL		JIM PLAUGHER		17613 SANTE FE LINE ROAD WAYNEFIELD OH 45896	07/16/2021	07/16/2026
DOL	DOL		JMJ7 & SON CONSTRUCTION, LLC		5553 CAIRNS TRAIL LIVERPOOL NY 13041	11/21/2022	11/21/2027
DOL	DOL		JMJ7 AND SONS CONTRACTORS		5553 CAIRNS TRAIL CLAY NY 13041	11/21/2022	11/21/2027
DOL	DOL		JMJ7 CONTRACTORS		7014 13TH AVENUE BROOKLYN NY 11228	11/21/2022	11/21/2027
DOL	DOL		JMJ7 CONTRACTORS AND SONS		5553 CAIRNS TRAIL CLAY NY 13041	11/21/2022	11/21/2027
DOL	DOL		JMJ7 CONTRACTORS, LLC		5553 CAIRNS TRAIL CLAY NY 13041	11/21/2022	11/21/2027
DOL	DOL		JOHN MARKOVIC		47 MANDON TERRACE HAWTHORN NJ 07506	03/29/2021	03/29/2026
DOL	DOL		JOHN NAGLE A/K/A JOHN NAGLE, JR.		36 OAKWOOD TRAIL S AL MONROE NY 10950	10/29/2025	10/29/2030
DOL	DOL		JOHN WASE		8545 RT 9W ATHENS NY 12015	03/09/2021	03/09/2026
DOL	DOL		JONATHAN DELISA		411 THEODORE FREMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL		JORGE FIGUEROA		411 THEODORE FRMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL		JORGE RAMOS		8970 MIKE GARCIA DR MANASSAS VA 20109	07/16/2021	07/16/2026
DOL	DA		JOSEPH DEMASCO		33 DOLLARD DRIVE NORTH BABYLON NY 11703	03/19/2025	03/19/2030
DOL	DOL		JOSEPH HALL		937 US ROUTE 11 CENTRAL SQUARE NY 13036	10/21/2024	10/21/2029
DOL	DOL	*****2271	JOSEPH HALL COMPANIES LLC		937 US ROUTE 11 CENTRAL SQUARE NY 13036	10/21/2024	10/21/2029
DOL	DOL		JOSEPH K. SALERNO		1010 TILDEN AVE UTICA NY 13501	07/24/2023	07/24/2028
DOL	DOL		JOSEPH K. SALERNO II		1010 TILDEN AVE UTICA NY 13501	07/24/2023	07/24/2028

NYSDOL Bureau of Public Work Debarment List 01/09/2026

Article 8

DOL	DOL	*****5116	JP RACE PAINTING, INC. T/A RACE PAINTING		3469 STATE RT. 69 PERISH NY 13131	02/09/2022	02/09/2027
DOL	DOL	*****5116	JP RACE PAINTING, INC. T/A RACE PAINTING		3469 STATE RT. 69 PERISH NY 13131	11/15/2022	11/15/2027
DOL	DOL	*****5116	JP RACE PAINTING, INC. T/A RACE PAINTING		3469 STATE RT. 69 PERISH NY 13131	09/29/2021	09/29/2026
DOL	DOL	*****5116	JP RACE PAINTING, INC. T/A RACE PAINTING		3469 STATE RT. 69 PERISH NY 13131	03/01/2022	03/01/2027
DOL	DOL	*****5116	JP RACE PAINTING, INC. T/A RACE PAINTING		3469 STATE RT. 69 PERISH NY 13131	03/01/2022	03/01/2027
DOL	DOL		JRN CONSTRUCTION CO, LLC		1024 BROADWAY ALBANY NY 12204	11/07/2023	11/07/2028
DOL	DOL	*****1147	JRN CONSTRUCTION, LLC		531 THIRD STREET ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL	*****1147	JRN CONSTRUCTION, LLC		531 THIRD STREET ALBANY NY 12206	12/22/2022	12/22/2027
DOL	DOL	*****1147	JRN CONSTRUCTION, LLC		531 THIRD STREET ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL		JRN PAVING, LLC		531 THIRD STREET ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL		JRN PAVING, LLC		531 THIRD STREET ALBANY NY 12206	12/22/2022	12/22/2027
DOL	DOL		JRN PAVING, LLC		531 THIRD STREET ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL		JULIUS AND GITA BEHREND		5 EMES LANE MONSEY NY 10952	11/20/2002	11/20/3002
DOL	DOL		KATE E. CONNOR		7088 INTERSTATE ISLAND RD SYRACUSE NY 13209	03/31/2021	03/31/2026
DOL	DOL		KEAN INDUSTRIES, LLC		2345 RT. 52 SUITE 2NHOPEWELL JUNCTION NY 12533	12/18/2023	12/18/2028
DOL	DOL	*****2959	KELC DEVELOPMENT, INC		7088 INTERSTATE ISLAND RD SYRACUSE NY 13209	03/31/2021	03/31/2026
DOL	DOL		KEVIN FUNEZ URBINA A/K/A KEVIN FUNEZ		1009 LYNDAL AVE TRENTON NJ 08629	12/16/2024	12/16/2029
DOL	DOL		KIMBERLY F. BAKER		7901 GEE ROAD CANASTOTA NY 13032	08/17/2021	08/17/2026
DOL	DOL	*****8760	KJ&J CONSTRUCTION, LLC		1009 LYNDAL AVE TRENTON NJ 08629	12/16/2024	12/16/2029
DOL	DOL		KMA GROUP II, INC.		29-10 38TH AVENUE LONG ISLAND CITY NY 11101	10/11/2023	10/11/2028
DOL	DOL	*****1833	KMA GROUP INC.		29-10 38TH AVENUE LONG ISLAND CITY NY 11101	10/11/2023	10/11/2028
DOL	DOL		KMA INSULATION, INC.		29-10 38TH AVENUE LONG ISLAND CITY NY 11101	10/11/2023	10/11/2028
DOL	DOL		KRIN HEINEMANN		2345 ROUTE 52, SUITE 2N HOPEWELL JUNCTION NY 12533	12/18/2023	12/18/2028
DOL	NYC		KULWANT S. DEOL		9-11 40TH AVENUE LONG ISLAND CITY NY 11101	09/26/2023	09/26/2028
DOL	DA	*****8816	LAKE CONSTRUCTION AND DEVELOPMENT CORPORATION		150 KINGS STREET BROOKLYN NY 11231	08/19/1998	08/19/2998
DOL	DOL		LEROY E. NELSON JR		531 THIRD ST ALBANY NY 12206	10/25/2022	10/25/2027
DOL	DOL		LEROY E. NELSON JR		531 THIRD ST ALBANY NY 12206	12/22/2022	12/22/2027
DOL	DOL		LEROY E. NELSON JR		531 THIRD ST ALBANY NY 12206	11/07/2023	11/07/2028
DOL	DOL	*****3716	LIGHTNIN ELECTRIC INC.		3418 NORTHERN BLVD SUITE 5-27LONG ISLAND CITY NY 11101	12/13/2024	12/13/2029
DOL	AG	*****3291	LINTECH ELECTRIC, INC.		3006 TILDEN AVE BROOKLYN NY 11226	02/16/2022	02/16/2027
DOL	DOL		LIZETTE PONCE		411 THEODORE FREMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL		LOUIS A. CALICCHIA		1223 PARK ST. PEEKSKILL NY 10566	05/17/2021	05/17/2026
DOL	DOL	*****2196	MAINSTREAM SPECIALTIES, INC.		11 OLD TOWN RD SELKIRK NY 12158	02/02/2021	02/02/2026
DOL	DA		MANUEL P TOBIO		150 KINGS STREET BROOKLYN NY 14444	08/19/1998	08/19/2998
DOL	DA		MANUEL TOBIO		150 KINGS STREET BROOKLYN NY 11231	08/19/1998	08/19/2998

NYSDOL Bureau of Public Work Debarment List 01/09/2026

Article 8

DOL	DOL	*****1320	MJC MASON CONTRACTING, INC.		42 FOWLER AVENUE CORTLAND MANOR NY 10567	10/25/2022	10/25/2027
DOL	DOL	*****1320	MJC MASON CONTRACTING, INC.		42 FOWLER AVENUE CORTLAND MANOR NY 10567	01/24/2023	01/24/2028
DOL	DOL		MOHAMMAD MIAN		8269 21ST ST BELLEROSE NY 11426	12/22/2022	12/22/2027
DOL	NYC		NASEER CHAUDHRY		2349 BRAGG STREET BROOKLYN NY 11229	04/22/2025	04/22/2030
DOL	DOL	*****7790	NATIONAL BUILDING & RESTORATION CORP		1010 TILDEN AVE UTICA NY 13501	07/24/2023	07/24/2028
DOL	DOL	*****1797	NATIONAL CONSTRUCTION SERVICES, INC		1010 TILDEN AVE UTICA NY 13501	07/24/2023	07/24/2028
DOL	NYC		NAVIT SINGH		402 JERICHO TURNPIKE NEW HYDE PARK NY 11040	08/10/2022	08/10/2027
DOL	DOL		NELCO CONTRACTING, LLC		1024 BROADWAY ALBANY NY 12204	11/07/2023	11/07/2028
DOL	DA		NICHOLAS BARNETT		33 DOLLARD DR BABYLON NY 11703	03/04/2025	03/04/2030
DOL	DOL		NICHOLAS RAO		411 THEODORE FREMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DA		NICHOLAS T. ANALITIS		505 MANHATTAN AVE WEST BABYLON NY 11704	10/05/2023	10/05/2028
DOL	DOL		NICHOLE E. FRASER A/K/A NICHOLE RACE		3469 STATE RT. 69 PERISH NY 13131	03/01/2022	03/01/2027
DOL	DOL		NICHOLE E. FRASER A/K/A NICHOLE RACE		3469 STATE RT. 69 PERISH NY 13131	11/15/2022	11/15/2027
DOL	DOL		NICHOLE E. FRASER A/K/A NICHOLE RACE		3469 STATE RT. 69 PERISH NY 13131	09/29/2021	09/29/2026
DOL	DOL		NICHOLE E. FRASER A/K/A NICHOLE RACE		3469 STATE RT. 69 PERISH NY 13131	02/09/2022	02/09/2027
DOL	DOL		NIKOLA NTONI		3418 NORTHERN BLVD SUITE 5-27LONG ISLAND CITY NY 11101	12/13/2024	12/13/2029
DOL	NYC	*****6971	NN CONSTRUCTION, INC.		2349 BRAGG STREET BROOKLYN NY 11229	04/22/2025	04/22/2030
DOL	NYC	*****5643	NYC LINE CONTRACTORS, INC.		402 JERICHO TURNPIKE NEW HYDE PARK NY 11040	08/10/2022	08/10/2027
DOL	DOL		PATRICK PENNACCHIO		2345 RT. 52 SUITE 2NHOPWELL JUNCTION NY 12533	12/18/2023	12/18/2028
DOL	DOL		PATRICK PENNACCHIO		2345 RT. 52 SUITE 2NHOPWELL JUNCTION NY 12533	12/18/2023	12/18/2028
DOL	DOL		PAULINE CHAHALES		935 S LAKE BLVD MAHOPAC NY 10541	03/02/2021	03/02/2026
DOL	DOL		PETER STEVENS		11 OLD TOWN ROAD SELKIRK NY 12158	02/02/2021	02/02/2026
DOL	DOL	*****4168	PHANTOM CONSTRUCTION CORP.		95-27 116TH STREET QUEENS NY 11419	07/12/2024	07/12/2029
DOL	DOL	*****4168	PHANTOM CONSTRUCTION CORP.		95-27 116TH STREET QUEENS NY 11419	05/28/2024	05/28/2029
DOL	DOL	*****4772	R.W. LOBDELL CONSTRUCTION LLC		635 WEST DRYDEN ROAD FREEVILLE NY 13068	01/31/2025	01/31/2030
DOL	DOL	*****2633	RAW POWER ELECTRIC CORP.		3 PARK CIRCLE MIDDLETOWN NY 10940	07/11/2022	07/11/2027
DOL	DOL		ROBBYE BISSESAR		89-51 SPRINGFIELD BLVD QUEENS VILLAGE NY 11427	01/11/2003	01/11/3003
DOL	DOL		ROMEO WARREN		161 ROBYN RD MONROE NY 10950	07/11/2022	07/11/2027
DOL	DOL		ROSA GARCIA		411 THEODORE FRMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL	*****7172	RZ & AL INC.		198 RIDGE AVENUE VALLEY STREAM NY 11581	06/06/2022	06/06/2027
DOL	DOL		SAL FRESINA MASONRY CONTRACTORS, INC.		1935 TEALL AVENUE SYRACUSE NY 13206	07/16/2021	07/16/2026
DOL	DOL		SAL MASONRY CONTRACTORS, INC.		(SEE COMMENTS) SYRACUSE NY 13202	07/16/2021	07/16/2026
DOL	DOL	*****9874	SALFREE ENTERPRISES INC		P.O BOX 14 2821 GARDNER RDPOMPEI NY 13138	07/16/2021	07/16/2026
DOL	DOL		SALVATORE A FRESINA A/K/A SAM FRESINA		107 FACTORY AVE P.O BOX 11070SYRACUSE NY 13218	07/16/2021	07/16/2026
DOL	DOL		SAM FRESINA		107 FACTORY AVE P.O BOX 11070SYRACUSE NY 13218	07/16/2021	07/16/2026

NYSDOL Bureau of Public Work Debarment List 01/09/2026

Article 8

DOL	DA	*****0476	SAMCO ELECTRIC CORP.		3735 9TH ST LONG ISLAND CITY NY 11101	01/05/2023	01/05/2028
DOL	DA		SILVANO TRAVAJA		3735 9TH ST LONG ISLAND CITY NY 11101	01/05/2023	01/05/2028
DOL	DOL	*****0440	SOLAR GUYS INC.		8970 MIKE GARCIA DR MANASSAS VA 20109	07/16/2021	07/16/2026
DOL	NYC	*****3661	SPANIER BUILDING MAINTENANCE CORP		200 OAK DRIVE SYOSSET NY 11791	03/14/2022	03/14/2027
DOL	DOL		STANADOS KALOGELAS		485 RAFT AVENUE HOLBROOK NY 11741	10/19/2021	10/19/2026
DOL	DOL	*****3496	STAR INTERNATIONAL INC		89-51 SPRINGFIELD BLVD QUEENS VILLAGE NY 11427	08/11/2003	08/11/3003
DOL	DOL	*****9528	STEEL-IT, LLC.		17613 SANTE FE LINE ROAD WAYNESFIELD OH 45896	07/16/2021	07/16/2026
DOL	DOL		STEVEN DELISA		411 THEODORE FREMND AVE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL	*****3800	SUBURBAN RESTORATION CO. INC.		5-10 BANTA PLACE FAIR LAWN PLACE NJ 07410	03/29/2021	03/29/2026
DOL	DOL	*****9150	SURGE INC.		8269 21ST STREET BELLEROSE NY 11426	12/22/2022	12/22/2027
DOL	DOL		SYED MUHAMMAD S. JAFRI A/K/A SHARRUKH JAFRI		4307 28TH AVE ASTORIA NY 11103	10/11/2024	10/11/2029
DOL	DOL		SYED RAZA		198 RIDGE AVENUE NY 11581	06/06/2022	06/06/2027
DOL	DOL		TARLOK SINGH		95-27 116TH STREET QUEENS NY 11419	05/28/2024	05/28/2029
DOL	DOL		TARLOK SINGH		95-27 116TH STREET QUEENS NY 11419	07/12/2024	07/12/2029
DOL	DOL	*****4855	TECH INDUSTRIES LLC		20 HEATHER RIDGE ROAD TROY NY 12180	05/20/2025	05/20/2030
DOL	DOL	*****9733	TERSAL CONSTRUCTION SERVICES INC		107 FACTORY AVE P.O BOX 11070SYRACUSE NY 13208	07/16/2021	07/16/2026
DOL	DOL		TERSAL CONTRACTORS, INC.		221 GARDNER RD P.O BOX 14POMPEI NY 13138	07/16/2021	07/16/2026
DOL	DOL		TERSAL DEVELOPMENT CORP.		1935 TEALL AVENUE SYRACUSE NY 13206	07/16/2021	07/16/2026
DOL	DOL	*****2426	THE MATRUKH GROUP, INC.		4307 28TH AVE PO BOX 9082ASTORIA NY 11103	10/11/2024	10/11/2029
DOL	DOL		THOMAS LOBDELL		635 WEST DRYDEN ROAD FREEVILLE NY 13068	01/31/2025	01/31/2030
DOL	DOL		TIMOTHY PERCY		29807 ANDREWS ROAD BLACK RIVER NY 13612	10/17/2023	10/17/2028
DOL	DA	*****1050	TRI STATE CONSTRUCTION OF NY CORP.		50-39 175TH PLACE FRESH MEADOWS NY 11365	03/28/2022	03/28/2027
DOL	DA	*****4106	TRIPLE H CONCRETE CORP		2375 RAYNOR STREET RONKONKOMA NY 11779	08/04/2021	08/04/2026
DOL	DOL	*****8485	TULA PLUMBING AND HEATING LLC		120 SEARS AVE ELMSFORD NY 10523	09/26/2025	09/26/2030
DOL	DOL	*****8210	UPSTATE CONCRETE & MASONRY CONTRACTING CO INC		449 WEST MOMBSHA ROAD MONROE NY 10950	06/06/2022	06/06/2027
DOL	DOL		VINCENT CORRAO		PO BOX 393 NANUET NY 10954	09/17/2024	09/17/2029
DOL	DOL	*****8266	WILLIAM CHRIS MCCLENDON	MCCLENDON ASPHALT PAVING	1646 FALLS STREET NIAGARA FALLS NY 14303	05/01/2023	05/01/2028
DOL	DOL		WILLIAM CHRIS MCCLENDON		1646 FALLS STREET NIAGARA FALLS NY 14303	05/01/2023	05/01/2028
DOL	DOL		WILLIAM G. PROERFRIEDT		85 SPRUCEWOOD ROAD WEST BABYLON NY 11704	01/19/2021	01/19/2026
DOL	DOL	*****5924	WILLIAM G. PROPHY, LLC	WGP CONTRACTIN G, INC.	54 PENTAQUIT AVE BAYSHORE NY 11706	01/19/2021	01/19/2026
DOL	DOL		WILLIAM SCRIVENS		4192 SIR ANDREW CIRCLE DOYELSTOWN PA 18902	07/18/2024	07/18/2029
DOL	DOL	*****9494	WND CONSTRUCTION LLC		411 THEODORE FREMD AVENUE SUITE 206RYE NY 10580	09/03/2025	09/03/2030
DOL	DOL		XENOFON EFTHIMIADIS		29-10 38TH AVENUE LONG ISLAND CITY NY 11101	10/11/2023	10/11/2028

Appendix A

Right of Way Clearance Certificate

APPENDIX 11-5
RIGHT OF WAY CLEARANCE CERTIFICATE FOR PSE

To: Regional Real Estate Officer, 2 Date: 04-28-26 Design Approval Date: 07-15-25
Region From: Edward Smith P.E. Sponsor: Oneida County
P.I.N.: 2754.83 Project: Simmons Road over Dix Brook
Sponsor ID: _____ Acquiring Agency: Town of Augusta

I certify that; the right-of-way has been or will be acquired in accordance with the Highway Law, the Eminent Domain Procedure Law (when applicable), Uniform Relocation Assistance Real Property Acquisition Policies Act of 1970 as amended, and Title 23 of the Code of Federal Regulations, Part 635, Section 309 and that the status of the right-of-way is as follows:

Select: a, b, c, or d

☐ (a) No right of way (including clearance of encroachments conflicting with the project construction within the existing right of way) is required for the project.

☒ (b) All of the necessary rights of way, including control of access rights have been acquired (legal and physical possession). All payments/deposits are completed. If applicable, "Statement of Donations" attached. There are no improvements existing that need to be removed or demolished and/or all occupants have vacated the land and/or improvements and the acquiring agency has the physical possession and the right to remove.

☐ (c) All the necessary rights of way, including control of access rights have not been completed, however, the acquisitions are being progressed and all legal and physical possession will be completed prior to advertisement of the contract (see attached ROW 9-15ALL "Acquisition and Clearance Status Report" for completion schedule).

☐ (d) Acquisition of one or more remaining properties has not been completed and will not be completed prior to project advertisement for bids. All eligible occupants of the residences, if any, on such properties have had replacement housing made available to them in accordance with 49 CFR 24.204. (See attached ROW 9-15ALL "Acquisition and Clearance Status Report" for completion schedule and ROW 9-16ALL "Special Note – Availability of ROW"). The completion schedule will be included in the contract plans, engineering substantiation and a report of the quantity and quality of relocation assistance. A note designating the lack of availability shall appear on the specific plan sheet of each indicated property. FHWA approval of this (these) projection(s) is required. (Reasons property may not be available include acquisitions of properties in bankruptcy, acquisitions from cemeteries, acquisitions from the federal/state government, and relocations.)

Project Information:

No. of Maps required for project:	<u>2</u>	No. of Relocations completed:	<u>0</u>
No. of Claimants:	<u>2</u>	No. of Maps paid to date:	<u>2</u>
No. of Maps not requiring payment:	<u>0</u>	No. of Maps deposited to date:	<u>0</u>
No. of Relocations:	<u>0</u>		

Completed Project Checklist and Property Checklist must be attached.

Responsible Local Official:

Title: Deputy Commissioner, Oneida Cty. DPW
Name: Edward Smith, P.E.
Signature: Edward Smith
Date: 1 May 2026

NYSDOT Real Estate Officer:

Name: Rebecca K. Jackson
Signature: Rebecca K. Jackson
Date: June 8, 2026

Appendix B

Environmental Permits



PERMIT
Under the Environmental Conservation Law (ECL)

Permittee and Facility Information

Permit Issued To:
ONEIDA COUNTY
800 PARK AVE

UTICA, NY 13501-2939
(315) 793-6269

Facility Application Contact:
Jeffrey Dora
5999 Judd Rd

ORISKANY, NY 13424
(315) 793-6269

Facility:
Simmons Rd over Dix Brook
Simmons Rd|Approximately 1/2 mile north of the
Rottamore Rd. intersection
Augusta, NY 13477

Facility Permit Contact:
Daniel A Eckert
MJ Engineering, Architecture, Landscape
Architecture, and Land Surveying, P.C.
21 Corporate Dr.
Clifton Park, NY 12065
(518) 371-0799

Facility Location: in AUGUSTA in ONEIDA COUNTY

Facility Principal Reference Point: NYTM-E: 458.5121144648211 NYTM-N:
4763.20143577709

Latitude: 43°01'13.3" Longitude: 75°30'33.0"

Project Location: Simmons Rd approximately 2400' north of the Rottamore Rd intersection

Authorized Activity: Remove and replace existing culvert. The replacement culvert will be 28' 2" long by 14' span by 7' rise with concrete wingwalls. Stone aprons will be placed at the inlet and outlet of the culvert. The culvert will be embedded to a minimum of 20% of the opening height. Dix Brook will be realigned to better convey the channel under Simmons Road. Approximately 110 linear feet of stream disturbance will occur. Approximately .12 acres of permanent disturbance, and .28 acres of temporary disturbance, will occur in the 100 foot regulated adjacent area of a NYS Regulated Freshwater Wetland.

Permit Authorizations

Stream Disturbance - Under Article 15, Title 5

Permit ID 6-3022-00052/00001

New Permit

Effective Date: 11/26/2025

Expiration Date: 11/25/2030

Freshwater Wetlands - Under Article 24

Permit ID 6-3022-00052/00002

New Permit

Effective Date: 11/26/2025

Expiration Date: 11/25/2030



NYSDEC Approval

By acceptance of this permit, the permittee agrees that the permit is contingent upon strict compliance with the ECL, all applicable regulations, and all conditions included as part of this permit.

Permit Administrator: TODD J PHILLIPS, Deputy Regional Permit Administrator
Address: NYSDEC Region 6 Utica Sub-Office
State Office Bldg - 207 Genesee St
Utica, NY 13501 -2885

Authorized Signature: Todd J. Phillips Date 11/26/2025

Distribution List

Daniel A Eckert
Jeffrey Dora
US ARMY CORPS OF ENGINEERS - BUFFALO DISTRICT
Law Enforcement
Town of Augusta
STEVE O CASE, JR

Permit Components

NATURAL RESOURCE PERMIT CONDITIONS

GENERAL CONDITIONS, APPLY TO ALL AUTHORIZED PERMITS

NOTIFICATION OF OTHER PERMITTEE OBLIGATIONS

Permit Attachments

Drawings/Blueprints
Site Plan

11/21/2025
11/21/2025



**NATURAL RESOURCE PERMIT CONDITIONS - Apply to the Following
Permits: STREAM DISTURBANCE; FRESHWATER WETLANDS**

- 1. Notify DEC of Commencement of Work and Completion of Work** The permittee shall notify the Department at least seven days prior to project commencement and within seven days of project completion. Each notification is to be made by e-mailing the region's Bureau of Ecosystem Health at R6BEH@dec.ny.gov or by telephone at 315-793-2404 during the Department's normal business hours (8:30 am to 4:45 pm), and providing the name of the permittee and the Permit ID(s) as listed in the Permit Authorization section of this permit.
- 2. Conformance With Plans** All activities authorized by this permit must be in strict conformance with the approved plans submitted by the applicant or applicant's agent as part of the permit application. Such approved plans were prepared by MJ Engineering and received November 21, 2025.
- 3. Failure to Meet Permit Conditions** Failure of the permittee to meet all the conditions of this permit is a violation of this permit and grounds for an order to immediately cease the permitted activity at the project site.
- 4. Prohibition Period for Trout** All instream work, as well as any work that may result in the suspension of sediment, is prohibited during the trout spawning and incubation period commencing October 1 and ending May 15.
- 5. Minimize Bed/Bank Disturbance** Disturbance to the bed and banks of Dix Brook shall be kept to the minimum necessary to complete the project.
- 6. Minimize Adverse Impacts to Wetlands, Wildlife, Water** All work must be performed in a manner which minimizes adverse impacts to wetlands, wildlife, water quality and natural resources.
- 7. Maintain Water Flow During Work** During periods of work activity, sufficient flow of water shall be maintained at all times to sustain aquatic life downstream.
- 8. Water Clarity** Stream reaches downstream of construction areas shall always remain as clear (non-turbid) as the reaches upstream of the construction areas.
- 9. No Equipment in the Water** Heavy equipment operation in the water is prohibited. With backhoes and similar heavy equipment, the bucket may enter the water.
- 10. Control Erosion During Construction** Provisions shall be made to minimize erosion during the construction of the project and to prevent increased sedimentation in any water body on or adjacent to the project.
- 11. Siltation Prevention Measures** Siltation prevention measures, such as silt fencing, sediment traps or settling basins, shall be installed and maintained during the project, to prevent movement of silt and turbid waters from the project site into any watercourse, stream, water body or wetland.
- 12. Silt Screen Around Wetland Area** Prior to commencement of any construction activities, a continuous line of silt screen (maximum opening size of U.S. Sieve #20) shall be staked along the upland edge of the wetland adjacent area.



13. Maintain Silt Screen The screen shall be maintained, repaired and replaced as often as necessary to ensure proper function, until all disturbed areas are permanently vegetated. Sediments trapped by the screen shall be removed to an approved upland location before the screen is removed.

14. Install Culvert in the Dry The culvert shall be installed in the dry. This may require pumping or piping the stream flow around the work area. The pump discharge shall be adequately protected to prevent stream bed and/or bank erosion.

15. Install Culvert below Existing Streambed Grade The bottom of the culvert shall be installed at a depth of a minimum of 20% of the culvert opening below the existing streambed elevation at the site. The streambed material that was excavated to accommodate this placement shall then be spread evenly throughout the bottom of the new culvert.

16. Flow Through Culvert Before Backfilling The entire stream flow shall be diverted through the culvert before commencing backfilling of the culvert.

17. Restore Area Around Culvert Upon completion of work, the areas of disturbed streambed adjacent to the culvert (both ends) shall be restored to approximate pre-existing conditions.

18. Stabilize Disturbed Areas All areas of soil disturbance resulting from this project shall be stabilized immediately following project completion or prior to permit expiration, whichever comes first. The approved methodologies are as follows:

- a. Stabilization of the entire disturbed area with appropriate vegetation (grasses, etc.).
- b. Stabilized as per specifications identified on approved plans.
- c. Temporarily stabilized with straw mulch or jute matting or other similar natural fiber matting within 1 week of final grading. Temporary stabilization shall be maintained until a mature vegetative cover is established.

19. Disposal of Material Any demolition debris, excess construction materials, and/or excess excavated materials shall be immediately and completely disposed of on an approved upland site more than 100 feet from any regulated waterbody or wetland. These materials shall be suitably stabilized so as not to re-enter any water body, wetland, or wetland adjacent area; and must be disposed of in accordance with all local, state, and federal statutes, regulations, or ordinances.

20. No Rock From Stream/Lake No rock for use in construction is to come from the stream bed.

21. Floodplain Regulations The project must meet all local and federal floodplain regulations.

22. Human or Archaeological Remains If any human remains or archaeological remains are encountered during excavation, the permittee must immediately cease, or cause to cease, all work in the area of the remains and notify

Regional Permit Administrator
NYSDEC Region 6 Headquarters
State Office Building - 317 Washington St
Watertown, NY13601

Work shall not resume until written permission to do so has been received from the Department.



23. State Not Liable for Damage The State of New York shall in no case be liable for any damage or injury to the structure or work herein authorized which may be caused by or result from future operations undertaken by the State for the conservation or improvement of navigation, or for other purposes, and no claim or right to compensation shall accrue from any such damage.

24. State May Order Removal or Alteration of Work If future operations by the State of New York require an alteration in the position of the structure or work herein authorized, or if, in the opinion of the Department of Environmental Conservation it shall cause unreasonable obstruction to the free navigation of said waters or flood flows or endanger the health, safety or welfare of the people of the State, or cause loss or destruction of the natural resources of the State, the owner may be ordered by the Department to remove or alter the structural work, obstructions, or hazards caused thereby without expense to the State, and if, upon the expiration or revocation of this permit, the structure, fill, excavation, or other modification of the watercourse hereby authorized shall not be completed, the owners, shall, without expense to the State, and to such extent and in such time and manner as the Department of Environmental Conservation may require, remove all or any portion of the uncompleted structure or fill and restore to its former condition the navigable and flood capacity of the watercourse. No claim shall be made against the State of New York on account of any such removal or alteration.

25. State May Require Site Restoration If upon the expiration or revocation of this permit, the project hereby authorized has not been completed, the applicant shall, without expense to the State, and to such extent and in such time and manner as the Department of Environmental Conservation may lawfully require, remove all or any portion of the uncompleted structure or fill and restore the site to its former condition. No claim shall be made against the State of New York on account of any such removal or alteration.

26. Precautions Against Contamination of Waters All necessary precautions shall be taken to preclude contamination of any wetland or waterway by suspended solids, sediments, fuels, solvents, lubricants, epoxy coatings, paints, concrete, leachate or any other environmentally deleterious materials associated with the project.



GENERAL CONDITIONS - Apply to ALL Authorized Permits:

1. Facility Inspection by The Department The permitted site or facility, including relevant records, is subject to inspection at reasonable hours and intervals by an authorized representative of the Department of Environmental Conservation (the Department) to determine whether the permittee is complying with this permit and the ECL. Such representative may order the work suspended pursuant to ECL 71- 0301 and SAPA 401(3).

The permittee shall provide a person to accompany the Department's representative during an inspection to the permit area when requested by the Department.

A copy of this permit, including all referenced maps, drawings and special conditions, must be available for inspection by the Department at all times at the project site or facility. Failure to produce a copy of the permit upon request by a Department representative is a violation of this permit.

2. Relationship of this Permit to Other Department Orders and Determinations Unless expressly provided for by the Department, issuance of this permit does not modify, supersede or rescind any order or determination previously issued by the Department or any of the terms, conditions or requirements contained in such order or determination.

3. Applications For Permit Renewals, Modifications or Transfers The permittee must submit a separate written application to the Department for permit renewal, modification or transfer of this permit. Such application must include any forms or supplemental information the Department requires. Any renewal, modification or transfer granted by the Department must be in writing. Submission of applications for permit renewal, modification or transfer are to be submitted to:

Regional Permit Administrator
NYSDEC Region 6 Utica Sub-Office
State Office Bldg - 207 Genesee St
Utica, NY13501 -2885

4. Submission of Renewal Application The permittee must submit a renewal application at least 30 days before permit expiration for the following permit authorizations: Freshwater Wetlands, Stream Disturbance.



5. Permit Modifications, Suspensions and Revocations by the Department The Department reserves the right to exercise all available authority to modify, suspend or revoke this permit. The grounds for modification, suspension or revocation include:

- a. materially false or inaccurate statements in the permit application or supporting papers;
- b. failure by the permittee to comply with any terms or conditions of the permit;
- c. exceeding the scope of the project as described in the permit application;
- d. newly discovered material information or a material change in environmental conditions, relevant technology or applicable law or regulations since the issuance of the existing permit;
- e. noncompliance with previously issued permit conditions, orders of the commissioner, any provisions of the Environmental Conservation Law or regulations of the Department related to the permitted activity.

6. Permit Transfer Permits are transferrable unless specifically prohibited by statute, regulation or another permit condition. Applications for permit transfer should be submitted prior to actual transfer of ownership.

NOTIFICATION OF OTHER PERMITTEE OBLIGATIONS

Item A: Permittee Accepts Legal Responsibility and Agrees to Indemnification

The permittee, excepting state or federal agencies, expressly agrees to indemnify and hold harmless the Department of Environmental Conservation of the State of New York, its representatives, employees, and agents ("DEC") for all claims, suits, actions, and damages, to the extent attributable to the permittee's acts or omissions in connection with the permittee's undertaking of activities in connection with, or operation and maintenance of, the facility or facilities authorized by the permit whether in compliance or not in compliance with the terms and conditions of the permit. This indemnification does not extend to any claims, suits, actions, or damages to the extent attributable to DEC's own negligent or intentional acts or omissions, or to any claims, suits, or actions naming the DEC and arising under Article 78 of the New York Civil Practice Laws and Rules or any citizen suit or civil rights provision under federal or state laws.

Item B: Permittee's Contractors to Comply with Permit

The permittee is responsible for informing its independent contractors, employees, agents and assigns of their responsibility to comply with this permit, including all special conditions while acting as the permittee's agent with respect to the permitted activities, and such persons shall be subject to the same sanctions for violations of the Environmental Conservation Law as those prescribed for the permittee.

Item C: Permittee Responsible for Obtaining Other Required Permits

The permittee is responsible for obtaining any other permits, approvals, lands, easements and rights-of-way that may be required to carry out the activities that are authorized by this permit.



Item D: No Right to Trespass or Interfere with Riparian Rights

This permit does not convey to the permittee any right to trespass upon the lands or interfere with the riparian rights of others in order to perform the permitted work nor does it authorize the impairment of any rights, title, or interest in real or personal property held or vested in a person not a party to the permit.



DEPARTMENT OF THE ARMY
US ARMY CORPS OF ENGINEERS, BUFFALO DISTRICT
478 MAIN STREET
BUFFALO, NEW YORK 14202-3278

February 6, 2026

Regulatory Branch

SUBJECT: Department of the Army Permit No. LRB-2025-01172, Nationwide Permit No. 3 - Maintenance as Published in the Federal Register, Volume 86, No. 8 on Jan. 13, 2021 and No. 245 on Dec. 27, 2021.

Jeffrey Dora, Assistant Engineer
Oneida County DPW
5999 Judd Road
Oriskany, NY 13424
Via Email: jdora@oneidacountyny.gov

Dear Mr. Dora:

This pertains to your proposal to discharge fill into waters of the United States in association with the removal of an existing culvert measuring 42 feet long by five (5) feet diameter with a new precast concrete culvert in a new alignment and on a different skew measuring up to 16 feet wide, nine (9) feet high, and 28.25 feet long. The project will also include a discharge of fill associated with the installation of reinforced concrete wingwalls and scout protection aprons. Permanent impacts include the loss of 0.17 acre of wetland from associated grading and filling along the shoulder of the roadway. The project is located in Dix Brook and adjacent wetlands, at Latitude: 43.020420 and Longitude: -75.509110; in the Town of Augusta, Oneida County, New York.

I have evaluated the impacts associated with your proposal and have concluded that they are authorized by the enclosed Nationwide Permit (NWP) provided that the attached conditions are satisfied.

Verification of the applicability of this NWP is valid until March 14, 2026 unless the NWP is modified, suspended, revoked, or the activity complies with any subsequent permit modification. Please note in accordance with 33 CFR part 330.6(b), that if you commence or are under contract to commence an activity in reliance of the permit prior to the date this NWP expires, is suspended or revoked, or is modified such that the activity no longer complies with the terms and conditions, you have twelve months from

the date of permit modification, expiration, or revocation to complete the activity under the present terms and conditions of the permit, unless the permit has been subject to the provisions of discretionary authority.

It is your responsibility to remain informed of changes to the NWP program. A public notice announcing any changes will be issued when they occur and will be available for viewing at our website: [New York Buffalo District Regulatory Website](#). Finally, note that if your activity is not undertaken within the defined period or the project specifications have changed, you must immediately notify this office to determine the need for further approval or reverification.

Your initiation of work as authorized by the enclosed NWP acknowledges your acceptance of the general and special conditions contained therein. This affirmation is limited to the attached NWP and associated Water Quality Certification and does not obviate the need to obtain any other project specific Federal, state, or local authorization. Specifically, you may need to obtain Article 15 (Protection of Water), Article 24 (Freshwater Wetland), and/or Article 34 (Coastal Erosion Management) authorization from the New York State DEC.

In addition to the general conditions and specific regional conditions attached to the NWP, your attention is directed to the following Special Conditions which are also appended at the end of the NWP.

1. The permittee must notify the Regulatory Branch, in writing, at least one day prior to the date the activities authorized in Waters of the United States, including wetlands, are scheduled to begin. Notification shall either be by: 1) e-mail sent to LRB.Regulatory.PermitCompliance@usace.army.mil; or 2) mailed to the following address: Regulatory Branch, U.S. Army Corps of Engineers, Buffalo District, 478 Main Street, Buffalo, New York 14202.
2. As compensatory mitigation for the permanent and unavoidable loss of 0.17 acres of Federal jurisdictional wetlands, the permittee must purchase 0.212 wetland credits from the Ducks Unlimited In-Lieu Fee Mitigation Program Oneida Service Area. Prior to commencing the work associated with this permit authorization, the permittee must supply this office with a copy of the signed Credit Sale Letter verifying acceptance of full payment by the Ducks Unlimited In-Lieu Fee Mitigation Program for the appropriate credits. The documentation must be sent to the attention of LRB.Regulatory.PermitCompliance@usace.army.mil).

Questions pertaining to this matter should be directed to me at 680-867-6196, by writing to the following address: U.S. Army Corps of Engineers Regulatory Branch, Auburn Field Office, 7413 County House Road, Auburn, NY 13021, or by e-mail at: michael.p.uitvlugt@usace.army.mil

Sincerely,

A handwritten signature in black ink, appearing to read 'Michael Uitvlugt', with a stylized, flowing script.

Michael Uitvlugt
Biologist

Enclosures

Cc (w/enclosures)

Daniel Eckert, MJ Engineering, Architecture, Landscape Architecture, and Land Surveying, P.C. (via deckert@mjteam.com)

U.S. Army Corps of Engineers (USACE) CERTIFICATION OF COMPLIANCE WITH DEPARTMENT OF THE ARMY PERMIT For use of this form, see Section 404 of the Clean Water Act, Section 10 of the Rivers and Harbors Act of 1899, and Section 103 of the Marine Protection, Research, and Sanctuaries Act; the proponent agency is CECW-COR.		Form Approved - OMB No. 0710-0003 Expires 2027-10-31
The Agency Disclosure Notice (ADN) The Public reporting burden for this collection of information, 0710-0003, is estimated to average 10 minutes per response, including time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding the burden estimate or burden reduction suggestions to the Department of Defense, Washington Headquarters Services, at whs.mc-alex.esd.mbx.dd-dod-information-collections@mail.mil . Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.		
PURPOSE: This form is used by recipients of U.S. Army Corps of Engineer Regulatory permits to certify compliance with the permit terms and conditions. Your permitted activity is subject to a compliance inspection by a U.S. Army Corps of Engineers representative. If you fail to comply with this permit, you are subject to permit suspension, modification, or revocation.		
Upon completion of the activity authorized by this permit and any mitigation required by the permit, sign this certification and return it to the U.S. Army Corps of Engineers, Buffalo District, Regulatory Office. The certification can be submitted by email at LRB.Regulatory.PermitCompliance@usace.army.mil or by mail at the below address:		
U.S. Army Corps of Engineers Buffalo District Office Street Address: 7413 County House Road City: Auburn State: NY Zip Code: 13021		
COMPLETED BY THE CORPS		
Corps Action Number:	LRB-2025-01172	
Permit Type: General Permit	_____	
General Permit Number and Name (<i>if applicable</i>):	NWP 3 (Maintenance)	
Name of Permittee:	Jeffrey Dora	
Project Name:	Oneida County DPW - Simmons Road over Dix Brook	
Project Location (<i>physical address</i>):	Latitude: 43.020420 and Longitude: -75.509110	
	Augusta, New York	
PERMITTEE'S CERTIFICATION		
Date Work Started: _____ Date Work Completed: _____		
Enclose photographs showing the completed project (<i>if available</i>). I _____ hereby certify that the work authorized by the above referenced permit has been completed in accordance with all of the permit terms and conditions, and that any required compensatory mitigation has been completed in accordance with the permit conditions.		
Name	Date	Signature

Appendix C

Utility Agreements

NEW YORK STATE DEPARTMENT OF TRANSPORTATION REF. #
UTILITY WORK AGREEMENT

Since the construction, reconstruction, or maintenance of the transportation project described below, identified as:

Project Identification No.: 2754.83	F.A. Project No.:
ROW Declaration No.: N/A	Map Nos.:
Parcel Nos.:	County of: Onieda
Contract No.: D036210	

Project Description: Simmons Road Culvert Replacement (CulvertNY)

necessitates the adjustment of utility facilities as hereinafter described, the owner, TDS Telecom, of said facilities herewith agrees with the State of New York acting through the Commissioner of Transportation that this agreement shall apply to the accommodation of these utility facilities. Any adjustment of said facilities will be accomplished under the terms of this agreement, in accordance with the Rules and Regulations Governing the Accommodation of Utilities within the State Highway Right-of-Way, in compliance with the attached Special Note "Coordination with the Utility Schedule, and in accordance with the contract plans, specifications, proposal, amendment(s) or change order(s).

I. Existing Facilities (describe type, size, capacity, location, etc.)

Three cable television/communication lines, one copper, two fiber optic lines attached to Pole #69. Pole #69 is a 25-foot pole located on the southeast side of the existing culvert.

presently located on Town of Augusta Right-of-Way
(indicate State, County, City, Town, Village, Private, etc.)

as shown on the plans for the proposed transportation project are to be adjusted as follows: (describe type, size, capacity, location, etc.)

TDS Telecom is the sole owner of the pole. One (1) pole, #69, will be replaced with a 35-foot pole by TDS Telecom so the communication lines can be raised so they are not in the way of the installation of the proposed precast concrete culvert and wingwalls. TDS Telecom will move the copper and fiber optic lines owned by TDS Telecom to the top of the new 35-foot pole. While moving their lines, TDS will also move Charter's one fiber optic line to the top of the new 35-foot pole. The old pole will be removed by TDS. The new pole #69 will be in the fill limits of the project, so the Contractor will be responsible for protecting the new pole during the entirety of construction. All lines will be shielded during lifting operations to install the proposed precast concrete culvert and wingwalls. All work by TDS Telecom will be completed before **April 4, 2026**.

for an estimated \$ _____

DWK

UTILITY WORK AGREEMENT

REF. #

II. Financial Responsibility (check appropriate boxes):

- ☒ The facilities to be adjusted under the terms of this agreement are subject to Section 52 of the State Highway Law, and the cost of this adjustment is the sole responsibility of the owner.
- ☐ Subdivision 24 of Section 10 of the State Highway Law enables the Commissioner of Transportation to provide at the expense of the State, for adjustment to a municipally owned utility when such work is necessary as a result of State highway work. (Municipal Agreement required.)
- ☐ Subdivision 24-b of Section 10 of the State Highway Law enables the Commissioner of Transportation to participate in the necessary expenses incurred for adjustment of privately, publicly or cooperatively owned facilities, municipal utility facilities, or facilities of a corporation organized pursuant to the State Transportation Corporations Law. (Privately Owned Property Agreement or Reimbursement Agreement required.)
- ☐ Subdivision 27 of Section 10 of the State Highway Law enables the Commissioner of Transportation, upon the request of a municipality, to perform for and at the expense of such municipality specified work to be included within a State-let contract. (Betterment Resolution required.)
- ☐ Subdivision 33 of Section 10 of the State Highway Law enables the Commissioner of Transportation, upon the request of a public utility corporation, to perform for and at the expense of such public utility corporation specified work to be included within a State-let contract.
- ☐ Subdivision 13 of Section 30 of the State Highway Law enables the Commissioner of Transportation to enter into an agreement to reimburse with public funds the owner for necessary expenses incurred as a result of this adjustment, or to replace the facilities in kind.
- ☐ The owner will develop and keep a record of costs in accordance with the New York State Department of Transportation (NYSDOT) Reimbursement Procedures, and when federal funds participate in the cost, the Federal Highway Administration (FHWA) Federal-Aid Policy Guide Part 645, or as indicated below:

III. **Physical Adjustment Method** (check appropriate boxes):

The actual adjustment or design engineering will be performed by the following method (s):

- ☐ Contract let by the Commissioner.
- ☐ Contract let by the Owner, (check applicable statement, i.e., a or b)
 - ☐ a. Best Interests of State.
 - ☐ b. Utility not sufficiently staffed or equipped.
- ☒ By the Owner's forces.

IV. **Betterment, Salvage, and Depreciation Credits Due the Project** (check appropriate boxes):

- ☒ There will be no extension of service life, improved capacity nor any other betterment of the facility (as defined by the NYSDOT Utility Reimbursement Procedures and by FHWA Federal-Aid Policy Guide Part 645) as a result of the adjustments made pursuant to this agreement.
- ☐ There is betterment described as follows:
- ☐ The owner will not claim reimbursement for that betterment portion of the work, but will duly account for it as required by applicable NYSDOT and FHWA procedures.
- ☐ The owner hereby agrees to deposit with the Comptroller of the State of New York the amount of \$_____ to cover the cost of the betterment as described above.
- ☐ The owner agrees to comply with the requirements of the NYSDOT Utility Reimbursement Procedure and FHWA Federal-Aid Policy Guide Part 645 with the respect to salvage and depreciation credits when applicable.

V. **General Covenants**

The owner hereby agrees to accept full title and responsibility for the adjusted facility in writing upon satisfactory completion of the work. Such acceptance will acknowledge the owner's responsibility to maintain the facility in accordance with all applicable codes, standards and regulations, including his obligation, where applicable, to remove any or all of the facility from the highway at the order of the Commissioner of Transportation, all in accordance with the Rules and Regulations Governing the Accommodation of Utilities within the State Highway Right-of-Way. All compensable claims covered by this agreement will be included in one of the following:

- A. Privately Owned Property Agreement executed prior to the performance of the work.
- B. Municipal Agreement executed prior to performance of the work.
- C. Reimbursement Agreement executed prior to performance of the work.
- D. Such other agreement as approved by NYSDOT Office of Legal Affairs.

UTILITY WORK AGREEMENT

REF. #

VI. References

The following documents are herewith incorporated in this agreement by reference (check appropriate boxes)

- ☐ Federal Highway Administration's Federal-Aid Policy Guide Part 645.
- ☒ Contract documents : Contract number: D036210
PIN: 2754.83
Plan sheets No.: GNP-01 to GNP-03
- ☐ Owner's plan sheets _____
- ☐ Owner's estimate sheets form No. _____
- ☐ Resolution dated _____, by _____
- ☐ Granting the State of New York authority to perform the adjustment for the owner.
- ☐ Agreeing to maintain facilities adjusted via State-let contract.
- ☐ Authorizing deposit of funds by the owner.
- ☐ Certification by the owner or his agent that he has the legal authority to enter into this agreement. DUANE KRZYZANOWSKI

Duane Krzyzanowski
(Print/Type Name) Owner or Agent

[Signature]
(Signature)

TDS
Title

9/18/25
Date

Jeffrey Dora

Oneida County Department of Public Works
Assistant Engineer

Date



FILE NAME = F:\m\1559\DN_Final_Design\WJ1559_cph_gnp-03.dgn
DATE/TIME = 9/9/2025 9:37:54 AM
USER = cde-track

DESIGN SUPERVISOR B. COOPER JOB MANAGER D. ECKERT DESIGN K. DIX CHECK M. WAINWRIGHT DRAFTING N. DIEHL CHECK D. ROSE PROJECT MANAGER D. ECKERT

LEGEND

FLOW OF TRAFFIC

ITEM 201.06
TREE CLEARING LIMITS

PERMANENT WETLAND
IMPACT AREA

TEMPORARY WETLAND IMPACT
AREA

GUIDERAIL RUN NO.

DELINEATOR LEGEND

ITEM 646.22
END OF GUIDE RAIL
SNOWPLOW MARKER

ITEM 646.22
START OF GUIDE RAIL
SNOWPLOW MARKER



AFFIX SEAL:
ON:

ALTERED BY:
ON:

NOTES:

1. SEE DWG. NO. GNP-01 FOR NOTES.

AS-BUILT REVISIONS DESCRIPTION OF ALTERATIONS:	REPLACEMENT CULVERT - SIMMONS ROAD OVER DIX BROOK	PIN 2754.83 ALL UTILITIES: QUALITY LEVEL C	BRIDGES	CULVERTS	ALL DIMENSIONS IN ft UNLESS OTHERWISE NOTED	CONTRACT NUMBER D036210	
	TOWN OF AUGUSTA, NY					GENERAL PLAN	DRAWING NO. GNP-03 SHEET NO. 20
	COUNTY: ONEIDA						REGION: 2
IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT, OR LAND SURVEYOR, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE STAMP OF A LICENSED PROFESSIONAL IS ALTERED, THE ALTERING ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT, OR LAND SURVEYOR SHALL STAMP THE DOCUMENT AND INCLUDE THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE, THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.							



NEW YORK STATE DEPARTMENT OF TRANSPORTATION REF. #
UTILITY WORK AGREEMENT

Since the construction, reconstruction, or maintenance of the transportation project described below, identified as:

Project Identification No.: 2754.83	F.A. Project No.:
ROW Declaration No.: N/A	Map Nos.:
Parcel Nos.:	County of: Onieda
Contract No.: D036210	

Project Description: Simmons Road Culvert Replacement (CulvertNY)

necessitates the adjustment of utility facilities as hereinafter described, the owner, TDS Telecom, of said facilities herewith agrees with the State of New York acting through the Commissioner of Transportation that this agreement shall apply to the accommodation of these utility facilities. Any adjustment of said facilities will be accomplished under the terms of this agreement, in accordance with the Rules and Regulations Governing the Accommodation of Utilities within the State Highway Right-of-Way, in compliance with the attached Special Note "Coordination with the Utility Schedule, and in accordance with the contract plans, specifications, proposal, amendment(s) or change order(s).

I. Existing Facilities (describe type, size, capacity, location, etc.)

Three cable television/communication lines, one copper, two fiber optic lines attached to Pole #69. Pole #69 is a 25-foot pole located on the southeast side of the existing culvert.

presently located on Town of Augusta Right-of-Way
(indicate State, County, City, Town, Village, Private, etc.)

as shown on the plans for the proposed transportation project are to be adjusted as follows: (describe type, size, capacity, location, etc.)

TDS Telecom is the sole owner of the pole. One (1) pole, #69, will be replaced with a 35-foot pole by TDS Telecom so the communication lines can be raised so they are not in the way of the installation of the proposed precast concrete culvert and wingwalls. TDS Telecom will move the copper and fiber optic lines owned by TDS Telecom to the top of the new 35-foot pole. While moving their lines, TDS will also move Charter's one fiber optic line to the top of the new 35-foot pole. The old pole will be removed by TDS. The new pole #69 will be in the fill limits of the project, so the Contractor will be responsible for protecting the new pole during the entirety of construction. All lines will be shielded during lifting operations to install the proposed precast concrete culvert and wingwalls. All work by TDS Telecom will be completed before **April 4, 2026**.

for an estimated \$_____

UTILITY WORK AGREEMENT

REF. #

II. Financial Responsibility (check appropriate boxes):

- ☒ The facilities to be adjusted under the terms of this agreement are subject to Section 52 of the State Highway Law, and the cost of this adjustment is the sole responsibility of the owner.
- ☐ Subdivision 24 of Section 10 of the State Highway Law enables the Commissioner of Transportation to provide at the expense of the State, for adjustment to a municipally owned utility when such work is necessary as a result of State highway work. (Municipal Agreement required.)
- ☐ Subdivision 24-b of Section 10 of the State Highway Law enables the Commissioner of Transportation to participate in the necessary expenses incurred for adjustment of privately, publicly or cooperatively owned facilities, municipal utility facilities, or facilities of a corporation organized pursuant to the State Transportation Corporations Law. (Privately Owned Property Agreement or Reimbursement Agreement required.)
- ☐ Subdivision 27 of Section 10 of the State Highway Law enables the Commissioner of Transportation, upon the request of a municipality, to perform for and at the expense of such municipality specified work to be included within a State-let contract. (Betterment Resolution required.)
- ☐ Subdivision 33 of Section 10 of the State Highway Law enables the Commissioner of Transportation, upon the request of a public utility corporation, to perform for and at the expense of such public utility corporation specified work to be included within a State-let contract.
- ☐ Subdivision 13 of Section 30 of the State Highway Law enables the Commissioner of Transportation to enter into an agreement to reimburse with public funds the owner for necessary expenses incurred as a result of this adjustment, or to replace the facilities in kind.
- ☐ The owner will develop and keep a record of costs in accordance with the New York State Department of Transportation (NYSDOT) Reimbursement Procedures, and when federal funds participate in the cost, the Federal Highway Administration (FHWA) Federal-Aid Policy Guide Part 645, or as indicated below:

III. Physical Adjustment Method (check appropriate boxes):

The actual adjustment or design engineering will be performed by the following method (s):

- ☐ Contract let by the Commissioner.
- ☐ Contract let by the Owner, (check applicable statement, i.e., a or b)
 - ☐ a. Best Interests of State.
 - ☐ b. Utility not sufficiently staffed or equipped.
- ☒ By the Owner's forces.

IV. Betterment, Salvage, and Depreciation Credits Due the Project (check appropriate boxes):

- ☒ There will be no extension of service life, improved capacity nor any other betterment of the facility (as defined by the NYSDOT Utility Reimbursement Procedures and by FHWA Federal-Aid Policy Guide Part 645) as a result of the adjustments made pursuant to this agreement.
- ☐ There is betterment described as follows:
- ☐ The owner will not claim reimbursement for that betterment portion of the work, but will duly account for it as required by applicable NYSDOT and FHWA procedures.
- ☐ The owner hereby agrees to deposit with the Comptroller of the State of New York the amount of \$_____ to cover the cost of the betterment as described above.
- ☐ The owner agrees to comply with the requirements of the NYSDOT Utility Reimbursement Procedure and FHWA Federal-Aid Policy Guide Part 645 with the respect to salvage and depreciation credits when applicable.

V. General Covenants

The owner hereby agrees to accept full title and responsibility for the adjusted facility in writing upon satisfactory completion of the work. Such acceptance will acknowledge the owner's responsibility to maintain the facility in accordance with all applicable codes, standards and regulations, including his obligation, where applicable, to remove any or all of the facility from the highway at the order of the Commissioner of Transportation, all in accordance with the Rules and Regulations Governing the Accommodation of Utilities within the State Highway Right-of-Way. All compensable claims covered by this agreement will be included in one of the following:

- A. Privately Owned Property Agreement executed prior to the performance of the work.
- B. Municipal Agreement executed prior to performance of the work.
- C. Reimbursement Agreement executed prior to performance of the work.
- D. Such other agreement as approved by NYSDOT Office of Legal Affairs.

VI. References

The following documents are herewith incorporated in this agreement by reference (check appropriate boxes)

- ☐ Federal Highway Administration's Federal-Aid Policy Guide Part 645.
- ☒ Contract documents : Contract number: D036210
PIN: 2754.83
Plan sheets No.: GNP-01 to GNP-03
- ☐ Owner's plan sheets _____
- ☐ Owner's estimate sheets form No. _____
- ☐ Resolution dated _____, by _____
- ☐ Granting the State of New York authority to perform the adjustment for the owner.
- ☐ Agreeing to maintain facilities adjusted via State-let contract.
- ☐ Authorizing deposit of funds by the owner.
- ☐ Certification by the owner or his agent that he has the legal authority to enter into this agreement.

DUSTIN Anderson [Signature] CONSTRUCTION COORDINATOR 10/24/25
(Print/Type Name) Owner or Agent (Signature) Title Date

Jeffrey Dora Oneida County Department of Public Works
Assistant Engineer Date

ALL WORK IS TO BE DONE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE NEW YORK STATE ENGINEERING AND SURVEYING LAW AND THE NEW YORK STATE ENGINEERING AND SURVEYING BOARD'S REGULATIONS.


DESIGN SUPERVISOR: B. COOPER, PROJECT MANAGER: B. COOPER, CHECKED: M. KAMINSKI, DRAWN BY: M. KAMINSKI, DATE: 10/10/2018, SCALE: AS SHOWN, PROJECT NO.: 18-001, SHEET NO.: 18

LEGEND

- FLOW OF TRAFFIC
- ITEM 204.06 TREE CLEARING LIMITS
- PERMANENT WETLAND IMPACT AREA
- TEMPORARY WETLAND IMPACT AREA
- ROWWAY NUMBER
- ROWWAY, RUN NO.


DELINEATOR LEGEND

- ITEM 646.32 END OF GRADE RAIL, SHOWN ON WHEELER
- ITEM 646.32 START OF GRADE RAIL, SHOWN ON WHEELER



CURVE S1	
Δ	1°35'00.56" L
R	18900.0 FT
L	223.7 FT
T	112.0 FT
PC	STA. S 11+32.86
PT	STA. S 13+56.54

- NOTES:**
- SEE DWS. NO. TYP-01 FOR ROADWAY TYPICAL SECTIONS.
 - SEE DWS. NO. ST-01 FOR ROADWAY PLAN AND ELEVATION.
 - SEE DWS. NO. PRO-01 FOR ROADWAY PROFILE AND BANKING DIAGRAM.
 - SEE DWS. NOS. ECP-01 TO ECP-03 FOR GRADING AND EROSION AND SEDIMENT CONTROL PLANS.
 - SEE DWS. NO. M51-01 FOR MISCELLANEOUS TABLES.





AS-BUILT REVISIONS DESCRIPTION OF ALTERATIONS:	REPLACEMENT CULVERT - SIMMONDS ROAD OVER BOX CREEK TOWN OF AUGUSTA, NY	PRJ 2754-01 ALL UTILITIES QUALITY LEVEL	BRIDGES	CL. NOTES	ALL DIMENSIONS IN FT UNLESS OTHERWISE NOTED	CONTRACT NUMBER 18136110
	COUNTY: BROOKS	SECTION: 2			GENERAL PLAN	DRAWING NO. GMP-01 SHEET NO. 18

IT IS A VIOLATION OF LAW FOR ANY PERSON UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A REGISTERED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT, OR LAND SURVEYOR TO ALTER AN ITEM IN ANY WAY, IF AN ITEM BEARING THE STAMP OF A LICENSED PROFESSIONAL IS ALTERED. THE ALTERING ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT, OR LAND SURVEYOR SHALL STAMP THE DOCUMENT AND INCLUDE THE NOTATION "ALTERED BY:" FOLLOWED BY THEIR SIGNATURE, THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.

(M)





1. SEE DOC. NO. QMP-01 FOR NOTES.

AS-BUILT REVISIONS DESCRIPTION OF ALTERATIONS	REPLACEMENT CULVERT - 5000x50 ROAD OVER DECK BRIDGE	PM 2754.3	BRIDGES	CULVERTS	ALL DIMENSIONS IN FT UNLESS OTHERWISE NOTED	CONTRACT NUMBER 0036210	
	TOWN OF ALBANY, NY	ALL REVISIONS QUALITY LEVEL C				GENERAL PLAN	DRAWING NO. CWP-03 SHEET NO. 20
	COUNTY OF ONEIDA	SECTION 2					
IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT, OR LAND SURVEYOR, TO ALTER AN ITEM BY ANY MEANS, OR HAVE ANY ITEM BEING THE WORK OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT, LANDSCAPE ARCHITECT, OR LAND SURVEYOR, BEING USED IN ANY MANNER OR FOR ANY PURPOSES OTHER THAN THAT SPECIFICALLY INTENDED BY THE ISSUING AGENCY.							